



Environmental and Social Impact Assessment (ESIA) Addendum

Proposed Dominica Geothermal Development

February 2021

Project No.: 0531607

February 2021

Environmental and Social Impact Assessment (ESIA) Addendum

Proposed Dominica Geothermal Development



Ricardo Calvo
Partner



Herbert Pirela
Project Manager

ERM Washington
1776 I St NW
Washington DC 20006
Tel: 1-202-466-9090

CONTENTS

1.	INTRODUCTION	1
1.1	Project Proponents	1
1.2	Purpose and Need for the Project.....	1
1.3	Objectives and Scope.....	1
2.	SUPPLEMENTAL POLICY, LEGAL, AND ADMINISTRATIVE FRAMEWORK.....	2
2.1	International Standards.....	2
2.1.1	Inter-American Development Bank (IDB).....	2
2.1.2	Caribbean Development Bank (CDB).....	4
2.1.3	International Finance Corporation (IFC).....	6
2.1.4	Agence Française de Développement (AFD).....	8
3.	PROJECT DESCRIPTION MODIFICATIONS SINCE THE 2018 ESIA	10
3.1	Project Overview.....	10
3.2	Project Location.....	11
3.3	Process Overview.....	12
3.4	Project Components.....	13
3.5	Production and Injection Wells.....	16
3.5.1	Well Pads.....	16
3.5.2	Well Drilling.....	18
3.5.3	Existing Site Conditions.....	23
3.6	Steamfield.....	23
3.7	Power Plant.....	24
3.7.1	Geothermal Fluid Cycle.....	24
3.7.2	The Organic Rankine Cycle.....	24
3.7.3	Design Parameters.....	25
3.8	Pipelines.....	27
3.9	Brine Ponds.....	28
3.10	Transmission Lines.....	28
3.11	Additional Facilities.....	28
3.11.1	Additional Structures.....	28
3.11.2	Hazardous Material Storage.....	28
3.11.3	Site Security.....	29
3.11.4	Site Surface Water Drainage Features.....	29
3.11.5	Water and Utilities.....	29
3.12	Project Phases and Schedule.....	31
3.12.1	Construction.....	31
3.12.2	Operation and Maintenance.....	35
3.12.3	Decommissioning.....	36
3.13	Alternative Analysis.....	36
4.	IMPACT ASSESSMENT METHODOLOGY.....	40
4.1	General Methodology.....	40
5.	BIOLOGICAL RESOURCES UPDATE.....	44
5.1	Biological Setting.....	44
5.1.1	Biotic Area of Influence.....	44
5.1.2	Natural Habitat and Modified Habitat Assessment.....	45
5.1.3	Protected Areas.....	47

5.1.4	Ecosystem Services.....	48
5.2	Critical Habitat Assessment Screening.....	49
5.2.1	Mountain Chicken, <i>Leptodactylus fallax</i> - IUCN CR.....	49
5.2.2	Black-capped Petrel, <i>Pterodroma hasitata</i> - IUCN EN.....	50
5.2.3	Dominican Myotis, <i>Myotis dominicensis</i> - IUCN VU.....	51
5.2.4	Conclusions.....	51
5.3	Morne Trois World Heritage Site.....	52
5.4	Summary Impacts on Biodiversity.....	54
5.4.1	Mitigation Measures and Monitoring.....	56
6.	SOCIOECONOMIC RESOURCES UPDATE.....	62
6.1	Socioeconomic Baseline.....	62
6.1.1	Migration.....	62
6.1.2	Gender.....	65
6.1.3	Human Rights.....	66
6.1.4	Emergency Services and Security.....	67
6.1.5	COVID-19.....	68
6.1.6	Land Use and Acquisition.....	69
6.2	Impacts and Mitigation.....	70
6.2.1	Gender.....	70
6.2.2	Worker Influx.....	71
6.2.3	Land Acquisition, Resettlement and Livelihood Restoration.....	72
6.2.4	Impacts Summary.....	73
7.	CUMULATIVE IMPACT ASSESSMENT.....	76
7.1	Key Terminology.....	76
7.2	Approach.....	76
7.3	Limitations.....	77
7.4	Determination of Spatial and Temporal Boundaries.....	77
7.5	Other Projects.....	78
7.6	External Drivers.....	79
7.7	VEC Selection and Description.....	80
7.7.1	Selection of VECs.....	80
7.7.2	Description of VEC Conditions.....	81
7.8	Assessment of Cumulative Impacts.....	81
7.9	Cumulative Impacts Management Framework.....	87
7.9.1	Project Level.....	87
7.9.2	Regional Level.....	87
8.	CONCLUSION.....	88
9.	REFERENCES.....	89

APPENDIX A ENVIRONMENTAL AND SOCIAL MANAGEMENT PLAN (ESMPs)

APPENDIX B RESETTLEMENT ACTION PLAN (RAP)

List of Tables

Table 2-1: Triggered Inter-American Development Bank Safeguards and Policies.....	2
Table 2-2 CDB Policies.....	5

Table 2-3: International Finance Corporation Performance Standards	7
Table 3-1: Physical Parameters of the Existing Production Wells	16
Table 3-2: Design Standards	25
Table 3-3: Proposed Water Take Limits	29
Table 3-4: Estimated Land Requirements by Project Component	32
Table 3-5: Minimum Required Equipment for Construction	33
Table 3-6: Minimum Required Workforce and their Qualifications	34
Table 4-1: Impact Designation Definitions	40
Table 4-2: Evaluation of Significance of Impacts	42
Table 5-1: Natural and Modified Habitat types within the BAOI.....	46
Table 5-2: Protected Areas on Dominica	48
Table 5-3. Impacts in Surface Area (m ²) to Vegetation Types by Project Component.....	55
Table 5-4: Impacts and Mitigation Measures for Project Modifications and Updates.....	57
Table 6-1 Migrant Stock by Origin (2013)	64
Table 6-2 Migrant Stock by Destination (2013).....	64
Table 6-3: Impacts and Mitigation Measures for Project Modifications and Updates.....	74
Table 7-1: Selection of VECs.....	81
Table 7-2: Summary of Cumulative Impact Assessment.....	83

List of Figures

Figure 3-1: Project Location	11
Figure 3-2: Project Component Location	12
Figure 3-3: Typical Binary Cycle	13
Figure 3-4: Proposed Preliminary Plant Layout	15
Figure 3-5: Panoramic View of Existing Well Pad from the East	17
Figure 3-6: Existing Pad Layout	17
Figure 3-7: Schematics of a Typical Drill Rig	18
Figure 3-8: Schematic of Proposed Deviated Wells	20
Figure 3-9: Typical Steamfield Arrangement	23
Figure 3-10: Approximate Location of the Reinjection Pipeline	27
Figure 3-11: Proposed Water Source Location	30
Figure 3-12: Power Plant Location Alternatives.....	37
Figure 3-13: Original Reinjection Wells and Pipeline Alternatives.....	38
Figure 3-14: Latest Reinjection Well Pads and Pipeline Alternatives.....	39
Figure 4-1: Impact Prediction and Evaluation Process.....	40
Figure 5-1: Biotic Area of Influence Based on Potential Noise Impacts	45
Figure 5-2: Land Cover Types Present in the BAOI	46
Figure 5-3: Natural and Modified Habitat in the BAOI	47
Figure 5-4: Map of WHS boundary for Morne Trois Pitons National Park.....	53
Figure 5-5: Project Components in Relation to the MTPNP WHS and 200 m Buffer	54
Figure 6-1 Migration Rate Dominica (1985-2015)	62
Figure 6-2 Total Population by Age, Sex and Origin (2013)	63
Figure 6-3 Migrant Stock by Age and Sex (2013).....	63
Figure 6-4 Number of Women Legislators (Percentage)	66
Figure 6-5 Police Stations	67
Figure 6-6 Fire Stations.....	68
Figure 6-7 Properties Neighboring Preferred Reinjection Line	69
Figure 7-1: Comparing ESIA and CIA.....	77

Figure 7-2: Summary of the Cumulative Impact Assessment Methodology..... 77

Acronyms and Abbreviations

Name	Description
°C	Celsius
AFD	Agence Française de Développement
amsl	above mean sea level
AOO	Area of occupancy
RAP	Resettlement Action Plan
BAOI	Biotic area of influence
BHA	Bottomhole assembly
BMCs	Borrowing Member Countries
BMCs	Borrowing Member Countries
BOP	Blowout preventer
CDB	Caribbean Development Bank
CGA	Country Gender Assessment
CH	Critical habitat
CIA	Cumulative Impact Assessment
CO ₂	Carbon Dioxide
CR	Critically Endangered
DAIC	Dominica Association of Industry and Commerce
dBA	A-weighted decibels
DC	Drill collar
DGDC	Dominica Geothermal Development Company
DOMLEC	Dominica Electricity Services Limited
DOWASCO	Dominica's Water and Sewerage Company Ltd
E&S	Environmental and Social
EHS	Environmental, Health, and Safety
EN	Endangered
EOO	Extent of occurrence
EPC	Engineering, Procurement, and Construction
ERM	Environmental Resources Management
ESMP	Environmental and Social Management Plan
ESRP	Environmental and Social Review Procedures
FPIC	Free, Prior, and Informed Consent
GoCD	Commonwealth of Dominica
H ₂ S	Hydrogen Sulfide
HDI	Human development index
IDB	Inter-American Development Bank
IFC	International Finance Corporation
ILO	International Labor Organization
IUCN	International Union for Conservation of Nature
kha	kilohectare
km	Kilometer
kV	Kilovolt
LC	Least Concern
m	Meter
m/s	Meter per second
m ²	Square meter
m ³	Cubic meter

m ³ /h	Cubic meter per hour
mg/L	milligram per liter
MTPNP	Morne Trois Pitons National Park
MW	megawatt
NT	Near threatened
OECS	Organization of Eastern Caribbean States
ORC	Organic Rankine Cycle
POOH	Pull out of the hole
PPA	Power Purchase Agreement
PS	Performance Standard
RoW	Right-of-Way
SGS	Steam Gathering System
TBC	The Biodiversity Consultancy
TD	Total depth
UNDESA	United Nations Department of Economic and Social Affairs
UNDP	United Nations Development Program
UNICEF	United Nations Children's Fund
UNPRI	UN Principles for Responsible Investment
VECs	Valued Environmental Components
VU	Vulnerable
WBG	World Bank Group
WBM	Water base muds
WHS	World Heritage Site
WOC	Waiting on cement

1. INTRODUCTION

The Dominica Geothermal Development Company (DGDC), Ltd., is a private “special purpose” company with its own board, created in 2017. DGDC is 100% owned by the Government of the Commonwealth of Dominica (GoCD) and equity is transferred from GoCD to the DGDC under subsidiary agreement. DGDC, with financial support from various partners, is developing a 10-megawatt (MW) binary geothermal power plant and related facilities on the Island of Dominica. The Project is located on the southwestern periphery of the village of Laudat, northeast from Wotten Waven and Trafalgar villages.

The Island of Dominica is located near the center of an archipelago of islands known as the Lesser Antilles, between the neighboring French territories of Martinique and Guadeloupe. The proposed Project would use local geothermal resources to provide a sustainable source of power that would reduce reliance on petroleum markets for electric power generation in Dominica, and would decrease emissions of criteria pollutants and greenhouse gases associated with global climate change.

In 2018, Jacobs New Zealand Limited (Jacobs) prepared an Environmental and Social Impact Assessment (ESIA) for the construction and operation of the Dominica Geothermal Project. The Project included the construction and operation of geothermal wells, reinjection systems and a geothermal power plant with a capacity of 7 MW and connection to the Dominica electrical grid and associated infrastructure. Following an unsuccessful procurement in November 2019, carried out by GoCD using World Bank financing and procurements rules, there has been subsequent design modifications (e.g., increase in capacity from 7 MW to 10 MW, the addition of a production well pad and well, and the relocation of the reinjection well pad and well; see Section 3.0).

While the Jacobs ESIA was reviewed and approved by the World Bank in 2018, due to the design modifications and advances in the preparation for the construction, an additional ESIA was prepared in 2020 by ECLIPSE, Inc. that assessed the impacts of the relocation of the reinjection well, its pad, and reinjection pipeline.

This ESIA Addendum, prepared by Environmental Resources Management (ERM), reviews and combines the existing two ESIA's, provides punctual updates of gaps identified in the existing ESIA's and mitigation/ management plans, assesses the impacts of any additional Project modifications which have occurred recently (described in Section 3 of this document), and provides mitigation and management of those additional impacts (such as for the addition of a back-up production pad and well).

1.1 Project Proponents

In 2020, the DGDC, with financial support from various partners is planning to construct a 10 MW Domestic Power plant. Dominica Electricity Services Limited (DOMLEC) is Dominica's privately owned electricity generation and distribution company, currently the sole generator and distributor (apart from some small scale solar installations) on the island. DGDC will sell geothermal energy to DOMLEC, who will distribute it to residents on the national grid.

1.2 Purpose and Need for the Project

The proposed geothermal development Project would provide baseload renewable electricity to the island of Dominica and reduce the reliance on diesel fuel for power generation.

1.3 Objectives and Scope

The objective of this Addendum to the ESIA is to complement the existing ESIA studies conducted by Jacobs and ECLIPSE to provide punctual updates of gaps identified and further assess the Project's

environmental and social impacts based on updated project design details, including an updated Environmental and Social Management Plan (ESMP) compliant to the relevant National regulations, International Finance Corporation (IFC) Performance Standards, Inter-American Development Bank (IDB) safeguard policies, Green Climate Fund requirements, Caribbean Development Bank (CDB), Agence Française de Développement (AFD), and the applicable IFC Environmental, Health and Safety Guidelines.

Specific objectives of this ESIA Addendum include:

- Supplement the policy, legal, and administrative framework to incorporate IFC, IDB, GCF, CDB, and AFD requirements;
- Update the Project Description and site alternative selection analysis with modifications since the 2018 and 2020 ESIA's;
- Update the Biological Resources and the Socioeconomic Resources assessments;
- Identify measures to minimize negative impacts and enhance positive impacts of the Project, following the mitigation hierarchy; and
- Present updated Environmental and Social Management Plans for the Project.

2. SUPPLEMENTAL POLICY, LEGAL, AND ADMINISTRATIVE FRAMEWORK

2.1 International Standards

2.1.1 Inter-American Development Bank (IDB)

The IDB has established its own policies and safeguards to ensure that projects financed by the IDB group are sustainable (see Table 2-1 below). These environmental and social policies are guided by international best practices, and are relatively consistent with widely used IFC guidelines regarding environmental, health, and social management.

Table 2-1: Triggered Inter-American Development Bank Safeguards and Policies

IDB Policies	Policy Description
<p>OP-703 – Environmental and Safeguards Compliance Policy</p>	<p>The Policy has three specific objectives:</p> <ul style="list-style-type: none"> (i) To enhance long-term development benefits by integrating environmental sustainability outcomes in all Bank operations and activities and strengthening environmental management capacities in its borrowing member countries. (ii) To ensure that all Bank operations and activities are environmentally sustainable (iii) To foster corporate environmental responsibility within the Bank. <p>The Policy has two sets of directives, as follows:</p> <ul style="list-style-type: none"> • <i>Environmental Mainstreaming (Directives A.1 through A.7)</i>, which refer to the concept of mainstreaming environmental issues and upstreaming them early on during the project cycle. • <i>Safeguarding Directives (Directives B.1 through B.16)</i> – allow the Bank to adopt a more effective and efficient risk management framework. <p>Safeguards are applied throughout the project cycle to ensure the environmental sustainability of all Bank-financed operations. The Environmental Safeguards Directives are: B.1 Bank Policies; B.2 Country Laws and Regulations; B.3 Screening and Classification; B.4 Other Risk Factors; B.5 Environmental Assessment Requirements; B.6 Consultations; B.7 Supervision and Compliance; B.8 Transboundary Impacts; B.9</p>

IDB Policies	Policy Description
	Natural Habitats and Cultural Sites; B.10 Hazardous Materials; B.11 Pollution Prevention and Abatement; B.12 Project Under Construction; B.13 Noninvestment Lending and Flexible Lending Instruments; B.14 Multiple Phase and Repeat Loans; B.15 Co-financing Operations; B.16 In-country Systems; B.17 Procurement.
OP-761 Gender Equality in Development	This Policy integrates a gender perspective that seeks equal conditions and opportunities for women and men to reach their social, economic, political, and cultural potential by providing specific mechanisms for ensuring the effective implementation of the Policy and the evaluation of its results.
OP-704 – Natural Disaster Risk Management	The Policy has two interrelated specific objectives: i) To strengthen the Bank’s effectiveness in supporting its borrowers to systematically manage risks related to natural hazards by identifying these risks, reducing vulnerability, and preventing and mitigating related disasters before they occur. ii) To facilitate rapid and appropriate assistance by the Bank to its borrowing member countries in response to disasters in an effort to efficiently revitalize their development efforts and avoid rebuilding vulnerability.
OP-102 Access to Information Policy	This Policy is based on the principle that information concerning the Bank and its activities must be made available to the public in the absence of a compelling reason for confidentiality. Information provided to the public must be made available in a form and at a time that enhances the transparency and therefore the quality of Bank activities.

Source: IDB, Operational Policies.

Regarding environmental and social issues, the Project triggers the following directives of the Environment Safeguard Policy (OP-703):

- **B.1, Bank Policies:** The Bank will only finance operations and activities that comply with the directives of this policy and are consistent with the relevant provisions of other Bank policies. This policy ensured the borrower/executing agency has legislation in place that promotes environmental management, training, and environmental governance, and promotes conservation and sustainable use of natural resources.
- **B.2, Country Laws and Regulations:** Project activities must comply with all Dominica laws and regulations, including the preparation of an ESIA.
- **B.3, Screening and Classification:** The Project will have impacts on the environment and the community. The Project is classified as Category “A”. In accordance with OP-703, Category A projects are “any operation that is likely to cause significant negative environmental and associated social impacts, or have profound implications affecting natural resources,” and require a project specific ESIA as well as an ESMP.
- **B.4, Other Risk Factors:** The Project’s executing agency needs to comply with the ESIA and ESMP requirements. Therefore, the executing agency and relevant third parties will be required to develop appropriate measures for managing the identified risks, and such risks include economic displacement.
- **B.5, Environmental Assessment Requirements:** This Addendum to the ESIA addresses the IDB’s requirement for environmental assessment for the Project.

- *B.6, Consultations:* An initial public consultation was conducted on 8 November 2017 to discuss possible alternatives and receive initial stakeholder feedback. Consistent with the IDB's Access to Information Policy (OP-102) and this policy (OP-703), this Addendum to the ESIA will be made available to the public.
- *B.7, Supervision and Compliance:* A monitoring plan will be implemented for the Project as part of the Project's ESMP.
- *B.9, Natural Habitats and Cultural Sites:* The Project is located near in the Roseau Valley, on the Island of Dominica and there are no known prehistoric archaeological sites and no currently listed historic sites or landmarks in the Project area. This directive requires the development of mitigation and monitoring measures to mitigate the potential impacts identified in this ESIA and the ESMP.
- *B.10, Hazardous Materials:* The Project will require the use of hazardous materials and will result in the production of hazardous waste. Hazardous material minimization, handling, storage, transportation and disposal is addressed in the Project's ESMP.
- *B.11, Pollution Prevention and Abatement:* Project activities have a risk of pollution, specifically during the construction phase. Pollution prevention is addressed in the Project's ESMP.
- *B17. Contractor clause for implementation of ESMP.*

Additionally, the Project triggers the IDB's Access to Information Policy (OP-102), the Gender Equality in Development Policy (OP-761), and the Disaster Risk Management Policy (OP-704). When it comes to financing projects, it is the Bank's intent to be as clear and transparent as possible and, through clear stakeholder communication, to improve the quality of its operations.

2.1.2 Caribbean Development Bank (CDB)

One of the most relevant CDB policies for the purpose of this report and the Project itself is the Environmental and Social Review Procedures (ESRP) from December 1, 2014.

The ESRP outlines how CDB within its mandate and operations ensure that environment and social risks are managed. The ESRP includes eight environment and social performance standards that reflect the principles, core policies, standards and best practice approaches adopted and used in the treatment of sensitive environmental and social issues by the multilateral financial and development community. The objectives of the performance requirements are to:

- Optimize decision making with respect to environment and social impacts, and risks to anticipate, avoid, mitigate, and/or compensate for adverse project impacts on the environment and affected people and communities;
- Assist Borrowing Member Countries (BMCs) to build capacity and strengthen their institutions and governance systems to effectively manage environmental and social risks; and
- Provide staff, BMCs and other development partners with a clear understanding of the CDB's requirements, and procedures, accountabilities for managing environment and social risks in its operations.

The environmental and social performance requirements include objectives, principles and scope related to the policies shown in Table 2-2.

Table 2-2 CDB Policies

CDB Policies	Policy Objectives
Pollution Prevention, Control and Management	Identify and address how pollution prevention, control and management requirements for the project will be appropriately managed, (given the nature and scale of the project geographic location and ambient environmental conditions) and taking into account financially feasible and cost effective control methods, throughout the project cycle using a discrete environment and social management system or a project specific ESMP.
Toxic and Hazardous Substances Control and Management	CDB financed projects should avoid and/or minimize risks and impacts to human health and safety, and to the environment, from the procurement, production and use, and disposal of toxic and hazardous materials and substances, including pesticides and Persistent Organic Pollutants
Cultural Property and Heritage	CDB financed operations will be guided by applicable international conventions ratified by the Borrower as well as by national legislation and regulations to avoid adverse impacts on cultural resources. The application of this requirement is designed to promote awareness and appreciation, encourage their protection, conservation and sound management and applies whether the cultural heritage has been legally protected, internationally recognized or previously disturbed.
Natural Habitats and Biodiversity Conservation	Identify and make every use of opportunities to conserve and sustainably use biodiversity natural habitats, and as priority, maintain the benefits of priority ecosystem services and in so doing reflect the objectives of the Convention on Biological Diversity. CDB will not finance or support operations that significantly convert or degrade impacts on critical, natural, protected habitats, and will instead promote the conservation, protection and management of natural resources.
Directly Affected Communities	To avoid or minimize adverse impacts on communities directly affected by development projects and ensure that they benefit from projects that affect them.
Vulnerable Groups	To avoid adverse impacts upon groups that may be disadvantaged in the development process by virtue of their age (children and the elderly), ethnicity, religion, culture, gender, physical and mental ability or way of life. In development projects financed by the Bank, likely to have significant impacts on vulnerable groups, especially those below the poverty line, the landless, the elderly, women and children, the disabled, and Indigenous Peoples (IP). Particular attention should be given to these groups to ensure that they are not disadvantaged and at a minimum restore their livelihoods in real terms relative to pre-project levels; and or enhance and improve their standards of living.
Land Acquisition and Involuntary Resettlement	In recognition of the long term adverse consequences involuntary displacement or badly planned resettlement initiatives can have on people, it is required that CDB-financed project activities ensure that where unavoidable, individuals affected by land acquisition or involuntary resettlement, (including ‘squatters’) are consulted, fairly compensated for the loss of land and other assets taken for development

	<p>purposes; and are able to restore their incomes and standards of living or improve them. The displacement (relocation, loss of residential land, or loss of shelter) and economic displacement (loss of land, assets, access to assets, income sources, or means of livelihoods) as a result of (i) involuntary acquisition of land, or (ii) involuntary restrictions on land use or on access to legally designated parks and protected areas, whether losses and restrictions are full or partial, permanent or temporary. Given the great diversity in the scale (from one person to more than 20 households) of involuntary resettlement issues encountered in CDB's BMCs the applicability of this performance requirement will be worked out with the Borrower on a "case by case" basis and applies to both the public and private sector. This performance requirement does not apply to victims of natural disasters or to resettlement resulting from voluntary land transactions</p>
<p>Community, Worker Health and Safety</p>	<p>The Borrower will provide workers with a safe and healthy environment, ensuring that risks (biological, physical, chemical or radiological) associated or inherent to the particular sector are: identified, avoided, mitigated or controlled. In addition, steps will be taken to prevent accidents, injury and disease arising from work that present potential hazard to workers through the provision of personal protective equipment, controls to avoid or minimize risks, as well as having in place appropriate emergency response plans and procedures. The Borrower will also assess and identify potential risks to safety of affected communities during all phases of the project cycle to both natural and accidental hazards. The approach will be based on favoring prevention or avoidance of risks and impacts to minimization or reduction.</p>

CDB will not finance projects that do not meet its environment and social performance requirements as defined in the ESRP. Borrowers are required to monitor and report to the Bank on their compliance with the ESRP requirements. The Bank recognizes the value a well-informed and engaged public can bring to the development process and contribute to the attainment of the BMC's sustainable development objectives. CDB is therefore committed to the principle of corporate transparency, accountability and stakeholder engagement, and BMCs are encouraged to adopt and promote these principles.

The ESRP requires that Borrowers initiate early engagement, participation, consultations and disclosure of information to parties likely to be affected by significant negative impacts from the investments projects it finances (CDB, Environmental and Social Review Procedures, 2014).

2.1.3 International Finance Corporation (IFC)

Although the Project is committed to complying with the IDB Safeguards and CDB policies and procedures, the IDB itself recognizes a series of additional norms and standards that, if implemented, could help minimize risks associated with the development of this Project. These are described below.

The IFC is a division of the World Bank Group that lends to private investors. The IFC released a Sustainability Policy and set of Performance Standards (PS) on Social and Environmental Sustainability in January 2012. These standards stipulate that the Project shall meet certain requirements throughout the life cycle of an investment by IFC or other relevant financial institution or commercial banks, which are signatory to the Equator Principles (EP, 2006).

These PS and guidelines provide ways and means to identify impacts and affected stakeholders and lays down processes for management and mitigation of adverse impacts, see the Table 2-3 below.

Table 2-3: International Finance Corporation Performance Standards

Performance Standard	Description	Purpose
PS 1: Assessment and Management of Environmental and Social Risks and Impacts	Underscores the importance of managing environmental and social performance throughout the life of a project (any business activity that is subject to assessment and management).	<ul style="list-style-type: none"> ■ To identify and assess environmental and social risks and impacts of the project. ■ To adopt a mitigation hierarchy to anticipate and avoid, or where avoidance is not possible, minimize impacts and risks ■ To promote improved environmental and social performance through management systems. ■ To ensure grievances and external communications from are responded to and managed appropriately. ■ To promote and provide means for adequate engagement with Affected Communities
PS 2: Labour and Working Conditions	Recognises that the pursuit of economic growth through employment creation and income generation should come with the protection of worker's fundamental rights.	<ul style="list-style-type: none"> ■ To promote the fair treatment, non-discrimination and equal opportunity of workers and to protect workers. ■ To promote compliance with national labour and employment laws. ■ To promote safe and healthy working conditions, and health of workers.
PS 3: Resource Efficiency and Pollution Prevention	Recognises that increased economic activity can generate increased levels of pollution and consume finite resources in a manner that may threaten people and the environment at the local, regional, and global levels.	<ul style="list-style-type: none"> ■ To avoid or minimise adverse impacts on human health and the environment by avoiding or minimizing pollution from project activities. ■ To promote more sustainable use of resources, including energy and water. ■ To reduce project-related greenhouse gas emissions.
PS 4: Community Health, Safety and Security	Recognises that project activities, equipment, and infrastructure can increase community exposure to risks and impacts.	<ul style="list-style-type: none"> ■ To anticipate and avoid adverse impacts on health and safety of the Affected Community during the project life from both routine and non-routine circumstances ■ To ensure that the safeguarding of personnel and property is carried out in accordance with relevant human rights principles and in a manner that avoids or minimizes risks to the Affected Communities.
PS 5: Land Acquisition and Involuntary Resettlement	Recognises that project-related land acquisition and restrictions on land use can have adverse impacts on communities and persons that use this land.	<ul style="list-style-type: none"> ■ To avoid, and when avoidance is not possible, minimize displacement by exploring alternative project designs. ■ To avoid forced eviction. ■ To anticipate and avoid, or where avoidance is not possible, minimize adverse social and economic impacts from land acquisition or restrictions on land use ■ To improve or restore, the livelihoods and standards of living of displaced persons.
PS 6: Biodiversity Conservation and Sustainable Management of Living Natural Resources	Recognises that protecting and conserving biodiversity, maintaining ecosystem services, and sustainably managing living and natural resources are fundamental to sustainable development	<ul style="list-style-type: none"> ■ To protect and conserve biodiversity. ■ To maintain the benefits from ecosystem services. ■ To promote the sustainable management of living natural resources through the adoption of practices that integrates conservation needs and development priorities.

Performance Standard	Description	Purpose
PS 7: Indigenous Peoples	Recognises that Indigenous Peoples, as social groups with identities that are distinct from mainstream groups in national societies, are often among the most marginalised and vulnerable segments of the population.	<ul style="list-style-type: none"> ■ To ensure that the development process fosters full respect for the human rights, dignity, aspirations, culture, and natural resource-based livelihoods of Indigenous Peoples ■ To anticipate and avoid or minimize adverse impacts of projects on communities of Indigenous Peoples ■ To promote sustainable development benefits and opportunities for Indigenous Peoples ■ To establish and maintain an ongoing relationship based on Informed Consultation and Participation with the Indigenous Peoples affected by a project through the project's life cycle. ■ To ensure the Free, Prior, and Informed Consent (FPIC) of the Affected Communities of Indigenous Peoples
PS 8: Cultural Heritage	Recognises the importance of cultural heritage for current and future generations	<ul style="list-style-type: none"> ■ To protect cultural heritage from the adverse impacts of project activities and support its preservation ■ To promote the equitable sharing of benefits from the use of cultural heritage.

Source: IFC Performance Standards, January 2012.

2.1.3.1 IFC Environmental, Health, and Safety Guidelines

The Environmental, Health, and Safety (EHS) Guidelines are technical reference documents that address IFC's expectations regarding the industrial pollution management performance of its projects. They are designed to assist managers and decision makers with relevant industry background and technical information. This information supports actions aimed at avoiding, minimizing, and controlling EHS impacts during the construction, operation, and decommissioning phase of a project or facility. The EHS Guidelines serve as a technical reference source to support the implementation of the IFC PSs, particularly in those aspects related to PS 3: Pollution Prevention and Abatement, as well as certain aspects of occupational and community health and safety. The IFC also has industry sector guidelines that can be used, especially, the Geothermal Power Generation guidelines for this Project. General EHS Guidelines (30 April 2007) also exist, which contain information on cross-cutting environmental, health, and safety issues potentially applicable to all industry sectors.

When host country (Dominica) regulations differ from the levels and measures presented in the EHS Guidelines, projects are expected to achieve whichever is more stringent. If less stringent levels or measures are appropriate in view of specific project circumstances, a full and detailed justification for any proposed alternatives is required. It is important to note that this is also the case for IDB, AFD and CDB guidelines.

2.1.4 Agence Française de Développement (AFD)

The French Development Agency (Agence Française de Développement (AFD)) gives aid within the framework of the Sustainable Development Goals that have been set by the United Nations for the 2015-2030 period. More specifically, in France, development aid meets four standards:

- Effectiveness: an assessment is made of direct results of the aid, and the specific features of the countries are taken into account.
- Transparency: detailed and updated information on the implemented programs is made available.

- Coherency: this requires taking into account the effects of the aid on all the economic and social policies of the donor countries.
- Accountability: the use of funds and the results obtained must be justified to citizens.

AFD aims to promote sustainable and equitable development in all operations funded, by ensuring that these operations effectively contribute to the objective of sustainable development (combating poverty and ensuring the satisfaction of human needs, strengthening solidarity between human beings and between territories, preserving biodiversity, preserving habitats and natural resources, combating climate change). All operations financed by AFD are required to comply with the national regulations of the country where the operation is implemented, including for environmental and social issues. However, as regulations in the countries where AFD operates are sometimes incomplete or under development, AFD uses as a reference a number of rules, good practices and directives produced by international standard-setting organizations and proven with more than 70 years of experience in the financing of development projects. This mainly concerns:

- The World Bank Safeguard Policies for public sector financing;
- The UN Principles for Responsible Investment (UNPRI); and
- The IFC Performance Standards.

The major international conventions ratified by the countries where AFD operates are also used as references, mainly:

- The United Nations Universal Declaration on Human Rights;
- The International Labor Organization fundamental conventions on labor law;
- The United Nations Convention on the Elimination of All Forms of Discrimination against Women; and
- The Organization for Economic Co-operation and Development guidelines for multinational enterprises.

In terms of Environmental and Social (E&S) risk management, AFD does not have specific E&S Standards and applies World Bank Group Standards including the World Bank E&S Framework and IFC Performance Standards and the related Guidance and Interpretation Notes.

3. PROJECT DESCRIPTION MODIFICATIONS SINCE THE 2018 ESIA

This section provides an updated project description of the design modifications which have occurred since the 2018 ESIA was published. Design modifications include:

- The increase in plant capacity from 7 MW to 10 MW;
- The selection of plant technology type: a Binary Cycle Power Plant utilizing Organic Rankine Cycle (ORC) technology;
- Decrease in number and location of the injection wells, from two injection wells at WWR1 and WWO1 to only one injection well at RVI2¹ (this requires drilling a deviated well, the construction of a well pad, the installation of a reinjection pipeline from the plant to the reinjection well, which was reduced from 4 km to approximately 1.2 km);
- The construction of a new well pad and the drilling of a back-up production well (well RVP2 at Production Pad A)²; and
- The reduction of the steam gathering system (SGS) from 3 km to 1 km.

3.1 Project Overview

This Project is being carried out by the DGDC, a private company developed in 2017 by the GoCD. DGDC will continue to own and manage the Project. The DGDC has a provisional Power Purchase Agreement (PPA) agreed with DOMLEC. DOMLEC is Dominica's privately owned electricity generation and distribution company, currently the sole generator and distributor (apart from some small scale solar installations) on the island. GoCD /DOMLEC will be installing the interconnection between the local Laudat hydro station and the Project, as well as any required grid updates to transmit and deliver the electricity.

The objectives of the Project:

- Reduction of high electricity tariff rates.
- Reduction or elimination of use of diesel fuel oil generation.
- Increase price certainty in electricity tariffs – diesel fuel oil varies in cost.
- Overall effect – make Dominica a more attractive place to do business & reduce cost burden to community.
- Increase resilience – Dominica has objective to be World's first climate resilient nation. Geothermal plant must be designed and built with high resilience & high reliability.
- Reduce carbon footprint by maximizing use of renewable energy.

Current restrictions and limitations of the Project include:

- Dominica has network restrictions brought about by sole use of 11 kilo-Volt (kV) for both "network" and distribution.
- Bulk of power distribution and consumption around Roseau. Average load around 11 MW at present, peak at 14.8 MW.
- Very limited ability to move power from south to north over 11 kV.

¹ To be financed by the World Bank.

² To be financed by the World Bank.

- Largest generator on island at present is 2.84 MW.
- Only one production well available at present – comfortably produce 7 MW.

3.2 Project Location

The Project is located on the Island of Dominica, in the Roseau Valley, to the southeast of Laudat, at an estimated elevation of 550 meter (m) above mean sea level (amsl) (Figure 3-1).




Figure 3-1: Project Location

The Project components will be located in four separate areas: Power Plant Site; Injection Area, Production Well Area, and the back-up Production Pad A. Figure 3-2 depicts the location of these general areas as well as the access roads and the approximate location of the injection pipeline route.





Figure 3-2: Project Component Location

3.3 Process Overview

The proposed Project will be a binary cycle geothermal power plant. A binary cycle power plant is a closed-loop system (with no emissions under normal operating conditions) where the heat from geothermal hot water is transferred to a secondary motive/working fluid via a heat-exchanger and is then reinjected back into the reservoir via injection wells (the working fluid, n-pentane or isopentane, will be an environmentally benign hydrocarbon working fluid with a negligible Ozone Depletion Potential and Global Warming Potential. The heat from the geothermal hot water causes this second fluid to turn to steam, which is used to drive a generator turbine (EERE, 2020). The second fluid is then re-condensed, and the cycle begins all over again as shown in Figure 3-3.



Source: EERE, 2020

Figure 3-3: Typical Binary Cycle

For the Project plant, two turbines and generators (2 x 5 MWe Net) will be installed and connected to the SGS (production well). The system will operate in two separately closed loops: one for the primary thermal fluid extracted from the reservoir and then reinjected back into the reservoir at a different location (the geothermal fluids), and the other for the ORC working fluid which is circulated from the heat exchangers, to the turbines, to the cooling and recondensing system, and then back to the heat exchangers.

The geothermal fluids drawn from the reservoir will flow through the heat exchangers in the Power Generation Units transferring heat through the heat exchanger to the ORC working fluid, causing it to flash to vapor, and spin the turbines. Once the geothermal fluid goes through the heat exchangers, it will be returned to the reservoir through the injection wells. After passing through the turbines, the ORC fluid in vapor form will be condensed back to liquid form via air cooling and cycled back into the heat exchanger.

The plant design includes a retention (sump) pond capable of accommodating the free flow of a well in the event it is needed for maintenance or bypass issue.

3.4 Project Components

The proposed geothermal facility will consist of the following main components which are explained in more detail in the following sub-sections:

Plant Equipment:

- Production and Injection Wells
- SGS and Brine Reinjection Pipeline and Well Pads
- Turbine Generator
- Heat Exchangers
- Recuperators
- Condensers

- Pumps (feed, wells, ponds, firefighting system)
- Storage Tanks
- Transformers
- Emergency Generator
- Water Tank and distribution system
- Fire Fighting Tank and System
- HVAC System
- Oil System

Facilities:

- Security Building and Parking Lot
- Brine Ponds
- Electrical Building which will include separate areas for offices, kitchen and meeting rooms, workshop and storage, a control room, and a machinery room.
- Septic Tank and Leach Field

Figure 3-4 shows a preliminary plant layout based on site topography and existing components locations for the binary plant.




Figure 3-4: Proposed Preliminary Plant Layout

3.5 Production and Injection Wells

As stated in the 2018 ESIA, five wells have already been drilled as part of the exploration phase of this Project. These include three slimhole exploration/production wells (WW-01, WW-02, and WW-03), one standard diameter production well (WW-P1), and one standard diameter injection well (WWR1, will not be used under the current Project configuration). The current Project is proposing to use two of the already existing wells as they are for production (WW-P1 and WW-03) with no modifications, and to install a new well for re-injection (RVI2) as well as a back-up well at Production Pad A (RVP2) (see Figure 3-2). The proposed back-up well at the Production Pad A will be a standard diameter production well. Details for the existing wells are provided in Table 3-1.

Table 3-1: Physical Parameters of the Existing Production Wells

Parameter	WW-P1	WW-03
Wellhead, Easting (m)	679,461	n/a
Wellhead, Northing (m)	1,695,567	n/a
Wellhead Elevation m (amsl)	552	543
Total Depth (mRKB) ³	1,505	1,613
Azimuth (°)	190	-
Throw (m)	465	-
Casing Size (in)	9 5/8	7
Casing Shoe Depth (m)	726	590.6
Liner Size (in)	7	4.5
Liner Depth (m)	700-1,505	569-1,612

Source: Jacobs, 2018.

Specific details for the proposed new wells (RVI2 and RVP2) are not available yet; however, they will be similar to the existing wells. Current proposed design details for the new wells are provided in Section 3.5.2.1 below.

3.5.1 Well Pads

As part of the previous well drilling activities, three well pads have already been constructed; however only one of these will be utilized under the current plant configuration. Site WW-03 pad contains two of the already existing wells: WW-P1 and WW-03; this pad still requires the following activities: site improvement, slope stabilization, drainage works, fencing, and security lighting (Figure 3-5).


³ mRKB - rotary kelly bushing depth, or the depth measured below the rotary table.



Source: Jacobs 2018

Figure 3-5: Panoramic View of Existing Well Pad from the East

The existing site WW-03 pad occupies (an area of approximately 2,000 m² and will be used to contain much of the steamfield equipment, including the separator and rock muffler. Figure 3-6 depicts the existing well layout as proposed during drilling activities. Proposed layouts for the new well pads at the reinjection site and Pad A are not yet available; however, they should be in line with the already existing well Pad.



Source: Iceland Drilling, 2012

Figure 3-6: Existing Pad Layout

The back-up production well site, Production Pad A, will consist of the following:


- An area of 4,700 m², stoned and compacted, generally treated as a "heavy roadway".
- A network of gutters arranged around the manufacturing and circulation basins for the drilling mud.

- Watertight basins or sludge tanks intended for the recovery of solid and liquid cuttings produced by drilling as well as geothermal water during the well test phase.
- A cuttings corral under the vibrators of the drilling rig. This structure is intended to be destroyed at the end of the drilling work.
- A reinforced concrete slab 0.30 m thick intended to accommodate the substructure of the drilling machine; this slab is 20 m long and 9 m wide for the construction of a well.
- For each well, a reinforced concrete cellar where the wellhead is located in its center with its stack of safety valves and adapters.

3.5.2 Well Drilling

3.5.2.1 Drilling Equipment

Well drilling equipment is not available on the Island and will have to be brought in via Lorry and boat. For existing wells, a hydraulic rotary drilling technique was used using a Drillmec G-102 drilling rig as shown in Figure 3-7 below.



Source: CGIP, 2013.

Figure 3-7: Schematics of a Typical Drill Rig


A drill bit bores into the ground (in this case, a roller cone drill bit) lowered on the end of a drill string by fitting additional drill pipes as drilling proceeds. The drill pipes are rotationally driven by the top drive which supports the weight of the drill string and injects drilling muds to lubricate and cool the drill bits and to allow cleaning. The whole drilling assembly is supported from a telescopic derrick installed over the well (CGOP, 2013).

3.5.2.2 Well Specifications

The proposed project involves the drilling of one new reinjection well (RV12) and one new production well (RVP2). The proposed wells would be drilled to a total added vertical depth of approximately 1,500 m; these will be deviated wells with a maximum inclination of 30°, drilled in four different sections:

1. Vertical section down to 110 m, 26" or 24" – installing casing 18"5/8 K55 BTC 87.5 lbs/ft and cement.
2. Vertical section down to 430 m, 17"1/3 – installing casing 13"3/8 L55 BTC 68 lbs/ft and cement.
3. Deviated section to a True Vertical Depth (TVD) of 750 m, 12"1/4 – Kick of Point (KOP) 430 m GBU 3°/30 m to 30°, Installing casing 9"5/8 47 lbs/ft and cement.
4. Deviated section to a TVD of 1500 m (1650 m measured depth [MD]), 8"1/2, installing a 7" K55 BTC slotted liner, with a liner hanger between 9"5/8 and 7" casing.

Figure 3-8 shows one of the proposed schematics for a deviated well, although actual depths are as proposed in numbers 1-4 above.



Source: ISOR 2020

Figure 3-8: Schematic of Proposed Deviated Wells

The actual drilling and completion time for all of the existing wells was from 35 to 45 workdays, with well WW-P1 drilled and completed in 47 days (including transportation and rig-up) (ISOR, 2020). It is expected that drilling of the new wells will be completed in the same amount of time.

3.5.2.3 Drilling Fluids and Cuttings

Although the final drilling fluid program is not available at this stage, it is anticipated that drilling fluids will be as utilized for the existing wells at the site. The drilling fluids will be water base muds (WBM), and therefore primarily environmental friendly, the contents consisting mainly of:

- natural clay
- caustic soda

- polymers
- heat protector for polymers
- lubricant
- biocide

The drilling muds are recovered and treated for recycling back into the well. Drilling muds are pumped down the boreholes where they mix with solid elements (cuttings) from the breakdown of the drilled rock formations, circulate back up the borehole where they pass through various separating systems to remove solid particulates:

- Three shale shakers,
- One to two centrifuges, and
- Flocculation unit to minimize the amount of mud to be treated.

The treated mud will be decanted into an impermeable pit to avoid contaminating surface water and/or groundwater, then sent to a suction tank while awaiting re-injection.

A cuttings corral of 150 cubic meter (m³) will be provided under the shale shakers and flocculation unit to temporarily store cuttings. The cuttings will be subsequently collected in a dedicated lined sump, approximately 1,200 m³ (5m L x 15m W x 3m D), prior to being transported to suitable disposal facilities. Reclamation for use as backfill may be considered, depending on the material's toxicity. If it is found to be toxic, this waste will have to be sent to disposal facilities for hazardous waste (CGIP, 2013).

During drilling activities for existing wells, substantial amounts of various conditioning materials had been procured by the DGDC; however, very limited quantity of additives was considered necessary during the drilling and therefore not used. A mud-engineer, provided by the drilling company, was on-site during the drilling and monitoring of the drilling mud was carried out at regular intervals. Lignosulfonate was added as an anti-coagulant agent and caustic soda to regulate pH (ISOR, 2020). Controlling the pH of the well helps provide fluid stability, improves polymer hydration and performance, and can treat out contaminants like carbon dioxide (CO₂), hardness, and hydrogen sulfide (H₂S) encountered in mix waters or while drilling (Schlumberger, 2020).

3.5.2.4 Gas Releases

It is already known that potentially dangerous gases are present in the areas of the wells as high levels of H₂S were detected at the Wotten Waven well pad. Although details are currently unknown for the equipment to be utilized to drill the proposed new wells, emissions of H₂S and CO₂ were monitored during drilling activities for the existing wells in order to protect site personnel.

An H₂S detection system was installed with sensors at the borehole, mud treatment units, and the storage unit roofs. These sensors had a warning light and siren that were activated if thresholds of 10 and 15 parts per million were reached. In addition, each employee was also equipped with an individual H₂S detector to wear. Wind socks on site informed personnel of the direction of wind flow in order to inform neighboring communities if necessary.

In addition to monitoring, previous drilling activities also include pH regulation using caustic soda. It is anticipated that proposed drilling activities will include at least the same measures used during previous drilling activities in order to prevent the release of potentially dangerous gases.

3.5.2.5 Blowout Prevention

During drilling activities for existing wells in the area, an over-pressurized feed-zone was encountered in well WW-02 (not part of this Project). It was noted as a sudden gas-kick when drilling was stopped at 903 m to run an inclination survey. Well head pressure quickly reached 32 bar and after pumping on the well with closed pipe-ram blowout preventer (BOP), the pressure faded. The source of the gas was later identified to be from a gas-filled pocket or aquifer at 562 m depth. The geothermal reservoir in Laudat is however generally under-pressurized with respect to a cold-water column.

During the drilling activities for the proposed wells, BOPs will be installed for each drilling section except the first one (to an estimated depth of 110 m). An annular type BOP will be implemented while drilling the second section (21"1/4 or 20"3/4) along with a kill and choke line to be able to kill the well if necessary

For the remaining two sections (diverted wells), a full stack BOP will be implemented with blind rams, variable bore rams, or pipe rams, and an annular preventer.

In addition, in order to control pressure, a choke manifold will be implemented with at least two chokes and two kill lines.

In accordance with American Petroleum Institute standards, the equipment will be tested at the start of a new section, and/or at least every 3 weeks. Functional tests will be carried out at least once a week but no more than once a day.

3.5.2.6 Scaling Control

An important parameter that must be considered for the efficient design and operation of a geothermal plant is management and control of the scaling potential from the produced geothermal fluids.

Geothermal fluids are typically at or near supersaturation for various elements, especially calcium, magnesium, silica and iron. As the fluid flows through the wells, temperature and pressure changes can result chemical equilibrium changes that if left untreated can lead to well bore clogging, restrictions in the capabilities of the heat exchangers, and ultimately, complete loss of production from the producing wells, injection wells, or heat exchangers.

Based on Project design and the results of brine testing at the site, no scaling control system will be installed. The reinjection temperature will be kept high enough to avoid scaling issues in the system.

3.5.2.7 Drilling Power

As was the case with the existing wells, power for operating the drilling equipment will provided via onsite diesel powered generators. Diesel used for drilling would be stored in double-walled diesel storage tanks with secondary containment capable of storing 120% of the capacity of the tanks. Diesel will be acquired from sources on the Dominica. The fuel storage tanks and drilling lubricants and additives would be stored in a designated area with impermeable surfaces. The storage area would be bermed to contain potential spills and any contaminated storm water.

3.5.2.8 Well Testing

Well testing will be carried out at the proposed new production well. The length of the testing will be around 48 hours with the actual duration adapted according to the flowrate encountered. Post testing, the fluid produced from the production well will be stocked in a pond (allowing the geothermal fluid to settle) and then reinjected in the new injection well via temporary pipes installed between the two wells. During testing, fluid samples will be collected and analyzed to determine the precise the chemistry of the geothermal fluid.

An injection test will be performed at the proposed new injection well once constructed. Details on testing procedures are not yet available.


3.5.3 Existing Site Conditions

Studies performed at the site have found the following conditions for the reservoir and the geothermal fluid:

- An injection test was performed post drilling at a previously proposed injection well (not part of this Project), which indicated that the injection well in the Project area has significant permeability.
- The maximum measured temperature was 230.86 Celsius (°C) at 1110.5 m, measured 6-hours after the injection test ended.
- The deep liquid (reservoir liquid) is relatively dilute with Chlorine (Cl) and Sodium (Na) concentrations close to 2,600 milligram per liter (mg/L) and 1,500 mg/L respectively;
- Boiling due to depressurization within the well is expected to cause calcite scaling at or slightly above the boiling level; and
- The overall gas content of the steam at 150°C (4.8 bara) based on calculations from samples was 1.6 wt% (at 4.8 bara) or approximately 8 L gas/kg condensate.

3.6 Steamfield

Once the brine comes up the production wells, the two-phase fluid is sent to a separator where it is divided into steam and brine phases. The steam will be directed to the power plant while the brine is pumped to the injection pipeline. A simplified typical steamfield arrangement is shown in Figure 3-9.



Source: Jacobs, 2018.

Figure 3-9: Typical Steamfield Arrangement

The steamfield, comprised of the SGS, will include the following components as described below:

- Production Wells,
- Two-Phase Piping,
- Two Phase Steam Separator: 7.5-10 m high, 1.5 m diameter,
- Steam Piping,
- Steam Scrubber,
- Brine System consisting of: piping, brine pumping station and all required piping fittings, brine and condensate sumps,
- Atmospheric Flash Tank: 1-3 m in diameter, a vessel used to receive fluid e.g., brine during well testing, start-up or in the event of operational issues. The brine will flash inside the vessel and the steam component will discharge to atmosphere, while the remaining brine is pumped to the reinjection wells for disposal, and
- Control valves and instrumentation.

3.7 Power Plant

Design parameters for the power plant components have not been finalized as of the date of this document. However, the potential impacts of the final design of the power plant are not expected to change the magnitude and significance rating of the impact. The proposed binary geothermal plant, would consist of two side by side ORC systems each with their own vapor preheater and vaporizer, turbine coupled to a generator, air-cooled condensers, and a recuperator, using an environmentally benign hydrocarbon working fluid n-pentane or isopentane.

The proposed binary plant layout was presented in Figure 3-4 above.

3.7.1 Geothermal Fluid Cycle

Geothermal production wells deliver a mixture of vapor and brine. This two phase flow from each well is carried through a two-phase flow pipe into a Vertical Separator where brine and vapor (consisting of steam and non-condensable vapors (NCV)) is separated.

- Vapor - the main use for the vapor portion is to deliver heat for vaporizing and superheating the ORC working fluid in the Vaporizer, and
- Liquid - the liquid from the separator is taken by the brine disposal pump into the preheater and then reinjected into the reservoir through the reinjection well.

Once both flows have been through the complete cycle, they go to the condensate system, which controls what is fed to the reinjection wells.

3.7.2 The Organic Rankine Cycle

Although the proposed plant design has not been finalized, the typical process for the ORC cycle is presented as follows. The systems circulation pumps deliver the high-pressure working fluid first to the shell side of two parallel Recuperators to heat the working fluid downstream at the Expander entering the tube side of the Recuperators. The working fluid feeds the Preheater by increasing temperature of the fluid.

Inside the Preheater the working fluid is heated up to a point close to the boiling point. The heat exchanger has a standard shell and tube design with the working fluid on the shell side, and the resource fluid on the tube side to facilitate cleaning of the tube side.

After the Preheater, the working fluid enters the (tube multi-pass) shell and tube Vaporizer. The boiling working fluid is on the shell side, and the brine and vapor on the tube side. The working fluid evaporates on the outside of the tubes and leaves the Vaporizer in the superheated condition through a Mist Eliminator, which removes any droplets which may be present in the vapor.

The working fluid vapor then enters the turbine or Expander. The Atlas Copco radial inflow expander proposed for the Project has variable guide vanes, which control the flow of the working fluid into the turbine. The variable guide vanes are designed in a way that they ensure best inlet angle of the flow into the expander wheel, regardless of the working fluid flow or turbine load. The variable guide vanes control Vaporizer and Preheater pressure as well.

The ORC working fluid leaves the turbine and enters to the tube side of the Recuperator, heating the shell side working fluid coming from the Feed Pump. In the air cooled condensers, the vapor condenses into liquid after exchanging heat with ambient air. The tube surface on the air side is designed with fins to increasing the heat exchange surface area. The Hot Well collects the working fluid condensate and functions as a Buffer Tank with sufficient height to protect the feed pumps from cavitation.

Electrically driven fans ensure adequate airflow over the tube bundles with the pressure controlled working fluid in the Hot Well Tank to eliminate excess sub-cooling.

Finally, the (condensed) liquid working fluid is circulated back into the ORC cycle via the Feed Pumps.

3.7.3 Design Parameters

Although the Plant design has not been finalized, the design life of the Plant shall be 30 years and the design life for all buildings shall be 50 years for the application of the structural design codes. Piping shall be analyzed and designed for a minimum of 7,000 equivalent full temperature displacement cycles.

Design standards and codes shall be as follows, unless stricter requirements or standards are required by Dominica code of practice (see Table 3-2).

Table 3-2: Design Standards

Component	Design Standards
Basis of structural Design	Euro norm (EN) 1990
Actions on structures	EN 1991
Design of concrete structures	EN 1992
Design of steel structures	EN 1993, EN 10025 or EN 10210 (hollow sections)
Design of composite steel and concrete structures	EN 1994
Design of timber structures	EN 1995
Design of masonry structures	EN 1996
Geotechnical design	EN 1997

Component	Design Standards
Design of structures for earthquake resistance	EN 1998
Steel for the reinforcement of concrete – Ribbed bars and welded fabric	EN 10080
Concrete - Specification, performance, production and conformity	EN 206
Foundations for Dynamic Equipment	American Concrete Institute (ACI) 351.3R-04
Connections	Deutsches Institute fur Normung (DIN) 931/EN 24014

Other relevant design requirements include:

- All buildings and sheds shall be designed for expected hurricane loading and other natural hazards and meet Dominica’s building code.
- All buildings and sheds shall be made of concrete.
- All building materials and surface coatings utilized shall consider the hostile corrosive environment often involved in geothermal power production due to H₂S.
- Foundations for all buildings, structures and miscellaneous equipment pads shall be selected and designed based on the superimposed loads, and the strength and character of the supporting material as determined by the geotechnical study at site.
- The turbine generator foundation shall be designed by the Contractor for dynamic loading as well as static and environmental loading to limit vibration and avoid resonance.
- Spill containment shall be provided for all oil-filled transformers and as required by applicable local and international codes and regulations.

3.7.3.1 Plant Safety Systems

Plant safety design systems will include:

- Fire Protection System - The fire protection system would consist of a fresh-water tank, an electric firewater supply pump and a jockey pump, fire mains, and local hose and spray stations.
- Pressure Relief System - The ORC cycle will be protected by pressure relief equipment such as pressure relief valves and rupture disks.
- Detectors/Monitors – detectors and monitors will be available throughout the plant. These will include working fluid detectors, fire detectors, windsocks, and hydrogen sulfide detectors.
- Natural Hazard Protection – the plant will be designed in order to withstand natural hazard events, including hurricane winds and flooding, and may include wind protection screens around the air-cooled condenser units to protect them from wind and air-borne debris during hurricanes.

3.7.3.2 Plant Control Systems

Primary operation of the SGS and Power Plant shall be via a fully integrated Distributed Control System (DCS) with operator workstations in the Operator Control Room.

3.7.3.3 Oil System

A lubricating oil system is required for the turbine generator units (one per each unit, see Figure 3-4 above). The system includes pumps, coolers, oil tank, filters and purifiers. As mitigation for leakage or spills, oil containment bunds / trays are normally specified around or under all lube oil equipment to contain at least 110% of the total oil system capacity.

3.8 Pipelines

Current Project design places the plant very close to the production well, with the SGS running for approximately 1 km and the reinjection pipeline's proposed length of approximately 1.2 km. Although final design details are unavailable, Figure 3-10 shows the approximate location of the reinjection pipeline.




Figure 3-10: Approximate Location of the Reinjection Pipeline

The reinjection pipeline will be an approximately 30 cm wide pipe (final design diameter is unknown at this time) that will require a 10 m wide corridor during construction and a 4 m wide corridor during operation. A maintenance road will run along the length of the pipeline; however, design details have not been finalized. The potential impacts of the final design of the reinjection pipeline is not expected to change the magnitude and significance rating of the impact

General construction activities will include site improvement and slope stabilization where necessary. This will entail vegetation clearance for the reinjection route and well pad. Earthworks will be required for installation of concrete foundations for the pipeline and the construction of a pipe crossing over the "Ravine Fordie." The work will also include welding and set up of the steel pipes and digging of trenches for drainage.

The injection pipeline will operate at a high temperature and pressure and must be carefully designed with suitable supports and guides which safely allow for thermal expansion of the pipe between its hot and cold states. This will require vertical or horizontal u-bends every 100 m. The reinjection pipeline will be insulated to reduce heat loss, which is necessary to avoid deposition of silica and to protect people and wildlife from burns. It will be clad in aluminum or other appropriate material and may be colored or camouflaged to reduce visual impacts.

Condensate production is associated with the steam pipes as a result of the difference between the walls of the pipelines and the surrounding atmosphere in spite of insulation (Jacobs, 2018). Condensate produced in the steam pipelines will be collected via a condensate collection drain pot, found at local low points on the route. Condensate will either flow through a piped network to downhill storage sumps from where it can then be pumped to the injection well for disposal or will be discharged directly to the ground.

3.9 Brine Ponds

Spills and releases during shutdowns would be contained within a lined containment pond, which should be able to contain several hours of brine flow from both ORC units. The containment pond would be on the lowest topographical area of the site.

Should a fault occur that requires the geothermal plant to be taken offline suddenly, the production wells must be shut down slowly, over a period of two to four hours, to avoid thermal shock to the production and injection wells. In the unlikely event of an outage, fluids would be diverted to the lined containment while the wells are gradually closed. The containment pond would hold the diverted fluids before being pumped to the injection wells and would ensure that no off-site flows would occur during these events.

Lined ponds will also be available at the low points along the reinjection pipeline in order to drain the pipeline during shutdowns if needed.

3.10 Transmission Lines

No above ground transmission lines are proposed as part of the Project. Current design assumes only 1x 11 kV and 2 x 33kV underground cable interconnection to the DOMLEC electricity grid at the power plant site are necessary. These underground cables will be approximately 300 m long to be installed as part of plant construction activities.

3.11 Additional Facilities

3.11.1 Additional Structures

Only one building is currently proposed at the plant site. This Electrical Building will include separate areas for offices, kitchen and meeting rooms, workshop and storage, a control room, and a machinery room. Design details for this facility have not been finalized. The potential impacts of the final design are not expected to change the magnitude and significance rating of the impact.

3.11.2 Hazardous Material Storage

Hazardous materials associated with the Project include the working fluid, oils and lubricants, and could include other chemicals such as sulfuric acid, sodium hydroxide, and hydrogen chloride that would be used to adjust the pH of the geothermal fluids and reduce scale build-up in the wells and heat exchangers. These materials would be stored in designated areas with impervious surfaces designed to contain potential spills. The working fluid for the ORC will be kept in a 30 m³ storage tank; however its location within the plant configuration is still unknown.

Workers would be instructed in the hazardous properties of these chemicals, required protective clothing, and in the proper procedures for handling, storing, and eventual disposal of these materials.

Any hazardous waste generated during construction and operation will be handled in accordance with the Hazardous Waste Management Plan (see Appendix A).

3.11.3 Site Security

The facility will be gated and completely fenced in with adequate lighting throughout. The contractor shall design, supply and install a 2.5 m high galvanized steel fence around the perimeter of the Project Area. The Project will also include a small security building for a security guard, however, this facility has not been designed yet (see Appendix A – for the site Security Management Plan and Operational Health and Safety Management Plan). The number of guards and their shift information has also not been defined yet.

3.11.4 Site Surface Water Drainage Features

The Contractor shall design, procure and install a storm water drainage system for the plant, capable of handling both storm water from building roofs and run-off from the plant site and applicable surrounds. Under no circumstances shall process effluents, contaminated or greywater be discharged directly into the storm water drainage system.

The storm water drainage system shall include the supply and installation of a storm water pipeline including all fittings, manholes, wells, drains, culverts, pumps, pits, and all other equipment for a fully functional storm water drainage system. Alternative systems, such as gravity drain in concrete channels/ducts, covered with concrete lids and/or hot dip galvanized gratings could also be implemented.

The site drainage shall be designed for the maximum peak rainfall as obtained from the meteorological data of the area and climate change projections.

The drainage pipe system shall have a gradient sized for a velocity not less than 0.7 meter per second (m/s) for self-cleaning with an upper limit of 3.0 m/s. The pipe material shall be consistent with the condition or characteristic of the site and the manholes, pipes and fittings shall comply with apparent standards.

There are no known existing stormwater systems in the immediate vicinity of the site. The Contractor shall design and define the discharge point of the storm water system, to be approved by DGDC.

3.11.5 Water and Utilities

3.11.5.1 Construction

Raw water will be required during construction and ongoing operation and maintenance of the plant. Water abstraction for the Project will require an authorization application to the “Minister for Housing Lands Settlement and Water Resource Management” (Caraïbes Environnement Développement, 2013; see Table 3-3; and Appendix A), as already discussed and included in the Jacobs ESIA.

Table 3-3: Proposed Water Take Limits

Duration	Quantity	Unit
Daily	10,000	Liters

Monthly	200,000	Liters
Maximum Instant	5	Liters/second

Source: Jacobs 2018

Raw water for construction and permanent works shall be drawn from a naturally occurring spring located at a higher elevation above the site (15°19'58.20" N, 61°19'34.22" W, at 623 amsl). Figure 3-11 shows the location of the water source.




Figure 3-11: Proposed Water Source Location

DGDC shall be responsible for obtaining the permit to use the water for construction and permanent works. The Engineering Procurement and Construction (EPC) Contractor shall be responsible for the design, execution and completion of the raw water intake structure and piping required to transfer to the Site. The proposed raw water sources have not been modified since the Jacobs ESIA and all requirements, impacts and mitigation measures are discussed in that document.

Domestic wastewater from amenities at the power plant site including the worker’s camp will need be collected and treated in a package plant to meet discharge requirements. The EPC Contractor will need to maintain the package plant and associated effluent disposal system to meet international guidelines discharge criteria (i.e. WBG EHS Guidelines) and to prevent odor or other nuisance to the community during the period of construction. The EPC Contractor will typically be responsible for decommissioning and removing the unit at the end of the construction period.

3.11.5.2 Operation

During Operation, the wastewater system shall be comprised of two separate systems, one handling sewerage from sanitary equipment and kitchen sinks in buildings, the other handling drainage from floor drains in process area and sump pits.

The sanitary sewerage system will be comprised of a septic tank with field drains, sized for 2 months between emptying, connected the plumbing from all occupied areas. Under no circumstance shall process effluents, storm water or contaminated water be discharged into the sanitary sewage system.

The greywater drainage system shall collect contaminated water by connecting drains in all process area and containment of oil spillage and pass it through an oil/water separator prior to discharge into the storm water system.

Potable water to be used at the site during operation will be supplied by Dominica's Water and Sewerage Company Ltd. (DOWASCO). The options currently being considered are:

- Option 1. Extend the existing 2" line to the geothermal plant site. This is about 1,200 m, and would deliver potable water at a rate of approximately 8 cubic meter per hour (m³/hr).
- Option 2. Pump water from Titou Gorge to the plant site. The water would be extracted below the DOMLEC intake point, to minimize interference with DOMLEC's systems. The flow in the Gorge can support the target flow rate (10 m³/hr).
- Option 3: Truck water to the site.

Selection of the final option is dependent on water capacity which is currently being assessed by DOWASCO.

3.12 Project Phases and Schedule

3.12.1 Construction

Construction activities related to the Project can be broken up in three different areas:

- The plant and associated facilities,
- The reinjection pad⁴ and pipeline which would require upgrades of an access road and the creation of a service road along the reinjection pipeline, and creation of a well pad for drilling of the ReInjection well, and
- The back-up Production Pad A and production well⁵, which would also require the construction of an access road from the area of the Plant.

3.12.1.1 Site Clearing

Although the designs for the proposed well pads and the plant have not been finalized, the potential impacts of the final design on site clearance for the well pads and plant have been assessed based on the general locations proposed. Design changes are not expected to change the magnitude and significance rating of the impacts as long as all proposed mitigation measures are applied. Below are some estimates of the amount of land that will be required by each of the Project's components based on available information (see Table 3-4):

⁴ To be financed by the World Bank.

⁵ To be financed by the World Bank.

Table 3-4: Estimated Land Requirements by Project Component

Project Component	Estimated Land Requirement
Power Plant Area	20,609 square meter (m ²)
Reinjection Pipeline and 10 m corridor	9,845 m ²
Injection Well Pad	2,557 m ²
Production Pad A	7,076 m ²
Proposed New Access Roads (width is unknown)	600 m

General construction activities will include site improvement and slope stabilization where necessary. This will entail vegetation clearance for the plant and its facilities (including the brine pond), the reinjection pipe route, well pads, and new access roads. Earthworks will be required for installation of concrete foundations for plant, the well pads, the pipeline and the construction of a pipe crossing over the “Ravine Fordie.” The work will also include welding and set up of the steel pipes and digging of trenches for drainage

Foundations

Concrete foundations for the pipeline will be constructed, followed by the set up and welding of steel pipes to transport the separated brine. The volume of water required for these foundations is minimal and will be sourced from local watercourses. Pipe bridges will need to be constructed over the intermittent watercourses within the site as appropriate.

For the well pads, a reinforced concrete slab 0.30 m thick intended to accommodate the substructure of the drilling machine, will be constructed. These slabs will be approximately 20 m long and 9 m wide for the construction of a well; however final dimensions are unknown.

The construction of the plant and associated facilities will also require foundations. Foundations for all buildings, structures and miscellaneous equipment pads shall be selected and designed based on the superimposed loads, and the strength and character of the supporting material as determined by the geotechnical study at site.

Drilling

The following process will be carried out for drilling the new proposed wells:

26” section

1. Make up bottomhole assembly (BHA) and drill the section to total depth (TD)
2. Short trip and circulate hole clean
3. Pull out of the hole (POOH) BHA and lay down the drill collar (DC)
4. Make up the casing, cement with stinger till observing cement in the cellar – stop injecting cement and start displacement
5. Waiting on cement (WOC), and while WOC – install casing head and annular preventer

17"1/2 section

1. Make up BHA, drill the section to TD
2. Short trip and circulate hole clean
3. POOH BHA and perform open hole (OH) caliper logging
4. Make up the casing, cement with stinger till observing cement in the cellar – stop injecting cement and start displacement
5. WOC and while WOC – install the spool and 13"5/8 BOP Stack

12"1/4 section

1. Make up BHA and drill the section to TD
2. Short trip and circulate hole clean
3. POOH BHA, and perform OH caliper logging, cement bond log (CBL)/ variable-density log (VDL) of the 13"3/8 casing
4. Make up the casing, cement with cement plug
5. WOC

8"1/2 section

1. Make up BHA and drill the section to 1000 m
2. Short trip and circulate hole clean
3. Drill the section to 1300 m
4. Short trip to the previous shoe and circulate hole clean
5. Drill the section to approximately 1650 m
6. Short trip to the shoe and circulate hole clean
7. POOH BHA, and perform OH caliper logging of the 9"5/8 casing and geological wireline logging like Neutron if possible according to the temperature
8. Make up the liner and set the liner in the 9"5/8 casing

Plant Construction

Although design details for the plant have not been finalized, bidding documents estimate at least the following types and number of equipment will be necessary (see Table 3-5):

Table 3-5: Minimum Required Equipment for Construction

Equipment Type	Minimum Number Required
Concrete Batching Plant	1
Concrete Transit Mixer	2
Hydraulic excavator	2

Diesel Welding Machines	4
Hydraulic Crane	2

Additional Facilities

The following temporary facilities will be present and utilized during the construction phase:

- Construction laydown area: At present two flat construction laydown areas are being considered adjacent to the power plant site. The exact location of the two areas is currently unknown; however, it is assumed they will be maintained within the project footprint assessed in this document and their exact location is not expected to change the magnitude and significance rating of the impacts. Other smaller laydown areas may be required along the reinjection pipeline during construction in order to store construction materials.
- Worker’s camp:
 - Canteen and showers with hot water facilities;
 - Sleeping quarters (to support an estimated 50 workers);
 - Potable water supplies from either a tanker-supplied storage tank, or a dedicated treatment plant; and
 - Septic tanks (on-site) and/or portable latrines (off-site disposal).
- Utility services (telecommunications and electricity).
- Water and wastewater systems.

Site Access

Access starts at the Woodbridge Bay Port, through Goodwill (thereby bypassing the city of Roseau), and continues along the “Valley Road” to the entry of the village of Laudat. The existing roads will need to be upgraded and repaired in order to safely move heavy equipment to Laudat, in addition to upgrades necessary to the access to the proposed injection pad (see Appendix A – Transportation Management Plan and Community Health and Safety Management Plan).

An access road from the proposed power plant site to the proposed Pad A will need to be constructed. This road will be approximately 60-100 m long.

Schedule

For the construction of the plant and its facilities, the Project estimates a construction duration of 18 months to 2 years. For the proposed reinjection pad and well as well as the proposed back up production Pad A, the construction phase is expected to be Q1 2021 to Q2 2022.

Workforce

For construction, the contractors will need to have at least the following personnel (see Table 3-6):

Table 3-6: Minimum Required Workforce and their Qualifications

Position	Total Work Experience (yrs)	Experience in Similar Work (yrs)
----------	-----------------------------	----------------------------------

Project Manager	20	10
Site Manager	15	8
Commissioning Manager	20	10
Health, Safety, and Environment Manager (HSE)	10	5
Operations Advisor	10	8
Maintenance Advisor (Mechanical)	10	5
Maintenance Advisor (Electrical)	10	5

Although exact numbers are still unknown, facilities available during construction will be for an estimated maximum of 50 people.

During drilling, a work team consisting of 6-8 people will work 12- hour shifts. Two teams will take turns to provide staffing around the clock. Other site workers include drilling supervision, testing service providers, and security personnel, although exact numbers are unknown.

3.12.2 Operation and Maintenance

3.12.2.1 Start-up and Shut-Down

Start-up

The injection pipeline will be flushed after construction and as part of a hydro-test. Location of a suitable discharge point will depend on the site piping layout and geometry, but is expected to be into one of the sumps at the injection well pad.

The start-up operation involves the start-up of the production well and the introduction of steam into the piping systems. Process drain valves are generally left open to remove condensate from the pipes and vessels, draining to storage sumps. Brine is discharged to the storage sumps at the power plant and separator station locations. Steam is vented to atmosphere through the steam vent valves located at high point vents as well as at the rock muffler located at the power plant.

Operation

During normal operation minimal steam venting occurs, the production steam is sent to the power plant and brine is sent to injection wells. When all power plant systems are in operation, the power plant generates electricity, which is exported to the grid.

Shut down

Geothermal power plants typically shut down once a year for annual maintenance of the facilities. Shut down may be planned or due to unscheduled maintenance / outage or in some instances may involve a major transmission line outage.

During shut-down the unit(s) stops generating electricity. The power plant vent valves will emit steam until the production wells are trimmed back to match the required remaining station demand. For a complete

station shut the steam field will be closed down and the steam field piping systems will be drained to sumps at the well pads as well as to the power plant sump.

The production well will be either shut in or placed on bleed. During scheduled outages, operators would shut in the well gradually, reducing flow through the plant and requiring little or no releases of steam and water from the separator.

If maintenance is required for the vessels containing working fluid, the area to be repaired would be isolated and the working fluid drained and held in drainage tanks. The working fluids would be contained and stored on site and reintroduced into the system when maintenance is completed.

3.12.2.2 *Emergency Shut Downs*

If conditions arise that requires the power plant to immediately shut down, the plant systems will trip the power plant and steam will be directed away to the vent station. If during the emergency shutdown, the pressure continues to rise in the steam field due to major equipment failure, the bursting discs may activate to release steam vertically to atmosphere. Under this situation, the steam venting from the bursting disc will create a significant noise until the wells are shut in and geothermal fluids stop flowing. This event is considered an emergency and is unlikely.

3.12.2.3 *Maintenance*

Unit maintenance would be undertaken to meet manufacturers, inspection agency and unit specific requirements. An inspection twelve months after commissioning is an anticipated requirement. Unit specific maintenance cycles will then be developed on the basis of the needs.

3.12.2.4 *Well Workovers*

After several years of operation, it may be necessary to bring in a “workover” rig to improve the flow of the production and injection wells, remove scale, or replace a downhole pump in a production well. This rig would be smaller than the rotary rig used for the production well, no bigger than 60 to 80-tons. The mast for the rig would be approximately 20 feet high when erected.

3.12.2.5 *Workforce*

During the operation phase, the plant will require a workforce of approximately 4-6 people. The makeup and requirements of the workforce are still being defined.

3.12.3 *Decommissioning*

As previously stated, the design life of the Plant shall be 30 years and the design life for all buildings shall be 50 years. Although there are no plans for decommissioning, continuing operations could require modifications to address future reservoir conditions and equipment requirements.

Although geothermal fluids will be reinjected back into the reservoir, they may experience reservoir temperature decline if the volume of the reservoir is small or if production exceeds the ability of the reservoir to recover from the heat extraction process. DGDC would assume all responsibility for continued responsible operations, or, if desired, decommission in accordance with applicable guidance and regulations at the time.

3.13 *Alternative Analysis*

As previously mentioned, as part of the feasibility campaign for this Project, wells were drilled at multiple locations in the area. Based on the results of well testing, the production well WW-P1 was selected. The

Dominica Geothermal Development ESIA of 2018 included an alternatives analysis for the project where multiple scenarios were laid out. This included multiple locations for the Plant (once the production well was selected), as shown in Figure 3-12, and multiple locations for the reinjection wells and reinjection pipelines, as shown in Figure 3-13.




Figure 3-12: Power Plant Location Alternatives




Figure 3-13: Original ReInjection Wells and Pipeline Alternatives

Based on the alternatives analysis performed as part of that ESIA, which included technical and non-technical considerations and public meetings to discuss the alternatives for the projects and to get the community’s opinion, a preferred option was selected for the location of the plant. The preferred option had the least number of residential receptors and was in an area of already modified habitat. The alternatives for reinjection, although discussed, could not be finalized since it was determined defining this location would require additional geotechnical assessments and could only be finalized once the preliminary engineering design was ready.

After the completion of the 2018 ESIA, the original alternatives for the reinjection wells and pipelines proved to be financially unfeasible, so new studies were carried out on a new alternative general area. This general area included several new locations for the reinjection well, much closer to the selected production well and plant, as shown in Figure 3-14.




Figure 3-14: Latest ReInjection Well Pads and Pipeline Alternatives

This most recent alternatives analysis provides the basis for the current location of the reInjection pad and pipeline presented in this ESIA Addendum.

4. IMPACT ASSESSMENT METHODOLOGY

4.1 General Methodology

The primary purpose of an ESIA is to predict the impacts resulting from the proposed project. Impacts can be direct, indirect, or induced, as defined in the Table 4-1.

Table 4-1: Impact Designation Definitions

Designation	Definitions
Direct	Impacts that result from a direct interaction between the Project and a resource/receptor (e.g., between disturbance of a plot of land and the habitats on that plot of land that are affected).
Indirect	Impacts that follow from the direct interactions between the Project and its environment as a result of subsequent interactions within the environment (e.g., viability of a species population resulting from loss of part of a habitat as a result of the Project occupying a plot of land).
Induced	Impacts that result from other activities (which are not part of the Project) that happen as a consequence of the Project (e.g., influx of camp followers resulting from the presence of a large Project workforce).
Cumulative	Impacts that result from the successive, incremental, and/or combined effects of an action, project, or activity added to other existing, planned, and/or reasonably anticipated actions, projects, or activities. For practical reasons, the identification, assessment, and management of cumulative impacts are limited to those effects generally recognized as important on the basis of scientific concern and/or concerns of Project-Affected Communities

Source: ERM, 2020

The assessment of impacts proceeds through an iterative process that considers four questions as illustrated in Figure 4-1.




Figure 4-1: Impact Prediction and Evaluation Process

These questions are expanded in Steps 1 through 4 below.

Step 1: Predict Impacts

An ESIA evaluates potential project impacts by predicting and quantifying to the extent possible the magnitude of impacts on resources (e.g., water and air) or receptors (e.g., people, communities, wildlife species, habitats). Magnitude is a function of the following impact characteristics:

- Type of impact (i.e., direct, indirect, induced);
- Nature of the change (what is affected and how);
- Size, scale, or intensity;
- Geographical extent and distribution (e.g., local, regional, international); and
- Duration and/or frequency (e.g., temporary, short term, long term, permanent).

Magnitude describes the actual change that is predicted to occur in the resource or receptor. The magnitude of an impact takes into account all the various dimensions of a particular impact in order to make a determination as to where the impact falls on the spectrum (in the case of adverse impacts) from *Negligible* to *Large*. Some impacts can result in changes to the environment that may be immeasurable, undetectable, or within the range of normal natural variation. Such changes can be regarded as essentially having no impact, and are thus characterized as having a *Negligible* magnitude. In determining the magnitude of impacts on resources and receptors, embedded controls (i.e., physical or procedural controls that are planned as part of the project design) are taken into consideration (e.g., the magnitude of impacts on stream water quality from construction take into consideration the effectiveness of proposed sediment and erosion control measures).

In addition to characterizing the magnitude of impact, the sensitivity/vulnerability/importance of the impacted resource/receptor is characterized. There is a range of factors taken into account when defining the sensitivity/vulnerability/importance of the resource/receptor. Where the resource is physical (e.g., a waterbody), its sensitivity (to change) and importance (on a local, national, and international scale) are considered. Where the resource/receptor is biological or cultural (e.g., the marine environment or a coral reef), its importance (e.g., its local, regional, national, or international importance) and its sensitivity to the specific type of impact are considered. Where the receptor is human, the vulnerability of the individual, community, or wider societal group is considered. Other factors may also be considered when characterizing sensitivity/vulnerability/importance, such as legal protection, government policy, stakeholder views, and economic value.

As in the case of magnitude, the sensitivity/vulnerability/importance designations themselves are universally consistent (i.e., *Low*, *Medium*, and *High*), but the definitions for these designations will vary on a resource/receptor basis.

Step 2: Evaluate Impacts

An ESIA evaluates the significance of a potential project impact by considering, in combination, the magnitude of the impact and the sensitivity/vulnerability/importance of the impacted resource or receptor. The assignment of a significance rating facilitates decision-makers and stakeholders to understand how much weight will be given to the issue in their process. In the case of positive impacts, the significance is assigned as *Positive*.

Significance was assigned for each impact using the matrix shown in Table 4-2. This matrix applies universally to all resources/receptors.

Table 4-2: Evaluation of Significance of Impacts

Impact Significance Matrix		Sensitivity / Vulnerability / Importance of Resource/Receptor		
		Low	Medium	High
Negative Impacts				
Magnitude of Impact	Negligible	Negligible	Negligible	Negligible
	Small	Negligible	Minor	Moderate
	Medium	Minor	Moderate	Major
	Large	Moderate	Major	Major
Positive Impacts				
Magnitude of Impact	N/A	Positive	Positive	Positive

Source: ERM, 2020.

In terms of what the various significance designations represent, the following considerations are provided:

- An impact of *Negligible* significance is one where a resource/receptor (including people) will not be affected by a particular activity, or the predicted effect is deemed to be imperceptible or is indistinguishable from natural background variations.
- An impact of *Minor* significance is one where a resource/receptor will experience a noticeable effect, but the impact magnitude is sufficiently *Small* (with or without mitigation) and/or the resource/receptor is of *Low* sensitivity/vulnerability/importance. In either case, the magnitude will be well within applicable standards.
- An impact of *Moderate* significance has an impact magnitude that is within applicable standards but falls somewhere in the range from a threshold below which the impact is *Minor*, up to a level that might be just short of breaching a legal limit. To design an activity so that its effects only just avoid breaking a law and/or cause a major impact is not best practice. The emphasis for *Moderate* impacts is therefore on demonstrating that the impact has been reduced to a level that is as low as reasonably practicable. This does not necessarily mean that impacts of *Moderate* significance have to be reduced to *Minor*, but rather that *Moderate* impacts are being managed effectively and efficiently.
- An impact of *Major* significance is one where an accepted limit or standard may be exceeded, or *Large* magnitude impacts occur to highly valued/sensitive resources/receptors.
- An impact of *Positive* significance is one that has been identified as having a positive effect on the receptor/resource. Generally, this ESIA does not attempt to characterize magnitude for positive impacts.

A goal of an impact assessment is to get to a position where a project does not have any *Major* residual impacts (i.e., after mitigation measures are considered), certainly not ones that will endure into the long term or extend over a large area. However, for some aspects, there may be *Major* residual impacts after all practicable mitigation options have been exhausted. An example might be the visual impact of a facility. It is then the function of the decision-makers and stakeholders to weigh such negative factors against the positive ones, such as employment, in coming to a decision on a project.

Step 3: Mitigation and Enhancement

An ESIA process aims to ensure that project decisions are made in full knowledge of their likely impacts on the environment and society. A vital step within the process for this ESIA was therefore the identification of measures that could be taken to mitigate potential impacts of the Nevis Geothermal Exploration Project (the Project).

The process involved identifying where potentially significant impacts could occur and identifying ways of mitigating those impacts as far as reasonably possible. A mitigation hierarchy was used in which preference is always given to trying to avoid or minimize the impact before considering other types of mitigation (i.e., remedy, compensate, offset). The conventional preferred hierarchy of measures, which was followed in this ESIA, is provided below:

- Avoid —remove the source of the impact;
- Minimize —reduce the magnitude of the impact;
- Mitigate—“repair” the results of the impact after it has occurred; and
- Compensate/offset—address the loss or change to a resource by replacing the loss/change in kind or with a different resource of equal value.

Step 4: Residual Impacts

Once mitigation measures are agreed to, the next step in the impact assessment process is to determine the residual impact significance. Residual impacts are the impacts that are predicted to remain after both embedded controls and committed mitigation has been taken into consideration. In most cases, the sensitivity/vulnerability/importance of a receptor is unaffected by proposed mitigation measures; the mitigation measure is typically intended to reduce the magnitude of a predicted impact, thereby reducing its overall significance.

5. BIOLOGICAL RESOURCES UPDATE

5.1 Biological Setting

Dominica is a volcanic island 46 km in length with a central mountain ridge running from Cape Melville in the north to the cliffs in the south. The island contains the most extensive “almost” undisturbed tropical forest in the Lesser Antilles or Leeward Islands in the Caribbean. Rugged volcanic mountains covered in moist tropical forest characterize this island, with 50 peaks reaching up to 1,446 m at its highest peak of Morne Diablotins.

Dominica suffered peak deforestation due to land conversion for agriculture in the 19th century, however in the past decade reports show low deforestation (FAO, 2015; Steiner, 2003). Despite this, the island of Dominica, as many of the Leeward/lesser Antilles islands, support a significant lack of well-developed rain forest (Beard, 1949). The lack of primary rainforest is attributed to the periodic stand damage from passing hurricanes, which results in uneven forest canopy and an emerging second growth forest habitat. The effect of storms continually molds the forest cover and maintains much of the forest in a pre-climax condition.

Since 1979, tropical storms and hurricanes which have impacted Dominica include David (1979), Gert (1981), Gilbert (1988), Hugo (1989), Iris (1995), Marilyn (1995), Hortense (1996), Lenny (1999), Dean (2007) and Maria (2017) (Jacobs, 2018). Hurricane David in 1979 did significant damage to the forest by damaging 60% of the tropical forests in the southern half of the island. Most of the trees were debranched causing significant loss of habitat and food supplies for wildlife species, which resulted in wildlife mortality (Edwards, 2018). In 2010, the island of Dominica had 70.7 kilohectare (kha) of tree cover, extending over 94% of its land area; with the landfall of Hurricane Marine in 2017 almost 15 kha of primary humid forest was lost, decreasing forest cover by 56%⁶.

The Project sits within the Roseau Valley, which is characterized by tropical rainforest, mountain forest, semi-deciduous forest, fumarole vegetation, marshlands, savannas, abandoned cropland, agricultural land and urban landscape, as described in the reports by Caraïbes Environnement Développement & Coll (2015a and b). Agricultural products include bananas, limes and root crops (Edwards, 2018).

5.1.1 Biotic Area of Influence

The biotic area of influence (BAOI) includes the Project area and the surrounding area that has the potential to be impacted by noise and light from the proposed power plant, existing and proposed access roads, the reinjection well, Pad A, production well P1, and the reinjection pipeline (see Figure 5-1). According to Bayer *et. al.*, (2013) and the IFC Environmental, Health, and Safety (EHS) guidelines for Geothermal Power Generation, noise due to drilling and steam venting activities may reach up to 100-120 A-weighted decibels (dBA). Based on IFC EHS noise nighttime guidelines for residential areas of 45 dBA, the BAOI has been established to include a radius of 600 m to capture noise levels as it attenuates to 45 dBA from potential Project noise sources. This distance was established with the assumption that total noise level is 100 dBA at 1 m. The total BAOI is an area of approximately 290 hectares (ha). Unlike humans, there are no standardized noise limits for fauna.

⁶ <https://www.globalforestwatch.org/dashboards/country/DMA/>




Figure 5-1: Biotic Area of Influence Based on Potential Noise Impacts

5.1.2 Natural Habitat and Modified Habitat Assessment

Within the Project BAOI, the major vegetation types include primary rainforest, secondary rainforest experiencing regrowth from abandoned croplands and damage from Hurricane Maria, agricultural land and urban areas (Figure 5-2). In Table 5-1, these vegetation types have been classified by natural and modified, as per IFC Performance Standard (PS) 6⁷. ERM used current and historical satellite imagery of forest cover and global forest watch data (Hansen et. al., 2010) to identify areas of natural and modified habitat in the BAOI.

⁷ IFC PS6 defines Modified Habitats are those that “contain a large proportion of plant and/or animal species of non-native origin, and/or where human activity has substantially modified an area’s primary ecological functions and species composition.” Natural Habitats are defined as “areas composed of viable assemblages of plant and/or animal species of largely native origin, and/or where human activity has not essentially modified an area’s primary ecological functions and species composition.” As per Guidance Note 39, “Natural habitats are not to be interpreted as untouched or pristine habitats. It is likely that the majority of habitats designated as natural will have undergone some degree of historical or recent anthropogenic impact.”




Figure 5-2: Land Cover Types Present in the BAOI

Natural habitat within the BAOI include primary forest and secondary regrowth after hurricane Maria. Land cover analysis distinguished forest into three categories based on densities: low, medium and high. Each forest type represents 21.7 %, 12.9%, and 41.4 % of the BAOI, respectively (Table 5-1, Figure 5-3). The forest has seen major impacts from the recent hurricane; however, much of these areas are experiencing secondary regrowth that maintains connectivity and can support ecological functions of the rainforest ecosystem. Low density forest represents a majority of the secondary forest experiencing regrowth after Hurricane Maria and isolated fragment areas, whereas abandoned agricultural plots with regrowth vegetation yet minimal forest canopy were classified as modified. Modified habitats include abandoned cropland with some secondary vegetation, open pasture grasslands, agricultural land, urban developed areas, bare soil areas, and roads (Table 5-1, Figure 5-3).

Table 5-1: Natural and Modified Habitat types within the BAOI

Habitat Type	IFC PS Habitat Classification	Area (hectares)	Percent (%)
Water bodies	Natural	10.27	3.5
High density forest	Natural	120.03	41.4
Medium density forest	Natural	37.42	12.9
Low density forest	Natural	63.08	21.7
Grassland/cropland	Modified	42.2	14.5
Bare soil	Modified	6.54	2.3

Habitat Type	IFC PS Habitat Classification	Area (hectares)	Percent (%)
Road	Modified	5.58	1.9
Urban developed areas	Modified	5.07	1.7
Total		290.19	100

The majority of the BAOI is covered in high density forest followed by low density forest, as much of the Project is located on the forest landscape of the south eastern periphery of the village of Laudat, nearby to the Morne Trois Pitons National Protected Area. In total 59 ha (20.5%) of modified habitat and 230 ha (79.5%) of natural habitat make up the BAOI. According to the analysis there is no critical natural habitat in the BAOI (see Section 5.2 for further information).




Figure 5-3: Natural and Modified Habitat in the BAOI

Section 5.4 reviews impact and mitigation measures in relation to the amount of natural and modified habitat impacted by the Project footprint. The Project footprint will result in direct impacts to approximately 4.61 ha (not including existing well pad P1 or the existing road).

5.1.3 Protected Areas

The Government of Dominica has established three national parks and two forest reserves to conserve the biodiversity of the island. Morne Trois Pitons National Park was the first unit of the National Park system to be established in July 1975, followed by Morne Diablotin National Park in 2000 under the

National Parks and Protected Areas Act. In 1997, Morne Trois Pitons National Park was enlisted by UNESCO as a “World Heritage Site (WHS)” (see Table 5-2).

Of these, Morne Trois Pitons National Park, the closest protected area, lies approximately 500 m upstream from the proposed Project infrastructure.

Table 5-2: Protected Areas on Dominica

Protected Area	Area (km ²)	Site Status	IUCN Status ^a
Morne Trois Pitons National Park	72.38	National Park	II
Morne Diablotin National Park	33.35	National Park	II
Central Forest Reserve	4.1	Forest Reserve	-
Northern Forest Reserve	54.75	Forest Reserve	-
Cabrits National Park	53.88	National Park/ Marine Reserve	-

Km² = square kilometer.

IUCN = International Union for Conservation of Nature.

^aRefers to internationally recognized protected area classification system by IUCN (2013)⁸.

Category II protected areas are large natural or near natural areas set aside to protect large-scale ecological processes, along with the complement of species and ecosystems characteristic of the area, which also provide a foundation for environmentally and culturally compatible, spiritual, scientific, educational, recreational, and visitor opportunities.

5.1.4 Ecosystem Services

According to the IFC PS6, “protecting and conserving biodiversity, maintaining ecosystem services and sustainably managing living natural resources are fundamental to sustainable development.” Ecosystem services are “the benefits that people, including businesses, derive from ecosystems.” Ecosystem services are organized into four types:

- Provisioning services, which are products people obtain from ecosystems;
- Regulating services, which are benefits people obtain from the regulation of ecosystem processes;
- Cultural services, which are nonmaterial benefits people obtain from ecosystems; and
- Supporting services, which are the natural processes that maintain other services.

Ecosystem services from the tropical forest of Dominica include provisioning services for food in regard to wildlife hunting, and wood for the use of building materials and charcoal production. The forested areas provide supporting and regulating services for carbon management, watershed management, freshwater, and erosion protection services. Recreational and cultural services are provided for locals and tourism through the National park and WHS for the connectivity and beauty of the rainforest ecosystem and natural pools. In addition, the rainforest habitat provides habitat for wildlife, such as migrating birds and endemic bats.

⁸ IUCN. 2013. Guidelines for applying protected area management categories including IUCN WCPA best practice guidance on recognizing protected areas and assigning management categories and governance types. <https://www.iucn.org/theme/protected-areas/about/protected-area-categories>

5.2 Critical Habitat Assessment Screening

The Jacobs ESIA (2018) Critical Habitat (CH) Screening assessment (Jacobs ESIA, Vol 5 Technical Appendices) evaluated against IFC PS6 CH Criteria, providing a detailed CH analysis for the Red-necked parrot (*Amazona arausiaca*, *Vulnerable IUCN*). In total, the CH report screened six species based on threat status and endemism. These include the following species:

- Martinique Robber frog (“tink frog”), *Eleutherodactylus martincensis* - IUCN Near Threatened (NT);
- Dominican ground lizard (*Ameiva fuscata*), Not Assessed;
- Dominica anole, *Anolis oculatus* – IUCN Least Concern (LC);
- Blue-headed hummingbird, *Cyanophaea bicolor* – IUCN LC; and
- Plumbeous warbler, *Setophaga plumbea* – IUCN LC.

The Jacobs CH screening assessment evaluated these species by CH criteria Tier 1 and Tier 2, which have since been updated. Ten individuals of the Red-necked Amazon were observed feeding within the Project area of the reinjection pipeline, with the updated IFC PS 6 (2019) Critical Habitat Criterion, the Red-necked Amazon is a possible CH trigger for Criteria 2 and should be considered a priority species for conservation.

This section is intended to supplement the Jacobs CH screening with species that were not included; however, which are relevant and potentially CH triggering according to The Biodiversity Consultancy (TBC) Biodiversity Screening and Review for the Wotton Waven Geothermal Project (TBC, 2020; included IBAT screening). The TBC report included a list of 28 species that may trigger CH. The below species were selected from this list for further evaluation due to their threat status, restricted range, recorded presence in the direct AOI of the wells and reinjection pipeline route, or sensitivity to potential indirect threats by the Project, such as hunting.

Data evaluated within this CH screening include the Jacobs Dominica Geothermal Development ESIA (2018), the ECLIPSE Drilling Geothermal Well RV-12 and Reinjection Route ESIA (2020), and The Biodiversity Consultancy (TBC) Biodiversity Screening and additional studies found when conducting a literature review.

The supplemental CH Assessment Screening evaluates species and habitats potentially present in the BAOI that may trigger Critical Habitat as outlined in the PS Guidance Note 6 – Biodiversity Conservation and Sustainable Management of Living Natural Resources (version June 2019). The following sections evaluate three species that were not included in the Jacobs CH screening. Here, we evaluate these species for Criteria 1-3 (threatened, restricted range and migratory/congregatory species).

- Mountain Chicken, *Leptodactylus fallax* - IUCN Critically Endangered (CR);
- Black-capped Petrel, *Pterodroma hasitata* - IUCN Endangered (EN); and
- Dominican Myotis, *Myotis dominicensis* - IUCN Vulnerable (VU).

5.2.1 Mountain Chicken, *Leptodactylus fallax* - IUCN CR

Leptodactylus fallax is one of the most threatened frogs in the Caribbean region and the world (Daltry, 2002). This terrestrial species currently occurs only on the Islands of Dominica and Montserrat up to an elevation of 330-400 m. The International Union for Conservation of Nature (IUCN) lists the Mountain Chicken as Critically Endangered because of two major population declines that occurred on Dominica between 2002-2004 and Montserrat between 2007-2017. Additionally, the two islands support only a small number of mature individuals in each subpopulation with less than 50. Its range is restricted on the western coast of Dominica to an area of around 40 km² and to less than 1 km² on Montserrat, with an

extent of occurrence (EOO) of 1,568 km² and its area of occupancy (AOO) is approximately 10 km² (IUCN, 2020). Reports from the Forestry and Wildlife division suggest that mountain chickens occupy scattered areas totaling about 25-50 km² (Daltry, 2002).

On Dominica it was formerly abundant in suitable habitat, despite heavy exploitation for food with an estimated annual harvest of 8,000-36,000 animals. Reports suggest that the subpopulation suffered a decline of greater than 85% during an 18-month period (2002-2004) due to chytridiomycosis (*Batrachochytrium dendrobatidis*). However, recent field studies report Bd-negative results from *L. fallax*, suggesting a degree of nascent post-epidemic recovery (Hudson et. al., 2016). The Dominican subpopulation is estimated to contain around 130 individuals (both adults and juveniles), based on continuous monitoring efforts (Jameson et. al., 2019).

L. fallax inhabits dense secondary vegetation to old growth forest, hill forest, gauts and has been found in plantations. Optimal habitat for *L. fallax* is likely to be undisturbed, mature forest with permanent watercourses (Jameson et. al., 2019). This nocturnal species hides in burrows during the day in moist forest and appears to be associated with certain soil types that allow the digging of nests. This species lays eggs in foam nests at the bottom of burrows, in which the tadpoles develop terrestrially, not in water (IUCN, 2020).

Ongoing threats include habitat loss for land development and logging, invasive species such as the cane toad and Johnston's whistling frog, volcanic activity and hunting for exploitation. In 1999, the Government of Dominica imposed a total ban on the hunting of *L. fallax* and recently enacted an indefinite ban on the hunting of this species as of April 2004.

During baseline diurnal and nocturnal surveys for amphibians in 2017 (Jacobs, 2018) and in July and August of 2020 (Eclipse, 2020), *L. fallax* was not recorded within the BAOI. The Project components lie at a higher elevation (above 500 m); therefore, the BAOI does not support habitat for this species. *Based on this information and recorded observations from published literature studies, the Project is not considered to be in Critical Habitat for this species under Criteria 1 or 2.*

5.2.2 Black-capped Petrel, *Pterodroma hasitata* - IUCN EN

The Black-capped Petrel (*Pterodroma hasitata*) is classified as Endangered because it has a very small, fragmented and declining breeding range and population. Declines are likely due to ongoing threats of habitat loss and degradation, natural disasters, hunting and invasive predators (IUCN, 2020). The Petrel is a nocturnal seabird and a Caribbean endemic; it occurs within the inter-island regions, straits, and offshore zones of both the Greater and Lesser Antilles. IUCN reports population estimates of no more than 1,000 breeding pairs, perhaps as few as 500, and a total population of 2,000–4,000 birds with an AOO of 20 km² and an EOO of 9,060,000 km² (2020). Breeding habitat is located at high elevations (>1,500 m), and most are in inaccessible areas with steep slopes, and heavily forested.

Radar surveys conducted in Dominica in January 2015 strongly suggest that Black-capped Petrels persist on the remote peaks of Dominica; hundreds of petrel-like targets were recorded over 17 separate coastal and inland flight corridors, and eight individual Black-capped Petrels were observed over five locations (Brown, 2015). These data, when coupled with recent observations of downed Black-capped Petrels on the island, suggests that there are still individuals breeding on the island, although the last confirmed nesting date was 1862. A recent acoustic survey (McKown, 2016) deployed acoustic recorders in three survey suites along Dominica from January to August 2015 and detected no Petrel calls. Adults have been reported on the summit of Morne Micotrin; however, no active nests have ever been recorded (Leopold et. al., 2019).

Baseline bird surveys in 2017 (Jacobs, 2018) and in July and August of 2020 (Eclipse, 2020) did not record the presence of the Black-capped Petrel. However, nocturnal radar surveys conducted in 2015 by

the research organization EPIC – Environmental Protection in the Caribbean, in collaboration with the Forestry, Wildlife and Parks Division, confirmed the presence of the Black-capped Petrel in the airspace over Laudat. *Based on this information and recorded observations from published literature studies, the Project is not likely to be in Critical Habitat for this species under Criteria 1.*

5.2.3 Dominican Myotis, *Myotis dominicensis* - IUCN VU

The Dominican Myotis (*Myotis dominicensis*) is classified as Vulnerable because it has a very small range known from three locations on two Caribbean islands (Dominica and Guadalupe). Its EOO is around 6,000 km², but it is not found throughout the islands it inhabits. Its habitat is declining due to expansion of human activities and hurricanes. The most recent registered record from the Global Biodiversity Information Facility for the island of Dominica is from 1986, while there are no confirmed records for the island of Guadalupe.

Historical ecological studies of the bats of Dominica recorded *M. dominicensis* from within “Glo Manioc Cave”, a cave along a hillside beside the Layou River tributary, mist nests along Clark Hall Estate and the Layou River, and a church bell tower in Portsmouth, in 1929, 1966 and 1978 respectively (Genoways et al., 2001). These records indicate that this insectivorous bat is a cavity-roosting species that utilizes caves primarily, and tree roosts. Genoways et al. (2001) suggest *M. dominicensis* is broadly distributed and common, but there is little recent information. In 2016, mist netting surveys report 22 captures of this species from private land near Rosalie, southeast of the Project, and 33 from in 2017. After Hurricane Maria, only nine and sixteen captures were reported for 2018 and 2019, respectively. Additionally to 3 *M. dominicensis* captures were recorded from Emerald pool, located north of the Project near Pont Casse (Sims pers. comm., unpublished data).

There are no published global or local Dominican population estimates. However, the 2016-2019 bat surveys and records estimate an average relative abundance of 0.26 bats captured/net-night at Rosalie and 0.05 at the Emerald Pool (Sims pers. comm.). However, insectivorous species such as *Myotis* are more difficult to capture as they fly higher to forage and are better at detecting mist nets than frugivores and nectarivores. Forest area that supports foraging habitat for *M. dominicensis* is considered potential suitable roosting habitat (Sims pers. comm.).

Baseline surveys in 2017 (Jacobs, 2018) recorded several species of unidentified insectivorous and frugivorous bat species. The Eclipse ESIA (2020) reported that the equipment and expertise for scientific monitoring of bats in Dominica were nonexistent for the 2020 surveys, albeit, locals reported that the several bat species frequent the BAOI. *Considering this species has been recorded in areas outside of Laudat and utilizes cave habitat for roosting primarily, the Project is unlikely to be in Critical Habitat for this species under Criteria 1 and 2.* However, if future surveys prior to construction record the species or tree roosts within the BAOI, then Critical Habitat status should be re-assessed.

5.2.4 Conclusions

Based on Critical Habitat criterion 1-3 outlined in the IFC Guidance Note 6 (June 2019), There are several threatened and restricted range species that may occur within the Project BAOI, as listed in Table 1 of the TBC biodiversity screening (2020). However, based on occurrence records, population, and ecological habitat preferences of *L. fallax*, *P. hasitata*, and *M. dominicensis*, it is unlikely that these species meet Criteria 1-3 for CH. With the recorded occurrence of ten individuals of the Red-necked Amazon, this species should be considered a priority species for biodiversity monitoring, conservation efforts, and habitat restoration activities.

Based on Critical Habitat criterion 4, the TBC biodiversity screening (2020) and Section 5.1.2 of this report, concur that the Project components are *unlikely* to trigger Critical Habitat based on sensitive and

unique ecosystems, as the secondary growth natural habitat that will be directly impacted by the Project is not considered montane elfin or montane cloud forest (TBC, 2020; Figure 4, page 15).

Therefore, considering the above CH evaluations, as well as the direct loss of habitat by the Project facilities and associated minor geothermal impacts, ERM do not believe it is a concern for critical habitat. If additional field work documents the presence of other threatened and/or restricted range species, ERM recommend CH be re-evaluated.

5.3 Morne Trois World Heritage Site

The Morne Trois Pitons National Park (MTPNP) was established in 1975 under the National Parks and Protected Areas Act and in 1997 established as a UNESCO World Heritage Site. The Park is in the central portion of southern volcanic complex of the island, covering an estimated 6,900 hectare (ha) (17,000 acres) and contains the most extensive “almost” undisturbed tropical forest in the Lesser Antilles (Figure 5-4). It is characterized by its high ecological biodiversity with rare and unique natural features, a variety of natural attractions and a number of watershed areas and domestic water catchments (Edwards, 2018). The park provides habitat for over 45 species of birds, (including the endemic Imperial Parrot and Red-necked Parrot), two species of frog, crabs and crayfish several species of mammals (bats, agouti, opossum and feral cats), species of freshwater fish, four species of snake, at least five types of lizard and a wide variety of insects and other small invertebrates. Birdlife International considers it an “Important Bird Area” supporting one endangered and one vulnerable species of Parrot (*Amazona imperialis* and *A. arausiaca* respectively), and 15 restricted-range species⁹.

⁹ <http://datazone.birdlife.org/site/factsheet/morne-trois-pitons-national-park-iba-dominica>




Figure 5-4: Map of WHS boundary for Morne Trois Pitons National Park

In June of 2018, the State Party of Dominica (State Party’s Report on the State of Conservation of Morne Trois Pitons National Park) completed a new management plan for the Morne Trois Pitons National Park, which clarified park boundaries, updated buffer zones and proposed a management structure to provide protection and conservation of the National park ecosystems. This management plan fulfills the government’s obligation to establish a buffer zone for the MTPNP WHS as per its international commitment to maintain its status as a WHS. Further, the plan re-establishes and clarifies discrepancies of national park boundaries on the ground.

The proposed buffer zone consists of 1232.3 ha with a varying depth of 152.4 m (500 ft) to 305 m (1000 ft), depending on proximity to residential development. Along the western edge of the MTPNP, the State recommends a 200 m buffer zone; this includes the Park area closest to Laudat and the Project site. Activities within the buffer zone must adhere to the proposed collaborative agreement by the state and participatory stakeholders; these activities must be ecologically and economically sustainable and not compromise the natural resources or ecology of the park (Edwards, 2018). The Project components are 300 m from the buffer zone boundary at its closest point. None of the Project lands or areas fall within the proposed buffer area as illustrated in Figure 5-5.



Figure 5-5: Project Components in Relation to the MTPNP WHS and 200 m Buffer

The BAOI of the Project overlaps with 11.8 ha of the MTPNP WHS and an additional 22.7 ha of the buffer boundary. The direct impacts of vegetation clearance and fragmentation due to Project construction will not reduce the ecological connectivity of the WHS, as the Project direct impacts will occur outside of the WHS. However, based on the BAOI Figure 5-1, noise impacts due to well drilling and steam venting may potentially affect the buffer zone and western perimeter of the WHS. Therefore, mitigation measures are proposed to mitigate potential impacts to the WHS are provided in Section 5.4.1 and in Table 5-4.

5.4 Summary Impacts on Biodiversity

The Jacobs ESIA (2018, Section 13.4) and ECLIPSE ESIA (2020, Section 9.7) identified Project impacts from the geothermal development, reinjection well and pipeline and associated infrastructure. Information within Project Description (Jacobs 2018, Vol 1. Section 3; ECLIPSE 2020, Section 3.), and Terrestrial Ecology Biodiversity Baseline (Jacobs 2018, Section 3.12; ECLIPSE 2020, Section 5.11), were used to assist the evaluation of the potential impacts and their significance.

Potential impacts due to construction and operations phase of the Project may occur within the Project BAOI, which covers approximately 290 ha. The impacts to biodiversity consider the pre-existing state and baseline influencing factors such as modified and previously cleared well pads.

The most significant Project impacts on terrestrial biodiversity would occur during the construction phase, which includes onsite vegetation clearing, an increase in noise and vibrations, the potential to injure or kill wildlife species, and the potential for harassment of flora/fauna by the construction/operation employees. During operations, the most significant Project impact to flora and fauna biodiversity is an unlikely scenario of a well blowout, which would cause additional direct impacts of disturbance, injury and/or mortality of terrestrial wildlife species. Indirect biodiversity impacts to surroundings areas of the WHS,

which include artificial light, hunting, increased human activity, noise, and waste, will be the most significant throughout construction and operations.

The modifications of the Project design will clear a total of approximately 4.6 ha (46,158.5 m²), which includes 2557 m² for the new reinjection well (RVI2), 20,609 m² for the power plant site, 9845 m² along 10 m of reinjection pipeline Right-of-Way (RoW), 7076 m² within the Pad A production well (RVP2) and about 6072 m² along the new access road. Total area of impacts to natural habitat is 2.7 ha, and 1.9 ha of modified habitat (Table 5-3). According to the analysis, there is no critical natural habitat in the BAOI (see Section 5.2 for further information).

Table 5-3. Impacts in Surface Area (m²) to Vegetation Types by Project Component

Vegetation Type	Power Plant	Reinjection Well	Reinjection Pipeline	Access Road to Power Plant	Production Pad A	Total
Water body	0.0	0.0	531.6	0.0	0.0	531.6
High Density Forest	7560.7	0.0	681.6	1814.8	6311.9	16369.0
Medium Density Forest	1533.5	10.5	529.8	350.9	563.4	2988.2
Grassland / Agriculture	6237.5	1637.7	3541.2	1689.0	0.0	13105.3
Barren	2602.2	0.0	541.0	513.7	0.0	3656.9
Developed	395.7	0.0	0.0	58.5	0.0	454.2
Road	1073.2	0.0	380.1	452.1	0.0	1905.4
Low Density Forest	1206.2	908.8	3639.8	1192.7	200.3	7147.8
Modified	10308.6	1637.7	4462.3	2713.3	0.0	19121.9
Natural	10300.4	919.3	5382.9	3358.4	7075.6	27036.6
Total	20,609.0	2557.0	9845.2	6071.7	7075.6	46,158.5

The proposed modifications and updates to the Project design would decrease the impacts of vegetation removal by 5.4 ha (1.4 ha cleared for power plant and 4 ha for the 10 m RoW reinjection pipeline) as discussed in the Jacobs ESIA (2018). Portions of the Power Plant area will be used for a temporary camp and laydown area and will be replanted with native vegetation. The modifications do not change the magnitude of the impact which was considered *Minor*.

With the drilling of an additional production well (Pad A) and reinjection well (RVI2), noise levels will range from 75-110 dBA causing potential impacts of disturbance and injury to wildlife due to construction noise and ground vibrations. These modifications increase the magnitude and significance of the impact to a *Moderate* significance.

5.4.1 Mitigation Measures and Monitoring

Table 5-4 provides a summary of mitigation measures that supplement the measures listed in the Jacobs ESIA (Section 13.4) and ECLIPSE ESIA (Section 9.7.1). Detail information on the mitigation measures monitoring frequency, parameters, including key performance indicators are provided in Appendix A – Biodiversity Management Plan.

Table 5-4: Impacts and Mitigation Measures for Project Modifications and Updates

Impact	Sensitivity	Magnitude	Duration	Pre- mitigation Impact Significance	Mitigation Measure	Residual impact Significance
<i>Direct:</i> Ground works would result in the direct loss and disturbance of vegetation (loss of 2.7 of primary and secondary rainforest, natural habitat)	High	Medium	Permanent	Moderate	<ul style="list-style-type: none"> ■ Demarcate construction areas. ■ Revegetate temporary laydown areas with native species. ■ Implement best practices when clearing vegetation and trees and provide wood to community for use as fences or for charcoal production. ■ Implement a restoration and reforestation measures in areas impacted by Hurricane Maria, focusing on stabilizing bare slopes and riparian forests. 	Minor
<i>Direct:</i> Mortality and Injury to fauna due vegetation clearing and habitat loss	Medium	Medium	Short-term	Minor	<ul style="list-style-type: none"> ■ Conduct pre construction field screening to repel, rescue and relocate fauna from area of direct influence. ■ Implement a <i>chytrid</i> protocol when handling of amphibians and clean bottom of boots after construction activity to avoid spreading Chytrid fungus. ■ Avoid clearing vegetation during bird breeding season. 	Negligible

<p><i>Direct:</i> Habitat loss for wildlife due to construction within the road improvement/ expansion locations, reinjection and production well pads, reinjection pipeline, power plant area and immediate surrounding areas</p>	<p>Medium</p>	<p>Medium</p>	<p>Long term/ Permanent</p>	<p>Minor</p>	<ul style="list-style-type: none"> ■ Minimize Project footprint to the maximum extent feasible. ■ Avoid removal of trees where possible. ■ Revegetate temporary laydown areas. 	<p>Minor</p>
<p><i>Indirect:</i> Operation of the drill rig and related drilling and testing activities would generate air emissions, the accumulation of which could inhibit growth of vegetation</p>	<p>Medium</p>	<p>Negligible</p>	<p>Medium-term</p>	<p>Negligible</p>	<ul style="list-style-type: none"> ■ Monitor air quality to meet IFC EHS standards. ■ Implement air quality management plan. 	<p>Negligible</p>
<p><i>Indirect:</i> During construction of the drill rig, blow testing, and other construction activities, the Project will generate high noise levels causing wildlife displacement and mask acoustic calling, thus affecting mating and feeding behaviors, within the BAOI.</p>	<p>Medium</p>	<p>Medium</p>	<p>Medium-term</p>	<p>Moderate</p>	<ul style="list-style-type: none"> ■ Implement pre-construction surveys to relocate ground dwelling wildlife from the activity sites to the extent practicable. ■ Assess the need of a shock absorber, or damper on the drill ■ Install silencers to vehicles and heavy equipment. ■ Survey areas for existing bat roosts and implement humane physical or acoustic exclusion measures to keep bats away from site. ■ Avoid drilling and steam blow testing, as feasible, 	<p>Minor</p>

					<p>between April and August to avoid impacts on maternity colonies of bats, and bird breeding season.</p> <ul style="list-style-type: none"> ■ Evaluate need to install temporary sound barriers, if construction is outside of hurricane season. ■ 	
<i>Direct:</i> Fragmentation of habitat and reduction of ecological connectivity	Medium	Small	Permanent	Minor	<ul style="list-style-type: none"> ■ Construct overpass and underpasses along pipeline and river crossings. ■ Revegetate temporary laydown areas and temporary RoW of pipeline. 	Negligible
<i>Direct:</i> Mortality or injury to fauna due to open geothermal brine ponds	Medium	Small	Long-term	Minor	<ul style="list-style-type: none"> ■ Installation of screen or nets over the brine collection pond to prevent wildlife contact with fluids. 	Negligible
<i>Indirect:</i> Project-related activities would result in the temporary degradation of habitat quality within the nearby MTPNP WHS	High	Small	Long-term	Moderate	<ul style="list-style-type: none"> ■ Ensure Project areas are appropriately demarcated. ■ Ban hunting and harassment of wildlife. ■ Minimize the amount of artificial lighting used at the pad sites, use directional lighting (downward facing lighting) and direction 	Negligible

					<p>accessories, and avoid the use of ultraviolet light.</p> <ul style="list-style-type: none"> ■ Avoid drilling during bird and bat breeding and nesting season. ■ Evaluate the need to install sound barriers outside of hurricane season. ■ Implement waste management plan. 	
--	--	--	--	--	---	--

Further monitoring to assess effectiveness of mitigation measures and evaluate impacts on flora, fauna, and the MTPNP WHS. Monitoring should include the following:

- Monitoring health of water courses and riparian areas during and after construction (refer to Water Management Plan, Appendix A);
- Monitoring of flora and fauna, with special focus on Red-necked Amazon (*Amazona arausiaca*) prior to and after construction (see Biodiversity Management Plan, Appendix A);
- Monitor habitat use of wildlife and potential impacts to MTPNP WHS with areas in BAOI; and
- Monitor reforestation and restoration efforts annually.


6. SOCIOECONOMIC RESOURCES UPDATE

6.1 Socioeconomic Baseline

6.1.1 Migration

Dominica has been ranked among the top five countries in the world having the highest rates of net migration, with a record high in 1989 of -32.7 per thousand of the population. Over the last hundred years, Dominicans have migrated in ever-increasing numbers in search of employment opportunities, as was the case in the early nineteenth and twentieth centuries, and more recently in pursuit of higher education (T. Fontaine, *Tracing the Diaspora's Involvement in the Development of a Nation: The Case of Dominica*). In fact, Dominica has even developed a Diaspora Policy to tap into potential in Diaspora communities and promote the social and economic development of all citizens to encourage their partnership in the development of the country (Government of the Commonwealth of Dominica, Ministry of Trade, Employment, Industry and Diaspora Affairs, Diaspora Policy, 2010).


However, it should be noted that in recent years Dominica's migration rates have decreased (see Figure 6-1). According to UNICEF's Migration Profile for Dominica, the island's crude net migration rate has changed from -21.43 in the late 1980s to -2.80 between 2010 and 2015. This translates to a net migration of -1 person per 1,000 inhabitants for the period 2010-2015. In absolute numbers, data from the World Bank Group and United Nations Department of Economic and Social Affairs shows that in 2018, Dominica's total population was 73,543 and the total immigrant population was 7,000 (or 9.5% of the total population), with 3,325 (or 4.5%) constituting the female immigrant population.



Source: UNICEF Migration Profiles, Dominica.


Figure 6-1 Migration Rate Dominica (1985-2015)

Figures 6-2 and 6-3 show total population by age and sex vs migrant stock by age and sex for 2013 in Dominica.



Source: UNICEF Migration Profiles, Dominica

Figure 6-2 Total Population by Age, Sex and Origin (2013)



Source: UNICEF Migration Profiles, Dominica.

Figure 6-3 Migrant Stock by Age and Sex (2013)

Tables 6-1 and 6-2 show migrant stock by origin and destination for 2013 for the top five countries or areas of origin / destination.

Table 6-1 Migrant Stock by Origin (2013)

Countries or Areas	Total
Guadeloupe	1,403
United Kingdom of Great Britain and Northern Ireland	587
United States of America	577
Antigua and Barbuda	469
Trinidad and Tobago	283
Total	3,319

Source: UNICEF Migration Profiles, Dominica

Table 6-2 Migrant Stock by Destination (2013)

Countries or Areas	Total
USA	35,425
United States Virgin Islands	6,547
France	6,336
United Kingdom of Great Britain and Northern Ireland	5,043
Antigua and Barbuda	4,624
Total	57,975

Source: UNICEF Migration Profiles, Dominica.

It is important to keep in mind that the crisis in Dominica after Hurricane Maria highlighted the importance of accounting for the migration aspects of disaster events, as its effects on mobility patterns were made evident through the immediate need to track displaced persons, and the subsequent need to recruit foreign labor to assist with reconstruction efforts; however, the long-term effects of this crisis have not yet been determined with certainty (International Organization for Migration, Migration Governance in the Caribbean: Report on the Island States of the Commonwealth Caribbean, 2018).

Lastly, the Dominica Association of Industry and Commerce (DAIC) has recently discussed the existing negative perceptions of immigrants in Dominica, emphasizing the positive impact that immigrants can have on Dominica through economic consumption.¹⁰

6.1.2 Gender

The 2018 Jacobs ESIA includes information on gender by population and women's perceptions of priority needs post-Hurricane Maria. This section will provide additional details on gender in Dominica.

The Dominica Country Gender Assessment (CGA), commissioned by the CDB in 2014, provides a gender analysis of the economic, social and governance sectors in Dominica. The CGA indicates that Dominica's gender inequality index, which measures three aspects of gender inequality – reproductive health, empowerment, and economic activity – has not been calculated by the United Nations Development Programme (UNDP), because of the unavailability of relevant country data.

In terms of legislation, Dominica has neither signed nor ratified the Protocol to the Convention on the Elimination of All Forms of Discrimination against Women (Gender Equality Observatory for Latin America and the Caribbean). The most recent legislation with regard to gender equality has been the Protection against Domestic Violence Act, in 2001 and amendments to the Sexual Offences Act in 1998 and 1992. The law does not prohibit sexual harassment. Civil society groups reported it was a pervasive problem (US State Department Human Rights Report for Dominica, 2019). With regard to domestic violence, the most recent data reports that two women died from domestic violence at the hands of their partners in 2015, one died in 2014 and one died in 2009 (Gender Equality Observatory for Latin America and the Caribbean). In 2010, there were 177 cases of reported child abuse against girls, vs 39 against boys (CGA). The Bureau of Gender Affairs did not disaggregate reported cases of gender-based violence, but there were 391 reports between 2011 and 2013 (CGA).

The US State Department Human Rights Report for Dominica, 2019 states that: "The law criminalizes rape of men and women, including spousal rape. Although the maximum sentence for sexual molestation (rape or incest) is 25 years' imprisonment, the usual sentence in 2019 was five to seven years. Whenever possible, female police officers handled rape cases involving female victims. Women were reluctant to report domestic violence to police. The only shelter for victims of gender-based violence remained closed after suffering damage during Hurricane Maria in 2017. Civil society reported that sexual and domestic violence was common. The government recognized it as a problem, but according to civil society groups, recognition of gender-based violence, particularly domestic violence, as a problem was low among the general population. Although no specific laws criminalize spousal abuse, spouses can bring battery charges against their partner."


With regard to teen pregnancies, it has increased in recent years, going from 17.5% in 1981 to 40.3% in 2009 (Gender Equality Observatory for Latin America and the Caribbean and CGA). This represents a significantly high incidence of teenage pregnancy. Data from the Gender Equality Observatory for Latin America and the Caribbean shows that 100% of births in Dominica are attended by skilled health personnel. The country's maternal mortality rate of 222.3 per 100,000 women (2010) represents a high rate, placing Dominica at 53rd in the global ranking (CGA).

In terms of education, secondary school enrolment for 2011/2012 was slightly higher for males (50.7% for males vs 49.3% for females) but the number of women in tertiary level education is significantly higher than the number of males (62.5% vs 37.5%) (CGA). For labor participation, 58.4% of the labor force in

¹⁰ Dominica Vibes, DAIC Speaks on Issues of Migration in Dominica, January 22, 2020 accessed at: <https://www.dominicavibes.dm/business-261845/>

2011 was composed of males and 41.6% of females; however, the unemployment rate in 2011 was slightly higher for males than females, standing at 12.3% vs 9.9% (CGA).

When it comes to autonomy in decision-making and women’s participation in government, Dominica exhibits male dominance in Parliament, with a male: female ratio of 87.5%: 12.5% in 2014 (CGA). For 2013, the number of male vs female village councilors was 59% vs 41%, and the number of male vs female chairpersons of village councils was 71% vs 29% (CGA). The number of women legislators are illustrated in the Figure 6-4 for the years 1997-2019 (Gender Equality Observatory for Latin America and the Caribbean).



Source: Gender Equality Observatory for Latin America and the Caribbean.

Figure 6-4 Number of Women Legislators (Percentage)

6.1.3 Human Rights

Dominica’s human development index (HDI) value (0.745) is in the ‘high’ human development category, which positions the country at 72 out of 187 countries and territories globally (CGA). According to the United States State Department’s 2019 Human Rights Report for Dominica, significant human rights issues included: criminalization of libel; and criminalization of consensual same-sex sexual activity between adults, although there were no reported cases of enforcement during the year. The government took steps to prosecute officials who committed human rights abuses, but some cases remained unresolved. The report also states that inadequate prosecutorial and police staffing, outdated legislation, and a lack of magistrates resulted in backlogs and other problems in the judicial system.

Local media and opposition leadership continued to raise allegations of corruption within the government. Civil society groups staged a protest alleging the government had misappropriated one billion Eastern Caribbean dollars (\$370 million) in revenues from the Citizenship by Investment program (US State Department Human Rights Report for Dominica, 2019). A December 2019 Al Jazeera video documented allegations of government officials selling diplomatic passports (US State Department Human Rights

Report for Dominica, 2019). The government denied the allegations of misappropriation and continued to deny allegations of selling diplomatic passports (US State Department Human Rights Report for Dominica, 2019).


According to the government and civil society, child abuse remained a pervasive problem. The government maintained a Child Abuse Prevention Unit responsible for protecting children from all forms of abuse. The unit supported victims by providing counseling, psychological assessments, and other services such as financial assistance to abused children and to family members (US State Department Human Rights Report for Dominica, 2019).

Lastly, Dominica has no legislation for human trafficking (International Organization for Migration, Migration Governance in the Caribbean: Report on the Island States of the Commonwealth Caribbean, 2018). Dominica has experienced difficulties in identifying victims of trafficking and has not yet conducted any investigations or recorded any cases of trafficking in persons within their borders (International Organization for Migration, Migration Governance in the Caribbean: Report on the Island States of the Commonwealth Caribbean, 2018). The country has not implemented any awareness campaigns regarding human trafficking at national or local levels (International Organization for Migration, Migration Governance in the Caribbean: Report on the Island States of the Commonwealth Caribbean, 2018).

6.1.4 Emergency Services and Security

6.1.4.1 Emergency Services

There are eighteen police stations and eight fire stations on the island. These are shown in Figure 6-5 and Figure 6-6.



Source: ERM, 2020.

Figure 6-5 Police Stations



Source: ERM, 2020.

Figure 6-6 Fire Stations

6.1.4.2 Security

Control Risk’s Country Profile for Dominica states that there are low levels of political and social unrest. The Country Risk Profile suggests that structures in some areas of the island remain damaged and recovery efforts persist in the wake of the 2017 Atlantic hurricane season. The Country Profile also states the following: “Although violent crime rates are low, petty crime poses a risk. Pickpocketing and bag-snatching are common, and the level of petty crime increases during popular annual events such as the Carnival in February and the Creole Music Festival in October. Business personnel can be targeted due to their perceived wealth, but violent crime does not often affect foreigners, and is mostly confined to the local community. Organized criminal groups have taken advantage of Dominica’s strict bank secrecy laws, as well as its Citizenship by Investment Programme, which grants Dominican passports without proper names or identification. Dominica has traditionally been attractive for criminals involved in money laundering because of weak law enforcement. Despite the high media coverage received by the protests that took place ahead of the December 2019 election, civil unrest remains highly unlikely. At their most intense, protests in Dominica were small (less than ten people) and largely focused on blocking streets, as opposed to engaging in violence or vandalism.”

6.1.5 COVID-19

Dominica has lifted stay at home orders, and resumed some transportation options and business operations (US Department of State). In June 2020, the government stated that it would not be extending

the state of emergency and the curfew that had been in place to curb the spread of COVID-19.¹¹ The Center for Disease Control and Prevention states that Dominica's COVID-19 risk is moderate as of December 1, 2020. As of November 21, 2020, Dominica had reported a total 77 cases of COVID-19 since the beginning of the pandemic, with 63 recovered cases, 14 active cases and 0 deaths (Dominica Ministry of Health, Wellness and New Health Investment Response to COVID-19).

6.1.6 Land Use and Acquisition

The Jacob's ESIA (Jacobs, 2018) and the updated ESIA (ECLIPSE, 2020) for the drilling of geothermal well RV-I2 new reinjection pipeline route include information on land use. From the new reinjection pipeline route, eight out of the twelve plots will be partially acquired, with the acquisition of a 10-m corridor that includes the area for the pipeline itself and a buffer zone. These plots include secondary forest and abandoned agriculture. Therefore, four plots will be fully acquired. One of the plots which will be fully acquired has some active subsistence farming. There will be no physical displacement.

There are no indigenous populations that will be affected by the Project's land acquisition.

Figure 6-7 shows the location of the plots that will be affected along the reinjection pipeline route.



Source: DGDC

Figure 6-7 Properties Neighboring Preferred ReInjection Line

¹¹ CARICOM, Dominica Lifts Curfew, State of Emergency (June 2020) accessed at: <https://today.caricom.org/2020/06/30/dominica-lifts-curfew-state-of-emergency/>

6.2 Impacts and Mitigation

6.2.1 Gender

The Project will likely affect men and women differently. This is because the type of employment opportunities provided by the Project are more likely to be directed towards men. Women typically benefit from any tourism-related impacts or opportunities that the Project may result in, as they are more likely to work in the tourism sector than the construction sector. Therefore, it is unlikely that women will benefit from the limited construction and operations-related employment opportunities that will be created by the Project, which risks creating gender-based exclusion.

Studies on gender equality in the construction sector have shown that the majority of men and women working in the construction industry get to know about job openings through friends and relatives (International Labor Organization (ILO) Country Office for Pakistan, Baseline Study to Assess Gender Disparities in Construction Sector Jobs, 2011, from now on "ILO Baseline Study"). The survey shows that most women cannot avail job opportunities in the construction sector, as they do not possess the necessary social connections (ILO Baseline Study). This finding highlights the need to mainstream job information for construction-related jobs, so that women can also have access to this information.

Further, women often lack relevant skills due in part to either the lack of information about training opportunities, or the actual lack of training opportunities, which means that they cannot compete in the job market with their male counterparts (ILO Baseline Study). This phenomenon ultimately leads to a situation where women are less visible (ILO Baseline Study). Prior to mitigation, gender-related impacts could be considered to be *Moderate*.

Therefore, the Project has the potential to contribute towards gender equality by mainstreaming job opportunity information and emphasizing that they are open to women applicants, so women know that they can apply. Additional mitigation measures are listed below. After these measures, gender-related impacts will be *Minor*.

- Possible negative impacts that DGDC's actions may generate will be identified, not only in relation to human life, but also in relation to gender;
- The cultural factors of each area will be prioritized, to evaluate important issues such as:
 - Ensuring an active female voice;
 - Addressing women's loneliness in the case of male migration to work; and
 - Addressing the types of help and assistance required these women to become an active voice in employee engagement.
- A safe environment for women in the communities will be created for them to express themselves without fear of reprisal;
- All community meetings will be held at the best time for the female population of the region, always respecting their established schedules of domestic activities and attention to children and older focus groups, if necessary;
- A welcoming environment will be created for motherhood needs (e.g., take her child to a meeting);
- No woman, child, or elderly person will be put at risk or suffer any kind of reprisal;
 - All of DGDC's partnerships on the construction site will have contractual clauses to the detriment of:
 - Zero tolerance for moral and sexual harassment (Gender-based Violence Policy);

- Minimum percentage of training and local female workforce in construction and project development;
 - Specific personal protection equipment for women's work; and
 - Flexible working hours if women are breastfeeding.
- The Grievance Mechanisms will be able to immediately act and resolve instances and complaints of gender-related discrimination (including harassment, bullying, sexual abuse, etc.). DGDC will monitor and oversee the handling of complaints of gender-related discrimination.

Key performance indicators (KPIs) should include, but not be limited to:

- Number of women employed by the Project (target of 15%);
- Number of women engaged by the Project;
- Non-discrimination and gender-based violence (zero tolerance of any discrimination of any type); and
- Track and evaluate grievances related to gender-issues through the Grievance Mechanism (100% reported, evaluated and solved grievances regarding discrimination complaints and gender-based violence in a timely manner).

6.2.2 Worker Influx

The Jacobs ESIA states that “It is likely that 30 to 40 workers will be at the power plant site at the peak of construction and a team of 10 to 15 working on the pipeline. These workers are likely to be sourced from outside of Dominica, depending on the selection of the final Engineering, Procurement, and Construction Contractor (EPC). This total could be slightly larger at times if more locals are required to support with construction equipment in difficult locations. As described above, a worker’s camp is also proposed on site that would house up to 50 workers throughout the construction phase.” Further, the ESIA also states that: “The majority of employment during construction is likely to be short-term and significant employment opportunities for local communities would be limited” and “the ability to acquire a position, and successful performance once hired, will favor experienced (skilled) personnel for professional roles, the majority of whom would likely come from abroad. Therefore, operational employment opportunities are likely to be sourced from outside the local community”. However, the Project will have a Local Hiring Management Plan and DGDC will undertake vocational training to assist local people in obtaining jobs with the Project. In addition, the Contractor shall, where practical, maximize the use of local Dominica labor, suppliers and services during the execution of the project. Local Dominican labor shall include non-skilled, semi-skilled and skilled labor as well as Dominica-based service providers. Service providers shall include labor hire companies, local civil contracting companies, catering and transport services and the like. Furthermore, Bidders shall provide a methodology statement on how local labor, suppliers and services will be sourced and engaged as well as the proposed conditions of engagement.

Despite this, given the migration context discussed in Section 6.1.1, this may pose a significant influx for the island. Further, influx may also result from increased expectations around Project activities, such as the expectation of employment. An increase in prostitution around Project sites and accommodations where foreigners are residing for extended periods is also common on construction projects, which may result in an increase in communicable disease rates amongst both foreign and local populations. This would result in *Moderate* impacts.

Therefore, mitigation measures should include:

- Implement Community Grievance Mechanism.

- Evaluate need of security guards, fencing, and/or other security measures. As part of this evaluation, it is also important to consider training (e.g., in human rights and use of force, among others), whether private or public security guards will be used, and whether firearms will be warranted.
- Code of Conduct for all Project employees and contracted staff including zero-tolerance policy for drug use, sale or purchase.
- Project should issue a policy statement regarding sexually transmitted infections including HIV/AIDS, and this policy would be communicated internally to staff, and externally to Contractors.
- Develop a Socioeconomic and Community Health and Management Plan to manage influx and recreation risks.
- Workers Accommodation Plan and Checklist.
- Local Hiring Plan and Local Supplier Plan
- Develop and implement vocational training for local communities.

KPIs should include, but not be limited to:

- Engage monthly with local NGOs, civil society leaders and/or church leadership on local perceptions related to influx.
- Document number of consultations and trainings with local communities on grievance mechanism.
- Track and evaluate monthly grievances related to crime, prostitution, and conflict (target of 100% resolution).
- Liaise monthly with local health officials and police stations to track and evaluate any increase in crime and/or prostitution within the Project area.
- Document number of workers and contractors who have signed Code of Conduct and zero-tolerance policy (target of 100%).
- Track and evaluate monthly internal and external grievances related to workers' accommodation.
- Track and evaluate percentage of local hiring and suppliers.
- Number of inhabitants of Laudat, Trafalgar and Wotten Waven who have received training, and nature of training received.
- Number of inhabitants of Laudat, Trafalgar and Wotten Waven hired by the Project.

After mitigation measures, worker influx impacts would be expected to be *Minor*.

6.2.3 Land Acquisition, Resettlement and Livelihood Restoration

The Jacobs ESIA includes information on the power plant and the updated drilling and reinjection pipeline ESIA (ECLIPSE) includes information on the reinjection pipeline route with regard to land acquisition, resettlement and livelihood restoration. They also include an Abbreviated Resettlement Action Plan (ARAP), which was updated as a Resettlement Action Plan (RAP).

Construction of the reinjection pipeline route corridor would consist of an approximately 10 m wide corridor. Future land requirements include the acquisition of some portion of eight properties and the acquisition of four entire properties. One subsistence farmer would be affected by the development of the pipeline, constituting economic displacement, but there will be no physical displacement from the reinjection pipeline route. As part of this addendum, the RAP will be updated by DGDC. Once the Project activities are finalized and the RAP is updated, the significance of this potential impact should be

reassessed. No indigenous populations will be affected by economic or physical displacement. Prior to mitigation measures, these impacts would be expected to be *Moderate* in significance.

The consulting company ECLIPSE conducted an ESIA in 2020 of the new reinjection pipeline route to determine impacts on behalf of DGDC. They state that all landowners have alternative means of income generation and that the land being acquired by the project is not their main source of income, which reduces the sensitivity. However, one owner is expected to suffer income loss.

After the mitigation and compensation measures included in the RAP, these impacts would be expected to be *Minor* in significance. The RAP is included in Appendix B. The principles in the RAP will guide land acquisition and displacement compensation.

6.2.4 Impacts Summary

Table 6-3 summarizes the socioeconomic impacts included in this Addendum.

Table 6-3: Impacts and Mitigation Measures for Project Modifications and Updates

Impact	Sensitivity	Magnitude	Duration	Pre- mitigation Impact Significance	Mitigation Measure	Residual impact Significance
<i>Gender</i>	High	Medium	Short-term	Moderate	<ul style="list-style-type: none"> ■ DGDC will work to identify possible negative impacts that DGDC’s actions may generate in relation to gender. ■ DGDC will prioritize the cultural factors of the region to evaluate important issues in relation to gender. ■ A safe environment for women in the communities will be created for them to express themselves without fear of reprisal; ■ All community meetings will be held at the best time for the female population of the region, always respecting their established schedules of domestic activities and attention to children and elders, if necessary. ■ A welcoming environment will be created for motherhood needs (e.g. take her child to a meeting). ■ No woman, child, or elderly person will be put at risk or suffer any kind of reprisal. ■ The Grievance Mechanisms will be able to immediately act and resolve instances and complaints of gender-related discrimination (including harassment, bullying, sexual abuse, etc.). DGDC will monitor and oversee the handling of complaints of gender-related discrimination. ■ KPIs will include gender metrics. 	Minor
<i>Worker Influx</i>	High	Medium	Short-term	Moderate	<ul style="list-style-type: none"> ■ Implement Community Grievance Mechanism. 	Minor

					<ul style="list-style-type: none"> ■ Evaluate need of security guards, fencing, and/or other security measures. ■ Code of Conduct for all Project employees and contracted staff including zero-tolerance policy for drug use, sale or purchase. ■ Project should issue a policy statement regarding sexually transmitted infections including HIV/AIDS, and this policy would be communicated internally to staff, and externally to Contractors. ■ Develop a Socioeconomic and Community Health and Safety Management Plan to manage influx and recreation risks. ■ Workers Accommodation Plan and Checklist. ■ Local Hiring and Supply Plan, training for local communities 	
<i>Land Acquisition, Resettlement and Livelihood Restoration</i>	High	Medium	Permanent	Moderate	<ul style="list-style-type: none"> ■ Implement the Resettlement Action Plan (RAP) being updated by DGDC. 	Minor

7. CUMULATIVE IMPACT ASSESSMENT

This chapter focuses on potential cumulative impacts from the Project. Cumulative impacts are defined as the successive, incremental, and/or combined effects of a Project or activity, accumulated with other Projects or activities. Given that the Project is complying with the IFC PS, potential cumulative impacts are evaluated pursuant to IFC's Cumulative Impact Assessment (CIA) guidance - Good Practice Handbook - Cumulative Impact Assessment and Management: Guidance for Private Sector in Emerging Markets (IFC, 2013).

7.1 Key Terminology

The following are definitions for key terminology used in the CIA.

Cumulative Impact: Impacts that result from the successive, incremental, and/or combined effects of an action, project, or activity added to other existing, planned, and/or reasonably anticipated actions, projects, or activities. For practical reasons, the identification, assessment, and management of cumulative impacts are limited to those effects generally recognized as important on the basis of scientific concern and/or concerns of Project-Affected Communities (PACs)¹².

CIA: Process to identify and evaluate cumulative impacts.

Other Projects: Existing, planned, or reasonably expected future developments, projects and/or activities potentially affecting Valued Environmental Components (VECs).

External Drivers: Sources or conditions that could affect or cause physical, biological, or social stress on VECs, such as natural environmental and social drivers, human activities, and external stressors. These can include climate change, population influx, natural disasters or deforestation, among others. These are typically less defined and planned than Other Projects.

Valued Environmental Components (VECs): Environmental and social components considered as important by the scientific community and/or potential PACs. VECs may include:

Physical features, habitats, wildlife populations (e.g., biodiversity, water supply);

Ecosystem services (e.g., protection from natural hazards, provision of food);

Natural processes (e.g., water and nutrient cycles, microclimate);

Social conditions (e.g., community health, economic conditions); and

Cultural heritage or cultural resources aspects (e.g., archaeological, historic, traditional sites).


VECs reflect the public and scientific community's "concern" or special interest about environmental, social, cultural, economic, or aesthetic values (IFC, 2013). According to the IFC's methodology, VECs are considered the ultimate recipients of cumulative impacts because they tend to be at the ends of ecological pathways.

7.2 Approach


Unlike an ESIA, which focuses on a project as a generator of impacts on various environmental and social receptors, a CIA focuses on VECs as the receptors of impacts from different projects and activities (see Figure 7-1). In a CIA, the overall resulting condition of the VEC and its related viability are assessed.

¹² PACs are defined as local communities potentially directly affected by the Project (consistent with IFC Performance Standard 1, paragraph 1 [IFC 2012a]).

EIA: Project-Centered Perspective




CIA: VEC-Centered Perspective



Source: IFC, 2013.

Figure 7-1: Comparing ESIA and CIA

The CIA was derived from desktop reviews of publicly available information, information obtained during the ESIA process, and information provided by DGDC. The assessment follows the six steps for a CIA (see Figure 7-2). The process is iterative and flexible, with some steps having to be revisited in response to the results of others. For example, the VEC selection step usually needs to be adjusted after the potential impacts of the Project are identified. The steps are described in detail below.



Source: IFC, 2013.

Figure 7-2: Summary of the Cumulative Impact Assessment Methodology

7.3 Limitations

The IFC CIA Handbook methodology takes into consideration the limitations that a private developer may face carrying out a CIA. The limitations applicable to this CIA include: (1) incomplete information about other projects and activities (e.g., the information is not available in the public domain); (2) uncertainty with respect to the implementation of future projects; and (3) difficulty in establishing thresholds or limits of acceptable change for VECs, and therefore the significance of cumulative impacts.

7.4 Determination of Spatial and Temporal Boundaries

The Project includes a Geothermal Plant, with an associated reinjection pipeline and steam gathering system (SGS). The components are located within the Roseau Valley. The reinjection pipeline will extend

for approximately 1.21 km and the SGS will run for approximately 1km. The proposed route for the reinjection pipeline will go through several plots, described in the RAP.

Based on an assessment of the VECs for the CIA, it was determined that using the island of Dominica will be appropriate to serve as the spatial boundary of the CIA, in that it covers: (1) the extent of the selected VECs, and (2) the extent of the potential impacts from the Project, other projects, and external drivers. Roseau is the largest town within the CIA area.

Temporal delimitation for a CIA is future focused and therefore frequently a challenge due to the uncertainty inherent to potential future other projects. For this reason, good international industry practice suggests consideration of a three-year temporal boundary when conducting a CIA (IFC, 2013), and revisiting the CIA periodically (every 3-5 years) to identify changes in proposed projects and external drivers and therefore expected cumulative impacts. Based on the expected timeline of the Project, the construction of the plants and its facilities is estimated to take between 18 to 24 months, with an estimated construction phase of Q1 2021 to Q2 2022. The CIA uses an extended five-year temporal boundary, 2022 – 2027, to cover the Project construction and initiation of Project operation activities.

7.5 Other Projects

Through a thorough review of publicly available information and interviews with DGDC personnel, ERM identified existing and future planned projects located within the spatial and temporal boundaries of the CIA, having the potential to result in cumulative impacts on identified VECs. The sources researched to identify other existing or planned projects for this CIA included:

- IDB website
- CDB website
- Organization of Eastern Caribbean States (OECS) website
- World Bank Group website
- Development Finance Corporation website
- GlobalEnergyObservatory.org

There are no other major developments of this type (geothermal project) in Dominica and impacts of the Project are anticipated to be fairly unique to the development itself. Due to the effects of Hurricane Maria, there are multiple restoration efforts underway in the island for existing buildings that suffered damage.

In addition, other projects that have been identified nearby are:

- Hospital expansion (Dominica-China Friendship Hospital)
- Renovation and expansion of Fort Young Hotel
- West Coast Road Rehabilitation Project (rehabilitation of damaged areas along the 45 km of West Coast Road to include construction of three new bridges)
- Reconstruction of EC Loblack Bridge
- Installation of Bailey Bridges (island-wide)
- Construction of Roseau River Walls (river training walls and related road and drainage works along the Roseau River, including relocation of utility infrastructure, construction of sidewalks, installation of street lighting)
- Construction of River Wall in Colihaut (Reinforced concrete river wall, curb wall and reinstatement of collapsed roadway and guard rails)

- Water Area-1 Network Upgrade (CDB)
- Rehabilitation and Reconstruction of Dominica Electricity Services Limited (CDB)
- Housing Recovery Project (World Bank)

It is important to note that the government may evaluate an expansion of this current or future geothermal Projects, including expansion of transmission to Martinique. Currently, there are plans for a Phase II, which would include a transmission line that runs from the geothermal power plant to an east coast substation (approximately 9 km). This is expected to be finalized by mid-2022. This expansion may incur many of the same impacts or additional impacts (therefore exacerbating cumulative impacts).

In addition, a World Bank "Regional Air Transport Connectivity Project" was identified in Dominica, but there was not sufficient information on the activities that the project would encompass for it to be included in the CIA. However, if more information becomes available at a later date, the CIA should be updated to reflect this project.

7.6 External Drivers

ERM identified the following external drivers: natural hazards and climate change. Please see the Jacobs ESIA (Jacobs, 2018) ESIA, Section 3.9 for a description of natural hazards including hurricanes, landslides, volcanic eruptions, flooding and induced seismicity and subsidence. Further, the design parameters of the plant and ancillary facilities will take into consideration natural risk hazards associated to climate change projections.

With regard to climate change, the Climate Investment Funds states that Dominica is on the frontlines of climate change, with sea level rise and extreme weather threatening its population.¹³ In fact, 62% of Dominica's 71,000 inhabitants live in the low-lying coastal areas vulnerable to hurricanes, storm surges and high winds.¹⁴

Further, the UNDP Climate Change Adaptation provides the following information regarding climate change in Dominica:

"The country's main economic sectors are rain-fed agriculture (with major crops including bananas, citrus and coconuts.), government services, banks and insurance, wholesale and retail trade, and transport (Bellot and Parr, 2001). Climate change is expected to impact on this sector in three ways:

- Temperature changes affecting range of species, water flow in watersheds, reduced food availability for wildlife and increased forest pests, disease and vulnerability to extreme climate events.
- The threat presented by sea level rise to the coastal habitats (e.g., coastal freshwater ponds, brackish water systems, mangroves and arable floodplains) is substantial. Increasing pressure on forest reserves due to loss of coastal agricultural lands by salinization. Loss of coastal forests due to inundation and increasing storm events (e.g., mangroves and low lying tropical dry forests). Migration or loss of wildlife species from altered habitats.
- There is also the potential for greater frequency and intensity of storms in the Caribbean leading to the risk of landfall. Terrestrial ecosystems are severely affected by tropical disasters.

Alongside these effects, the coastal ecosystem faces additional stresses while the beaches also experience erosion and inundation. Elevated sea temperatures can also impair the coral reefs of

¹³ Dominica Climate Investment Funds, accessed at <https://www.climateinvestmentfunds.org/country/dominica#:~:text=Small%20island%20nation%20Domini%20is,not%20just%20an%20environmental%20concern.>

¹⁴ Ibid.

Dominica through bleaching. Studies done by the Fisheries Development Division in 1998, reported that approximately 15% of the coral showed sign of bleaching (Guiste, 2000, personal communication). Moreover, as sea levels rise, there will be destruction of mangroves reducing the availability of fresh water for keeping the salinity balance. Dominica's fresh water supply is also vulnerable to major hurricane impacts as water quality is affected through landslides, gully erosion and flooding.

As much of Dominica's important infrastructure is located along the coastline, close to the present sea level, this makes them vulnerable to flooding and storms. Furthermore, 90% of the population is dispersed among coastal villages, with the main population center, Roseau, located along the leeward coast. Most settlements have very little room for expansion except through hillside residential development, or density increases in already built up areas. As a result, population increase in certain districts is leading to the increasing emergence of hillside developments on the fringes of the existing towns and on small coastal headlands. These areas are highly susceptible to the ravages of extreme events such as hurricanes.

While it is difficult to quantify the impacts of climate change on Dominica's agriculture, banana - as the most significant crop in Dominica - is very sensitive to levels of precipitation. A stark contrast in optimal productivity is observed when the above average rainfall production is compared to drought production levels. There was a 17- 37% difference in the 1970's and a staggering 53-60% difference in the 1980's. In addition, crops such as vegetables are extremely sensitive to the fluctuations in precipitation. Excess rainfall tends to increase the incidence of pest and diseases leading to declining productivity, whilst drought conditions lead to reduced yields. Extreme events inflict damage directly on food systems through the destruction of crops and livestock and the erosion of farmlands.”

Consequently, climate change impacts could be negative and widespread for Dominica. The island is working hard to increase its climate resilience through, for example creating a new government agency to mainstream resilience into all areas of the country's growth.¹⁵

7.7 VEC Selection and Description

7.7.1 Selection of VECs

To be included, VECs must also be reasonably expected to be affected by both the project under evaluation (i.e., geothermal plant) and some combination of other projects and external drivers. The identification of VECs was based on social and environmental receptors identified in the assessment of impacts of the ESIA, other known activities in the project area, supplemented with information obtained during the baseline, and the consultation process.

The Jacob's ESIA and the additional studies conducted as part of this addendum concluded that most of the resources affected by the Project will incur *Minor or Negligible* impacts that were very localized in extent and duration. The major environmental and social concerns related to the Project include the risk of flooding for the reinjection pipeline; and community health and safety related to traffic and land acquisition. Chapter 6 of this Addendum describes the baseline conditions and impacts to biological resources, and Chapter 7 describes the baseline and impacts to socioeconomic resources, complementing Volume 2 and Volume 3 of the Jacobs ESIA.

All potentially eligible VECs were analyzed against the following criteria: (1) confirmed to be valued by an identifiable stakeholder group; (2) reasonably expected to be impacted by the Project (i.e., at least one

¹⁵ Devex, Dominica determined to become World's First Climate-Resilient Nation, April 16, 2020 accessed at <https://www.devex.com/news/dominica-determined-to-become-world-s-first-climate-resilient-nation-96999>

potential impact significance rating of Minor or above); **and** (3) reasonably expected to be potentially impacted by some combination of other projects and external drivers. To be included in the CIA, the VEC had to meet all three criteria. Table 7-1 presents the results of this analysis, and highlights the VECs that are selected in the CIA.

Table 7-1: Selection of VECs

VEC	Valued by Stakeholders	Potentially Affected by the Project ^a	Potentially Affected by the Project expansion	Potentially Affected by One or More Other Projects	Potentially Affected by One or More External Drivers
Terrestrial and Aquatic Biota (flora and fauna)	Yes	Yes	Yes	Yes	Yes
Land Traffic	Yes	Yes	Yes	Yes	Yes
Community Health and Safety	Yes	Yes	Yes	Yes	Yes
Landscape Aesthetics	Yes	Yes	Yes	Yes	Yes

^a At least one potential impact significance rating of Minor or above.

7.7.2 Description of VEC Conditions

The baseline conditions of the selected VECs were previously described (see Chapters 6 and 7 of the Addendum and Volumes 2 and 3 of the Jacobs ESIA). The VEC baselines provide information on the VECs’ current conditions, the anticipated resilience against external stressors and potential impacts (cumulative impacts and sources of stress), and thus provide an indication of their viability and sustainability.

7.8 Assessment of Cumulative Impacts

CIA’s are future-oriented and Project contributions are assessed as the difference between the expected future condition of the VEC in the context of all possible known stressors and that condition plus the Project under evaluation. This step of the CIA assesses the future conditions of the VECs, considering the impacts from the Project, other projects, and external drivers. The potential impacts to VECs were established from the results of the Project ESIA and Addendum and other available information. If no impact information was available (e.g., for other projects), ERM assumed common sector-based impacts.

The results of the CIA are presented in tabular format. The significance of cumulative impacts is not evaluated in terms of the magnitude of change but in terms of VEC response and the resulting condition and sustainability. If cumulative impacts do not exceed the VEC threshold, the development of the project under assessment is considered acceptable. Given the intrinsic limitations of Project-driven CIA’s, the present assessment was not intended to obtain sufficient baseline information to establish thresholds of the selected VECs and therefore establish the significance of the cumulative impacts. Instead, based on the publicly available information and the findings of the stakeholder interviews, cumulative impacts were categorized by priority using the following definitions:

High Priority: The VEC is expected to or is currently being adversely impacted by other projects and/or external drivers and the future addition of the Project could incrementally contribute to the adverse impact. Actions will be implemented in the short term to mitigate potential adverse cumulative impacts on the VEC.

Medium Priority: The VEC could potentially be impacted by other projects and/or external drivers, and the Project could potentially contribute to the adverse impact. Actions will be implemented in the medium term to mitigate potential adverse cumulative impacts on the VEC.

Low Priority: The VEC is not expected to be potentially impacted significantly by other projects and/or external drivers, and therefore the Project impacts will not be expected to contribute to an adverse cumulative impact. No actions are required to mitigate potential adverse cumulative impacts on the VEC beyond proposed Project mitigation measures.

Table 7-2 summarizes the results of the assessment of cumulative impacts identified for the selected VECs. For the CIA, the potential impacts from the current Project and the expansion are discussed separately given their differences in geography and potential impacts. The potential impacts from other projects that are within the same industry or sector are discussed together. Based on the potential cumulative impacts, a priority ranking is established for each VEC.

In summary, one High priority cumulative impact was identified for terrestrial and aquatic biota, linked to the transmission line component for the expansion of the Project. A medium priority cumulative impact was identified for landscape aesthetics. All other VECs are deemed as Low priority cumulative impacts.

Table 7-2: Summary of Cumulative Impact Assessment

VEC	Potential Impacts from the Geothermal Plant Component of the Project	Potential Impacts from the Expansion of the Project	Potential Impacts from Other Projects	Potential Impacts from External Drivers	Cumulative Impact	Priority Ranking
<p>Terrestrial and Aquatic Biota (flora and fauna)</p>	<p>During Construction, activities such as pipeline installation, vegetation removal, soil movement, and use and storage of hazardous waste and materials may result in distribution and habitat changes for terrestrial fauna, death of fauna from collision with vehicles and elimination of terrestrial flora within the Project's layout including access roads and laydown area.</p> <p>During Operations, activities such as routine maintenance, reception and delivery of materials, generation of electricity, storage and use of hazardous waste and materials, could cause the following potential impacts: hazardous materials spills on the ground, habitat loss, increased noise and vibrations, air emissions, and increased exposure to light.</p> <p>The disturbances described above could result in vegetation cover loss and distribution changes for the fauna found in the Geothermal Plant area. Mammals and birds are largely mobile, and most of the bird species identified during the baseline are considered migrant species, which makes them less vulnerable to anthropogenic intervention. Therefore, it is not expected that the Geothermal Plant construction and operations phases will result in an overall reduction in their abundance and diversity. The impact is considered Minor. Potential impact on less mobile species will be considered Moderate.</p>	<p>During an expansion and the construction of a transmission line, activities such as soil movement and compaction, and transportation of machinery, equipment and parts could result in loss of vegetation cover. The Phase II transmission line was routed to run through the Morne Trois Pitons National Park, a designated UNESCO World Heritage Site (WHS), which was likely to trigger the exclusion list criteria for destruction of Critical Habitat. However, because of these impacts, the TL will be rerouted. The impact is therefore considered Moderate until the TL is defined.</p>	<p><i>Hospital and Hotel Expansions:</i> Construction activities could disturb fauna in the area causing distribution and habitat changes from altered terrestrial habitats. The movement of trucks and heavy machinery could result in collisions with fauna. After construction, potential impacts include artificial lights that can attract birds.</p> <p><i>Road Network Improvement:</i> During Construction, activities such as soil movement and compaction, and transportation of machinery, equipment and parts could result in loss of vegetation cover. Because the roads that are being improved are already existing roads, the impact on vegetation cover loss is considered Negligible.</p> <p><i>Bridge Reconstructions and River Walls:</i> Construction activities could disturb fauna in the area causing distribution and habitat changes from altered terrestrial and aquatic habitats. The movement of trucks and heavy machinery could result in collisions with fauna. After construction, potential impacts include collisions with project vehicles or disruptions to aquatic fauna during maintenance work.</p> <p><i>Electricity Services Reconstruction:</i> Construction activities on infrastructure could disturb fauna in the area causing distribution and habitat changes from altered terrestrial habitats. The movement of trucks and heavy machinery could result in collisions with fauna. During Operations, potential impacts include collisions with project vehicles.</p> <p><i>Water Area-1 Network Upgrade:</i> establishing a new intake on Check Hall River; the construction of diversion dam upstream of the existing Springfield Intake; network transmission and distribution system upgrades; and the construction of new reinforced concrete distribution tanks could all contribute to disturbing fauna in the area causing distribution and habitat changes from altered terrestrial and aquatic habitats. The movement of trucks and heavy machinery could result in collisions with fauna. During Operations, potential impacts include collisions with project vehicles or disturbance of aquatic fauna during maintenance on the dam and intakes. Potential impacts are likely to be Moderate before mitigation measures.</p> <p><i>Housing Recovery Project:</i> Construction activities could disturb fauna in the area causing</p>	<p><i>Climate Change and Natural Hazards:</i> Rising temperatures associated with longer-term global climate change could potentially affect some special status species' ranges. Changes in precipitation and natural disasters could also affect vegetation growth and/or result in vegetation removal.</p>	<p>The Project, other projects, and external drivers could have potential negative impacts on terrestrial flora and fauna. Effects and disturbances caused by the plant construction activities will be short-term and reversible. The Project embedded controls and management plans, including the vegetation plans related to visual impacts, will mitigate potential impacts to an acceptable level (mostly Minor or Negligible). Additionally, the potential impacts are localized to the Project area within the larger CIA spatial boundary. However, the TL is yet to be defined, resulting in a conservative estimation of Moderate impacts. In sum, the current Project could potentially contribute incrementally to the adverse impact, but further VEC conversion and/or degradation is not likely to occur, and once the TL is defined the Project's contribution will be expected to be Minor to negligible.</p>	<p>High</p>

			distribution and habitat changes from altered terrestrial habitats. The movement of trucks and heavy machinery could result in collisions with fauna.			
Land Traffic	<p>During Construction, which is expected to last 18 to 24 months, there will be an increase in the volume of land traffic, consisting of cars and light trucks transporting equipment and parts. This increase in road traffic can affect the conditions of road infrastructure, disturb users of adjacent properties, lead to traffic delays, and possibly have public safety implications. The volume of traffic generated will likely be mitigated by an accommodation camp for workers during the construction period. Therefore, high volume of traffic is not expected during the Construction phase. The impacts during Construction will be Minor.</p> <p>During Operations: Most traffic will be related to routine maintenance and regular operations activities, including daily commute of plant personnel which will be a maximum of 6 roundtrips per day. The impacts during Operations will be Negligible.</p>	<p>During Construction of the TL, there will be a light increase in the volume of traffic. This increase in road traffic can affect the conditions of road infrastructure, disturb users of adjacent properties, lead to traffic delays, and possibly have public safety implications. The impacts during Construction will be Minor.</p> <p>During Operations: Most traffic will be related to routine maintenance. The impacts during Operations will be Negligible.</p>	<p><i>Hospital and Hotel Expansions:</i> Construction activities could cause increased vehicle traffic for a defined period of time.</p> <p><i>Bridge Reconstructions and River Walls:</i> During construction, transport of personnel, heavy trucks delivering or picking up equipment and machinery, and maintenance vehicles could cause congestion.</p> <p><i>Road Network Improvement:</i> During construction some roads may be partially closed or block, increasing traffic through other roads for a defined period of time.</p> <p><i>Electricity Services Reconstruction:</i> During construction, transport of personnel, heavy trucks delivering or picking up equipment and machinery, and maintenance vehicles could cause congestion.</p> <p><i>Water Area-1 Network Upgrade:</i> During construction, transport of personnel, heavy trucks delivering or picking up equipment and machinery, and maintenance vehicles could cause congestion.</p> <p><i>Housing Recovery Project:</i> During construction, transport of personnel or materials may cause congestion and increased vehicle traffic.</p>	<p><i>Climate Change and Natural Hazards:</i> To the extent the frequency or intensity of severe storms and flooding could be influenced by climate change, these could potentially damage some roads. Natural disasters may also result in damaged roads.</p>	<p>The Project and other projects could contribute to the potential negative impacts on this VEC by increasing land traffic. The external driver could exacerbate traffic due to potential damages to road infrastructure. The mitigation measures proposed by the Project will appropriately mitigate the negative impacts and contribution (Minor for the short-term construction and then Negligible for operation). In sum, the Project could potentially contribute incrementally to the adverse impact, but VEC conversion and/or degradation is not likely to occur, or the Project's contribution will be expected to be negligible.</p>	Low
Community Health and Safety	<p>During Construction, air quality could be negatively affected by activities related to earth movement and terrain preparation, movement of heavy machinery and increased land traffic in surrounding areas. These activities could increase the amount of dust and certain gases (CO₂ and H₂S) in the environment. These potential impacts will be localized and short term, and with the application of the proposed mitigation measures, the impact will be Minor.</p> <p>During Operations, there will be no emissions that will negatively affect air quality, apart from workers' travel to the site, which is consider Negligible. However, if the injection</p>	<p>During Construction, air quality could be negatively affected by activities related to earth movement and terrain preparation, movement of heavy machinery and increased land traffic in surrounding areas. These activities could increase the amount of dust and combustion gases from diesel engines (i.e. CO, SO₂, NO_x, PM_{2.5}, PM₁₀, VOCs) in the environment. These potential impacts will be localized and short term, and with the application of the proposed mitigation measures, the impact will be Negligible.</p> <p>During Operations, the main source of emissions that could negatively affect air quality will be combustion from diesel engines from maintenance trucks transiting the line if applicable. The impact will be Negligible.</p>	<p><i>Hotel and Hospital Expansions:</i> During Construction for the expansion projects, air quality could be negatively affected by activities related to earth movement, which will generate dust, and by emissions from diesel engines combustion gases. During Operations, no additional impacts are expected.</p> <p><i>Bridge Reconstructions and River Walls:</i> During Construction, air quality could be negatively affected by activities related to earth movement, which will generate dust, and by emissions from diesel engines combustion gases.</p> <p><i>Road Network Improvement:</i> During Construction, air quality could be negatively affected by activities related to earth movement, which will generate dust, and by emissions from diesel engines combustion gases.</p>	<p><i>Climate Change and Natural Hazards:</i> Rising temperatures associated with longer-term global climate change could potentially affect the dispersion and thermodynamics of pollutants emitted to the air.</p>	<p>The Project, other projects, and external drivers could contribute to the potential negative impacts on this VEC: decreased quality of the air shed. However, the other projects are already in operation and therefore their impacts are already considered in the Project baseline and residual impact assessment. The Project's embedded controls and mitigation measures proposed will appropriately mitigate the negative impacts and contribution (Minor or Negligible). In sum, the Project could potentially contribute incrementally to the adverse impact, but further VEC conversion and/or degradation is not likely to occur, or the Project's contribution will be expected to be negligible.</p>	Low

	<p>well has to be shut down during an emergency, there may be additional air emissions. Due to the extraordinary nature of this circumstance, it is expected to be of a low occurrence. Therefore, the impact will be Minor or Negligible.</p>		<p><i>Electricity Services Reconstruction:</i> During Construction, air quality could be negatively affected by activities related to earth movement, which will generate dust, and by emissions from diesel engines combustion gases.</p> <p><i>Water Area-1 Network Upgrade:</i> During Construction, air quality could be negatively affected by activities related to earth movement, which will generate dust, and by emissions from diesel engines combustion gases.</p> <p><i>Housing Recovery Project:</i> During Construction, air quality could be negatively affected by activities related to earth movement, which will generate dust, and by emissions from diesel engines combustion gases.</p>			
<p>Landscape Aesthetics</p>	<p>During Construction, the landscape will be affected by site-clearing activities, construction equipment and construction-related traffic. Of these, the only permanent effect will be site-clearing, new infrastructure and the associated loss of flora. The Project has mitigation measures for visual impacts. During Operations, there will be no further effects to landscape aesthetics. After mitigation measures, the impact during Construction will be Moderate to Minor.</p>	<p>During Construction, the landscape will be affected by construction equipment and construction-related traffic. The TL is not expected to be underground at the moment. Therefore, the TL's impact on landscape aesthetics is expected to be Minor.</p>	<p><i>Hotel and Hospital Expansions:</i> During Construction, the landscape will be affected by site-clearing activities, construction equipment and construction-related traffic. Of these, the permanent effects will be site-clearing, new infrastructure and the associated loss of flora.</p> <p><i>Bridge Reconstructions and River Walls:</i> During Construction, the landscape will be affected by site-clearing activities, construction equipment and construction-related traffic. Of these, the permanent effects will be site-clearing, new infrastructure and the associated loss of flora.</p> <p><i>Road Network Improvement:</i> During Construction, the landscape will be affected by construction equipment and construction-related traffic. Given that the roads that are being improved are already in existence, there are expected to be no permanent negative impacts to landscape aesthetics.</p> <p><i>Electricity Services Reconstruction:</i> During Construction, the landscape will be affected by site-clearing activities, construction equipment and construction-related traffic. Of these, the permanent effects will be site-clearing, new infrastructure and the associated loss of flora.</p> <p><i>Water Area-1 Network Upgrade:</i> During Construction, the landscape will be affected by site-clearing activities, construction equipment and construction-related traffic. Of these, the permanent effects will be site-clearing, new infrastructure, particularly the concrete distribution tanks, water intakes and dam diversion, and the associated loss of flora.</p>	<p><i>Climate Change and Natural Hazards:</i> Changing temperatures and higher risk of drought could lead to vegetation loss.</p>	<p>The Project and other Projects will contribute to the potential negative impacts on this VEC by reducing flora. Additionally, landscape aesthetics was identified as a highly valued VEC by stakeholders. The Project could potentially contribute incrementally to the adverse impacts that already exist, and some degree of VEC conversion and/or further degradation or perception of degradation is likely to occur. Actions will be implemented in the medium term to mitigate potential adverse cumulative impacts on the VEC.</p> <p>Effects in the TL area are expected to be Minor.</p>	<p>Medium</p>

ADDENDUM

Proposed Dominica Geothermal Development

			<p><i>Housing Recovery Project:</i> During Construction, the landscape may be affected by site-clearing activities, construction equipment and construction-related traffic. Of these, the permanent effects will be limited to any new housing projects, since existing housing that is restored will not incur additional impacts.</p>			
--	--	--	--	--	--	--

7.9 Cumulative Impacts Management Framework

Although there are other power sources on the island, the Project area is largely isolated and development of a 10 MW power plant is not anticipated to result in significant cumulative social impacts.

However, given the relatively pristine nature of the Roseau Valley, the importance of ongoing proper stakeholder engagement, understanding of community concerns, and the provision of (where possible and appropriate) training and employment opportunities to community members becomes paramount.

Internationally recognized good practices for managing cumulative impacts include:

- Effective application of the mitigation hierarchy (avoid, reduce, and remedy) in the environmental and social management of the specific contributions of a project to expected cumulative impacts; and
- Undertaking best efforts to engage, leverage, and/or contribute in multi-stakeholder collaborative initiatives or discussion groups to implement management measures that are beyond the capacity and responsibility of any individual project developer. (IFC, 2013).

The embedded controls and management measures included in the ESIA and the Addendum provide a means to mitigate the specific contributions of the Project to effects on VECs, following the mitigation hierarchy. Supplementing these controls and management measures, the CIA provides a framework of additional actions that DGDC will apply in the regional and Project context to manage potential cumulative impacts on these VECs.

7.9.1 Project Level

Effective application of the mitigation hierarchy (avoid, reduce, remedy) to manage individual contributions of cumulative impacts will be applied as best practice. DGDC has incorporated a number of physical or procedural embedded controls in the Project design. These are considered from the very start of the impact assessment process as part of the Project, and are factored into the pre-mitigation impact significance ratings. In addition, a number of mitigation measures detailed in the ESIA and Addendum have been proposed to address potential impacts from the Project. The ESIA and Addendum also include an Environmental and Social Management Plan (see Appendix A), which summarizes the mitigation and monitoring measures for all environmental parameters, including the VECs assessed in this CIA.

At the Project level, the above measures are considered sufficient to address the contributions of the Project to cumulative impacts on the identified VECs related to landscape aesthetics.

With regard to impacts on biota, it is highly recommended that the Project expansion, if and when carried forward, relocate the transmission line to avoid any impacts to Critical Habitats. Potential options include:

- Around the northern boundary of the WHS to the current departure point, following existing infrastructure as much as possible, to avoid direct impacts to Natural Habitat, particularly any intact forests.

7.9.2 Regional Level

Ultimately, the management of cumulative impacts is the responsibility of government and regional planners. However, it is considered best international practice that private-sector developers make best efforts to engage relevant stakeholders and promote management of cumulative impacts in their project areas (IFC, 2013; Franks, 2010).

The CIA identified medium and high priority cumulative impacts on the following VECs: Terrestrial and Aquatic Biota and Landscape Aesthetics. Therefore, the development and implementation of a multi-stakeholder collaborative management framework, to the extent possible, is recommended. DGDC has agreed to foster such collaboration by participating, to the extent feasible and practicable, in working

groups and/or industry organizations aimed at addressing management of potential impacts on regional resources to which DGDC's Project could incrementally contribute with respect to cumulative impacts.

Here are some initiatives that DGDC will take to strengthen a collaborative management framework for the VECs that the Project could contribute cumulatively with medium priority:

Landscape Aesthetics

- Promote the creation and maintenance of green spaces around the Project and other project areas.
- Promote the use of colors for Project components that blend into the natural surroundings.

Terrestrial and Aquatic Biota

- Promote information sharing related to impacts from the Project and the other projects to enrich common information and identify potential synergies on information gathering and mitigation measures.
- Evaluate opportunities to use shared access roads with other projects in the vicinity.
- Promote the creation and maintenance of urban green spaces around the Project and other project areas.
- Recommend the collaborative monitoring of impacts on biota among the projects, with adaptive management.

8. CONCLUSION

The results of the environmental and social impact assessment presented in this Addendum to the ESIA are valid insofar as the design of the Project remains the same. Should the design of the Project or any of its components change, then the results presented in this Addendum may have to be updated to reflect the changes.

9. REFERENCES

- Bayer, P., Rybach, L., Blum, P., and R. Brauchler. 2013. Review on life cycle environmental effects of geothermal power generation. *Renewable and Sustainable Energy Reviews*. 26:446-463.
- Beard, J. 1949. *The natural vegetation of the Windward and Leeward Islands*. Oxford: Clarendon Press.
- Bellot, P. and Parry. 2001. *Commonwealth of Dominica, Initial Communication under the United Nations Framework Convention on Climate Change*. Ministry of Agriculture and the Environment, 2001.
- BirdLife International. 2018. *Pterodroma hasitata*. The IUCN Red List of Threatened Species 2018: e.T22698092A132624510. <https://dx.doi.org/10.2305/IUCN.UK.2018-2.RLTS.T22698092A132624510.en>. Downloaded on 04 November 2020.
- BirdLife International. 2020. Important Bird Areas factsheet: Morne Trois Pitons National Park. Downloaded from <http://www.birdlife.org> on 02/11/2020.
- Brown, A.C. 2015. Radar surveys for the endangered Blackcapped Petrel on Dominica, West Indies. *Environmental Protection in the Caribbean*, Green Cove Springs, FL.
- Caraiibes Environnement Développement & Coll. 2015a. Initial environmental status of the Roseau Valley in Dominica, planned for development of geothermal electricity production. Final report, May 2015. Section 3 Biodiversity / Terrestrial Flora and Fauna.
- Caraiibes Environnement Développement & Coll. 2015b. Initial environmental status of the Roseau Valley in Dominica, planned for development of geothermal electricity production. Final summary report.
- Caribbean Development Bank, *Dominica Country Gender Assessment*, 2014.
- CARICOM, *Dominica Lifts Curfew, State of Emergency (June 2020)* accessed at: <https://today.caricom.org/2020/06/30/dominica-lifts-curfew-state-of-emergency/>
- CGIP. 2013. *Environmental Impact Assessment, Dominica Geothermal Energy Development Project Phase 2: Environmental Survey and Impact Assessment of Geothermal Wells Drilling in the Roseau Valley*. Caribbean Geothermal Interreg Programme. October 2013.
- Control Risk's Country Profile for Dominica.
- Daltry, J.C. 2002. *Mountain chicken monitoring manual*. Fauna & Flora International, Cambridge, and the Forestry and Wildlife Division, Dominica.
- Devex, *Dominica determined to become World's First Climate-Resilient Nation*, April 16, 2020 accessed at <https://www.devex.com/news/dominica-determined-to-become-world-s-first-climate-resilient-nation-96999>
- Dominica Climate Investment Funds, accessed at <https://www.climateinvestmentfunds.org/country/dominica#:~:text=Small%20island%20nation%20Dominica%20is,not%20just%20an%20environmental%20concern.>
- Dominica Ministry of Health, Wellness and New Health Investment Response to COVID-19
- Dominica Vibes, *DAIC Speaks on Issues of Migration in Dominica*, January 22, 2020 accessed at: <https://www.dominicavibes.dm/business-261845/>
- ECLIPSE. 2020. *Drilling of Geothermal Well RV-12 and Injection Pipeline. Draft Environmental and Social Impact Assessment*. Dominica, September 2020.
- Edwards, Maria-Jose. 2018. *Technical Report: Updated Design of Buffer Zones for the Morne Trois Pitons National Park World Heritage Site*.

EERE. 2020. Electricity Generation. Office of Energy Efficiency & Renewable Energy, U.S. Department of Energy. Accessed October 2020. <https://www.energy.gov/eere/geothermal/electricity-generation>

Food and Agriculture Organization (FAO). 2015. Country Report: Dominica. Global Forest Resources Assessment (FRA) 2015. <http://www.fao.org/3/a-au190e.pdf>.

Gender Equality Observatory for Latin America and the Caribbean.

Genoways, H.H., Timm, R.M., Baker, R.J., Phillips, C.J. and Schlitter, D.A. 2001. Bats of the West Indian island of Dominica: natural history, areography, and trophic structure.

Government of the Commonwealth of Dominica, Ministry of Trade, Employment, Industry and Diaspora Affairs, Diaspora Policy, 2010

Guiste, 2000, personal communication.

Hudson, M.A., Young, R.P., Jackson, J.U., Orozco-terWengel, P., Martin, L., James, A., Sulton, M., Garcia, G., Griffiths, R.A., Thomas, R. and Magin, C. 2016. Dynamics and genetics of a disease-driven species decline to near extinction: lessons for conservation. *Scientific reports*, 6(1), pp.1-13.

Iceland Drilling. 2012. Site Layout For Production Well, Dominica Rig Equipment. Engineering Drawing by Iceland Drilling, dated October 26, 2012. Provided by DGDC.

IFC, Cumulative Impact Assessment Methodology

International Finance Corporation (IFC). 2013. Good Practice Handbook - Cumulative Impact Assessment and Management: Guidance for the Private Sector in Emerging Markets. Washington D.C.: IFC.

International Labor Organization Country Office for Pakistan, Baseline Study to Assess Gender Disparities in Construction Sector Jobs, 2011.

International Organization for Migration, Migration Governance in the Caribbean: Report on the Island States of the Commonwealth Caribbean, 2018.

International Union for Conservation of Nature (IUCN) SSC Amphibian Specialist Group. 2017. *Leptodactylus fallax*. The IUCN Red List of Threatened Species 2017: e.T57125A3055585. <https://dx.doi.org/10.2305/IUCN.UK.2017-3.RLTS.T57125A3055585.en>. Downloaded on 04 November 2020.

ISOR. 2020. Laudat – Dominica, A Proposed New Site and Design of Re-injection Wells. Prepared by ISOR Iceland Geosurvey, Prepared for Dominica Geothermal Development Company Ltd. (DGDC). September 2020.

Jacobs. 2018. Dominica Geothermal Development – Environmental and Social Impact Assessment. NZ Ministry of Foreign Affairs & Trade. Environmental and Social Impact Assessment, Volumes 1-5. RZ020300-002-NP-RPT-0004 | 21, July 2018.

Jameson, T., Tapley, B., Barbón, A., Goetz, M., Harding, L., López, J., Upton, K. and García, G., 2019. Best Practice Guidelines for the Mountain Chicken (*Leptodactylus fallax*).

Larsen, R. 2016. *Myotis dominicensis*. The IUCN Red List of Threatened Species 2016: e.T14155A22057933. <https://dx.doi.org/10.2305/IUCN.UK.2016-1.RLTS.T14155A22057933.en>. Downloaded on 04 November 2020.

Leopold, M.F., Geelhoed, S., Scheidat, M., Cremer, J., Debrot, A.O., and R.V. Halewin. 2019. A review of Records of the Black Capped Petrel *Pterodroma hasitata* in the Caribbean Sea. *Marine Ornithology* 47:235-241. http://www.marineornithology.org/PDF/47_2/47_2_235-241.pdf

McKown, M., Fleishman, A.B. and Earl, A.D. 2016. Acoustic surveys for Black-capped Petrel on Hispaniola and Dominica–2016.

Schlumberger, 2020. Alkalinity Control – Drilling Fluid Additives. Schlumberger Limited, 2020. Accessed November 2020. <https://www.slb.com/drilling/drilling-fluids-and-well-cementing/drilling-fluids/drilling-fluid-additives/alkalinity-control>

Simms, Lisa. Personal communication, unpublished. November 9, 2020

Steiner, S C. 2003. Stony corals and reefs of Dominica. Atoll Research Bulletin.

T. Fontaine, Tracing the Diaspora's Involvement in the Development of a Nation: The Case of Dominica

The Biodiversity Consultancy (TBC). 2020. Biodiversity screening and review against STOA/AFD/EDFI exclusion list for the Wotton Waven geothermal project, Dominica. The Biodiversity Consultancy Ltd, Cambridge, UK.

UNDP Climate Change Adaptation for Dominica

UNEP-WCMC. 2020. Protected Area Profile for Morne Trois Pitons National Park from the World Database of Protected Areas, October 2020. Available at: www.protectedplanet.net

UNICEF, Migration Profile for Dominica, 2013

US State Department Human Rights Report for Dominica, 2019.

Appendix A Environmental and Social Management Plan (ESMPs)



Environmental and Social Impact Assessment (ESIA) Addendum – Environmental and Social Management Plans

Proposed Dominica Geothermal Development
Project

February 2021

February 2021

Environmental and Social Impact Assessment (ESIA) Addendum – Environmental and Social Management Plans

Proposed Dominica Geothermal Development Project



Ricardo Calvo
Partner



Herbert Pirela
Project Manager

ERM Washington
1776 I St NW
Washington DC 20006
Tel: 1-202-466-9090

The Bank may copy, reproduce, distribute, disseminate, publish and/or display the Works in any format or media now known or hereafter developed, in any publication, website, blog, catalog, event, exhibit, archive, as well as in any Bank materials.

CONTENTS

1.	BIODIVERSITY MANAGEMENT PLAN	1
1.1	Introduction	1
1.2	Scope	1
1.3	Key Impacts	1
1.4	National/International Standards.....	3
1.5	Mitigation Measures.....	3
1.5.1	Minimize Project Footprint	3
1.5.2	Pre-clearing Surveys, and Rescue and Relocation.....	4
1.5.3	Best Practice Vegetation Removal.....	4
1.5.4	Revegetation of Temporary Areas	5
1.5.5	Habitat Management Biodiversity Offset.....	5
1.5.6	Habitat Fragmentation Management.....	6
1.5.7	Artificial Lighting Management	6
1.5.8	Noise and Vibration Mitigation	7
1.5.9	Invasive Species Management	8
1.5.10	Worker Education and Conduct	8
1.5.11	Protected Area and Area of Conservation Importance.....	9
1.6	Roles and Responsibilities.....	10
1.7	Summary Table of Verification of Mitigation Measures and Key Performance Indicators.....	10
1.8	No Net Loss (NNL) Biodiversity Monitoring and Reporting	26
2.	EROSION AND SEDIMENT CONTROL PLAN	27
2.1	Introduction	27
2.1.1	Objective	27
2.1.2	Scope of Application	27
2.2	Roles and Responsibilities.....	27
2.2.1	Construction.....	28
2.2.2	Operation	28
2.3	Key Impacts	28
2.4	Mitigation Measures.....	29
2.4.1	Pre-Construction	29
2.4.2	Construction.....	29
2.4.3	Operation	30
2.5	Monitoring and Reporting.....	31
2.5.1	Construction.....	31
2.5.2	Operation	33
2.6	Training.....	33
2.7	Key Performance Indicators.....	33
3.	WASTE MANAGEMENT PLAN	34
3.1	Introduction	34
3.1.1	Objective	34
3.1.2	Scope of Application	34
3.2	Roles and Responsibilities.....	34
3.3	Sources of Impacts	35
3.4	Waste Generation.....	36
3.5	Approach	36
3.6	Mitigation Measures.....	38

3.6.1	Construction.....	38
3.6.2	Operation	41
3.7	Documentation and Monitoring	41
3.7.1	Contractor Monitoring Responsibilities.....	41
3.7.2	DGDC Monitoring Responsibilities.....	42
3.8	Training.....	42
3.9	Key Performance Indicators.....	42
4.	WATER MANAGEMENT PLAN.....	44
4.1	Objective.....	44
4.2	Scope of Application	44
4.3	Roles and Responsibilities.....	45
4.4	Activities.....	46
4.4.1	Water	46
4.4.2	Wastewater.....	49
4.4.3	Stormwater.....	51
4.5	Documentation and Monitoring	52
4.5.1	Construction.....	52
4.5.2	Operation	52
4.6	Training.....	52
4.7	Key Performance Indicators.....	53
5.	AIR EMISSIONS MANAGEMENT PLAN.....	54
5.1	Introduction.....	54
5.1.1	Objective.....	54
5.1.2	Scope of Application	54
5.2	Roles and Responsibilities.....	54
5.3	Sources of Impacts	55
5.4	National/International Standards.....	56
5.5	Approach	57
5.6	Management/Mitigation Measures.....	57
5.6.1	Dust Control.....	57
5.6.2	Combustion Gases and Mobile Sources.....	58
5.6.3	Odors and Process Emissions.....	58
5.6.4	Greenhouse Gas Emissions	59
5.7	Air Emissions Monitoring and Response	59
5.7.1	Construction.....	59
5.7.2	Operation	60
5.8	Training.....	60
5.9	Documentation and Record Keeping.....	61
5.10	Key Performance Indicators.....	61
6.	NOISE MANAGEMENT PLAN.....	62
6.1	Introduction.....	62
6.1.1	Objective.....	62
6.1.2	Scope of Application	62
6.2	Roles and Responsibilities.....	62
6.3	Sources of Impacts	63
6.4	National and International Standards.....	64
6.5	Approach	64

6.6	Management and Mitigation Measures.....	65
6.6.1	Construction Noise.....	65
6.6.2	Operational Noise.....	66
6.7	Noise Monitoring.....	66
6.8	Training and Complaint Resolution.....	67
6.9	Key Performance Indicators.....	67
7.	DISASTER RISK AND EMERGENCY MANAGEMENT PLAN.....	69
8.	WELL BLOWOUT PREVENTION PLAN.....	70
8.1	Introduction.....	70
8.1.1	Objective.....	70
8.1.2	Scope of Application.....	70
8.2	Roles and Responsibilities.....	70
8.2.1	Construction.....	71
8.2.2	Operation.....	72
8.3	Blowout Preventers.....	72
8.4	Prevention Activities.....	72
8.4.1	Construction.....	72
8.4.2	Operation.....	75
8.5	Emergency Response.....	75
8.6	Documentation and Monitoring.....	76
8.6.1	Construction.....	76
8.6.2	Operation.....	77
8.7	Training.....	77
8.7.1	Construction.....	77
8.7.2	Operation.....	77
8.8	Key Performance Indicators.....	77
9.	EMERGENCY RESPONSE PLAN.....	79
10.	SECURITY MANAGEMENT PLAN.....	80
10.1	Introduction.....	80
10.1.1	Objective.....	80
10.1.2	Scope of Application.....	80
10.2	Roles and Responsibilities.....	80
10.3	Activities.....	81
10.3.1	Site Security.....	82
10.3.2	Recruitment for Security Personnel.....	82
10.3.3	Training and Information.....	83
10.3.4	Security Guard Functions.....	83
10.3.5	Site Access Control.....	83
10.3.6	Additional Measures.....	84
10.4	Documentation and Monitoring.....	84
10.5	Key Performance Indicators.....	84
11.	OPERATIONAL HEALTH AND SAFETY MANAGEMENT PLAN.....	86
12.	LABOR CONDITIONS AND WORKERS SELECTION PLAN.....	87
12.1	Introduction.....	87
12.1.1	Objective.....	87

12.1.2	Scope of Application	87
12.2	Roles and Responsibilities.....	87
12.3	Activities.....	88
12.3.1	Working Conditions and Management of Worker Relationship.....	88
12.3.2	Human Resources Policy.....	88
12.3.3	Working Conditions and Terms of Employment.....	88
12.3.4	Worker’s Organizations.....	89
12.3.5	Non-Discrimination and Equal Opportunity	90
12.3.6	Gender Equality	90
12.3.7	Retrenchment	91
12.3.8	Grievance Mechanism	92
12.4	Workforce	92
12.4.1	Child Labor	92
12.4.2	Forced Labor.....	92
12.5	Occupational Health and Safety	92
12.6	Temporary Jobs.....	92
12.6.1	Hiring Requirements	92
12.6.2	Communication Mechanisms.....	95
12.6.3	Workers Engaged by Third Parties	95
12.7	Performance Management Process	95
12.8	Documentation and Monitoring	96
12.9	Key Performance Indicators.....	96
13.	INTERNAL GRIEVANCE MECHANISM	98
13.1	Introduction.....	98
13.1.1	Objective.....	98
13.1.2	Scope of Application	98
13.1.3	Definitions	98
13.2	Roles and Responsibilities.....	99
13.3	Activities.....	100
13.3.1	Principles	100
13.3.2	Publication of the Mechanism	101
13.3.3	Internal Grievance Mechanism Procedure.....	101
13.4	Confidentiality and Protection from Retaliation	107
13.5	Documentation and Monitoring	107
13.6	Key Performance Indicators.....	107
14.	COMMUNITY HEALTH AND SAFETY MANAGEMENT PLAN.....	109
14.1	Introduction.....	109
14.1.1	Objective.....	109
14.1.2	Scope of Application	109
14.2	Roles and Responsibilities.....	110
14.3	Activities.....	110
14.3.1	Health and Safety Risk Identification Associated to Affected Communities.....	110
14.3.2	Emergency and Preparedness Response Plan	111
14.3.3	Community Health and Safety Measures.....	111
14.3.4	Communication of Information	111
14.3.5	Training.....	113
14.4	Documentation and Monitoring	114
14.5	Key Performance Indicators.....	114

15.	EXTERNAL GRIEVANCE MECHANISM.....	116
15.1	Introduction.....	116
15.1.1	Objective.....	116
15.1.2	Scope of Application.....	117
15.1.3	Definitions.....	117
15.2	Roles and Responsibilities.....	117
15.3	Activities.....	118
15.3.1	Principles.....	118
15.3.2	Publication of the Mechanism.....	119
15.3.3	Grievance Mechanism Procedure.....	120
15.4	Confidentiality and Protection from Retaliation.....	126
15.5	Documentation and Monitoring.....	127
15.6	Key Performance Indicators.....	127
16.	CONTRACTOR MANAGEMENT PLAN.....	129
16.1	Introduction.....	129
16.1.1	Objective.....	129
16.1.2	Scope of Application.....	129
16.2	Roles and Responsibilities.....	129
16.3	Activities.....	130
16.3.1	Current DGDC Contractor Management Procedures.....	130
16.4	Training and Competency.....	133
16.5	Contractor Supervision Procedure.....	133
16.5.1	Direct Supervision.....	134
16.5.2	Reports.....	136
16.5.3	Monthly Audits.....	136
16.5.4	Accommodation Auditing Protocol.....	136
16.5.5	Subcontractor Monitoring by the Contractor.....	137
16.6	Documentation and Monitoring.....	137
16.7	Key Performance Indicators.....	138
17.	STAKEHOLDER ENGAGEMENT PLAN.....	139
17.1	Introduction.....	139
17.1.1	Objective.....	139
17.1.2	Scope of Application.....	140
17.2	Roles and Responsibilities.....	140
17.3	Activities.....	141
17.3.1	Stakeholder Identification.....	141
17.3.2	Community Participation.....	147
17.3.3	Registration Process: Stakeholder Database.....	156
17.4	Documentation and Monitoring.....	156
17.5	Reporting.....	156
17.5.1	Meeting Minutes.....	156
17.5.2	Recording Grievances.....	156
17.5.3	Stakeholder Database.....	157
17.5.4	Commitments Register.....	157
17.5.5	Annual Reporting.....	157
17.6	Key Performance Indicators.....	157
18.	COVID-19 CONTINGENCY PLAN.....	159

18.1	Introduction.....	159
18.1.1	Objective.....	159
18.1.2	Scope of Application.....	159
18.2	Roles and Responsibilities.....	159
18.3	Activities.....	160
18.3.1	DGDC COVID-19 Committee.....	160
18.3.2	Monitoring of Normative Acts and COVID-19 Cases.....	161
18.3.3	Disclosure of Information.....	161
18.3.4	Social Actions and Community Engagement.....	161
18.3.5	Identification of Essential Activities to Begin and Continue the Project.....	162
18.3.6	Social Distancing Measures.....	162
18.3.7	Activity Security Analysis and Work Permit.....	163
18.3.8	Control Measures and Working Conditions.....	163
18.3.9	Food Supply and Preparation Measures.....	163
18.3.10	Control Measures for Mobilizing Workers.....	163
18.3.11	Control Measures for potential Workers' Accommodations.....	164
18.3.12	Preventive Measures for Drinking Water Supply, Sanitation and Solid Waste Management.....	165
18.3.13	Measures for the Office Spaces.....	167
18.3.14	Management of Meetings or Events.....	168
18.3.15	Visitors.....	169
18.3.16	Remote Work (Home Office).....	170
18.4	Documentation and Monitoring.....	170
18.5	Key Performance Indicators.....	170
19.	CHANCE FIND PLAN.....	172
19.1	Introduction.....	172
19.1.1	Objective.....	172
19.1.2	Scope of Application.....	172
19.2	Roles and Responsibilities.....	172
19.3	Regulatory Background.....	172
19.3.1	National Requirements.....	172
19.3.2	International Standards.....	173
19.4	Cultural Heritage Monitoring Program.....	174
19.5	Chance Find Procedure.....	174
19.6	Cultural Heritage Training Program.....	177
19.7	Site Protection Program.....	177
19.8	Key Performance Indicators.....	177
20.	TRANSPORTATION MANAGEMENT PLAN.....	179
21.	TRAINING PLAN.....	180
21.1	Introduction.....	180
21.1.1	Objective.....	180
21.1.2	Scope of Application.....	180
21.2	Roles and Responsibilities.....	181
21.3	Required Training Activities.....	181
21.4	Documentation and Monitoring.....	185
21.5	Key Performance Indicators.....	185
22.	ESMP ESTIMATED COSTS.....	186

23. REFERENCES 191

APPENDIX 13-A INTERNAL CLAIM FORM

APPENDIX 13-B COMMUNICATION FORM

APPENDIX 15-A EXTERNAL CLAIM FORM

APPENDIX 15-B COMMUNICATION FORM

APPENDIX 16-A WORKERS ACCOMMODATION AUDIT

APPENDIX 17-A SUMMARY OF COMMUNITY MEETINGS

List of Tables

Table 1-1: Summary of Biodiversity Impacts, Mitigation Measures, Timing, Monitoring, KPIs, and Responsibilities	11
Table 1-2: Summary of Biodiversity Values to Monitor to demonstrate NNL	26
Table 2-1: Roles and Responsibilities.....	28
Table 2-2: Key Performance Indicators	33
Table 3-1: Roles and Responsibilities.....	34
Table 3-2: Waste Management Procedures in Dominica	38
Table 3-3: Key Performance Indicators	42
Table 4-1: Roles and Responsibilities.....	45
Table 4-2: Proposed Water Take Limits	47
Table 4-3: IFC EHS Guidelines Water Discharge Criteria	50
Table 4-4: Key Performance Indicators	53
Table 5-1: Roles and Responsibilities.....	54
Table 5-2: Guidelines for Ambient Air Quality for Typical Air Pollutants.....	56
Table 5-3: Exposure Limits to Potential Air Contaminants	57
Table 5-4: Key Performance Indicators	61
Table 6-1: Roles and Responsibilities.....	63
Table 6-2: IFC Guidelines for Ambient Noise	64
Table 6-3: Key Performance Indicators	67
Table 8-1: Roles and Responsibilities.....	70
Table 8-2: Design Standards	74
Table 8-3: Key Performance Indicators	77
Table 10-1: Roles and Responsibilities.....	80
Table 10-2: Key Performance Indicators	84
Table 12-1: Roles and Responsibilities.....	87
Table 12-2: Targets.....	95
Table 12-3: Key Performance Indicators	97
Table 13-1: Terms and Definitions	98
Table 13-2: Roles and Responsibilities.....	99
Table 13-3: Timeframe per Claim Category.....	104
Table 13-4: Key Performance Indicators	107
Table 14-1: Roles and Responsibilities.....	110
Table 14-2: Key Performance Indicators	114
Table 15-1: Terms and Definitions	117
Table 15-2: Roles and Responsibilities.....	118

Table 15-3: Grievance Contacts	120
Table 15-4: Classification of Grievances	123
Table 15-5: Key Performance Indicators	127
Table 16-1: Roles and Responsibilities.....	129
Table 16-2: Supervision of the EPC Contractor.....	134
Table 16-3: Supervision of the O&M Contractor	135
Table 16-4: Key Performance Indicators	138
Table 17-1: Roles and Responsibilities.....	141
Table 17-2: Assessment of Position Criteria.....	143
Table 17-3: Interest Evaluation Criteria	143
Table 17-4: Influence Evaluation Criteria.....	143
Table 17-5: Affected and Interested Stakeholder Groups in the Project's AOI	144
Table 17-6: Analysis and Identification of Stakeholder Groups.....	145
Table 17-7: Summary of DGDC Interviews with Key Stakeholders.....	149
Table 17-8: Consultation and Participation Action Plan.....	154
Table 17-9: Key Performance Indicators	158
Table 18-1: Roles and Responsibilities.....	159
Table 18-2: Key Performance Indicators	171
Table 19-1: Roles and Responsibilities.....	172
Table 19-2: Three-tier Chance Find Hierarchy	175
Table 19-3: Key Performance Indicators	178
Table 21-1: Roles and Responsibilities.....	181
Table 21-2: Required Training Activities by Topic	181
Table 21-3: Key Performance Indicators	185
Table 22-1: ESMP Estimated Costs	186

List of Figures

Figure 2-1: Erosion and Sediment Control Audit Flow Diagram	31
Figure 4-1: Proposed Water Source Location.....	47
Figure 13-1: Internal Grievance Mechanism Procedure	102
Figure 15-1: General Grievance Mechanism Procedure	120
Figure 15-2: DGDC's Grievance Flow Chart.....	122
Figure 17-1: Mapping of the Stakeholder Groups.....	147
Figure 17-2 Stakeholder Engagement with the Laudat Community	152
Figure 19-1: Chance Find Procedure Flowchart.....	176

ACRONYMS AND ABBREVIATIONS

°C	Degree Celsius
ACC	Air Cooled Condensers
ADI	Area of Direct Influence
All	Area of Indirect Influence
AOI	Area of Influence
AVR	automatic voltage regulator
BAOI	Biotic Area of Influence
BMP	Biodiversity Management Plan
BOP	Blow Out Preventer
BOPE	Blow Out Prevention Equipment
CBD	Convention on Biological Diversity
CDB	Caribbean Development Bank
CFCs	Chlorofluorocarbons
CH ₄	Methane
CHS	Community Health and Safety
CIA	Cumulative Impact Assessment
CITES	Convention on the International Trade in Endangered Species
CO	Carbon Monoxide
COVID-19	New Coronavirus
CR	Critically Endangered
dB	Decibels
dBA	A-weighted decibels
dBC	C-weighted decibels
DD	Data Deficient
DDR	Daily Drilling Report
DGDC	The Dominica Geothermal Development Company
DGR	Daily Geological Reports
DOA	Department of Agriculture
DOE	Department of Environment
DOMLEC	Dominica Electricity Services Limited
DOWASCO	Dominica's Water and Sewerage Company Ltd.
EHS	Environmental, Health, and Safety
EIA	Environmental Impact Assessment
ESG	Environmental, Social and Governance
ESIA	Environmental and Social Impact Assessment
ESMP	Environmental and Social Management Plans
ESPII	Public Health Emergency of International Importance
EU	European Union
F	Fahrenheit
ft	Feet
ft msl	Feet Mean Sea Level
GHGs	Greenhouse Gases
H&S	Health and Safety
H ₂ S	Hydrogen Sulfide
Ha	Hectare
HIV/AIDS	Human Immunodeficiency Virus/ Acquired Immunodeficiency Syndrome
IBAs	Important Bird Areas
IBAT	Integrated Biodiversity Assessment Tool
IDB	Inter-American Development Bank
IFC	International Finance Corporation

IFC PS	International Finance Corporation Performance Standards
ILO	International Labor Organization
IPPC	International Plant Protection Convention
km ²	Kilometers squared
KPIs	Key Performance Indicators
kW	Kilowatt
kWe	Kilowatt Electric
kWhr	Kilowatt-hours
LAeq	levels as equivalent
lbs	Pounds
LEL	Lower Explosive Limit
Leq	Sound Level
m	Meters
m ³	Cubic meters
m ³ /year	Cubic meters per year
Mg	Milligrams
mm/year	millimeter per year
mph	Miles per hour
MPL	Maximum Permissible Limits
MTPNP	Morne Trois Pitons National Park
MW	Megawatt
MWe	Megawatt Electric
NCG	Non-Condensable Gas
NGOs	Non-Governmental Organizations
NIOSH	U.S. National Institute for Occupational Safety and Health
NO ₂	Nitrogen dioxide
NOAA	National Oceanic and Atmospheric Administration
NT	Near threatened
ORC	Organic Rankin Cycle
OSHA	U.S. Occupational Safety and Health Administration
PEC	Predicted Environmental Concentration
PEL	Permissible Exposure Limits
pH	Potential of hydrogen
PM	Particulate Matter
PM 2.5	Particulate Matter 2.5
PM ₁₀	Particulate Matter 10
ppb	Parts per billion
PPE	Personal Protective Equipment
ppm	Parts per million
PS	Performance Standard
REL	Recommended Exposure Limits
SDS	Safety Data Sheet
SEP	Stakeholder Engagement Plan
SO ₂	Sulfur dioxide
SPCC	Spill Prevention Control and Countermeasures
STIs	Sexually Transmitted Infections
TWA	Time Weighted Average
US	United States
UV	Ultraviolet
VU	Vulnerable
µg/m ³	Microgram per cubic meter air

1. BIODIVERSITY MANAGEMENT PLAN

1.1 Introduction

The following Biodiversity Management Plan (BMP) establishes a framework for minimizing impacts of the Dominica geothermal power plant (the Project) on terrestrial biodiversity. Some of the Project area has already been cleared (existing injection pad); however, for any additional clearance (for the plant site, pipelines, new pads, and access/maintenance roads), the following management plan will be implemented. The BMP's purpose is to set forth procedures that DGDC will implement to manage and monitor terrestrial biodiversity during construction and operations of the Project. This will allow compliance with legal requirements and guidance standards for the environmental coordinator and the hired Contractors to avoid, minimize, and reduce adverse effects to terrestrial biodiversity receptors within the Project's BAOI. This BMP is based on the impacts and mitigation measures for terrestrial biodiversity values identified and described in the Project Description and the impact assessment provided in the Jacobs ESIA (2018), and the ECLIPSE (2020). The current document compiles and summarizes relevant documentation regarding impacts and mitigation measures for terrestrial biodiversity which includes the Habitat and Biodiversity Management and MTPNP Monitoring Plan (ESMS-DGDC-ENV-005) and provides a summary of the best management practices. Where necessary, supplemental measures are provided.

The mitigation activities presented in this plan are aligned with the Environmental and Social Standard 6 (ESS6) Biodiversity Conservation and Sustainable Management of Living Natural Resources (WB, 2016) and Performance Standard 6 of the IFC, *Biodiversity Conservation and Sustainable Utilization of Living Natural Resources* (IFC, 2012). It is anticipated that the BMP will be periodically updated as the Project design advances and as improvements and adaptive management are identified through all stages of the Project.

The key objectives of this Plan are:

- Follow the guidelines of international best practices, legal requirements and commitments; and ensure these are met throughout the construction and operation activities that relate to management of biodiversity impacts;
- Define and implement the roles and responsibilities, training and scheduling towards avoiding, minimizing, reducing, and mitigating impacts on terrestrial biodiversity in the Project's BAOI; and
- Define the Key Performance Indicators (KPIs) that will be used to assess the effectiveness and success of the Plan at managing biodiversity impacts.
- Specify requirements for biodiversity management during construction and operations, as per the ESMP

1.2 Scope

This plan is part of DGDC's Environmental and Social Management System (ESMS). This Plan covers all DGDC activities with the potential to impact terrestrial biodiversity. It includes activities carried out on DGDC's behalf by contractors and subcontractors. The plan does not substitute any other legal means.

1.3 Key Impacts

Direct and indirect impacts to biodiversity can occur during the following Project Construction and Operation activities.

Construction phase:

- Construction activities for Power Plant and temporary laydown areas, production well pad, reinjection well pad, reinjection pipeline right-of-way (RoW), and access road to power plant, which will result in vegetation and habitat loss, fragmentation, noise, erosion and sedimentation, wildlife disturbance and displacement;
- Operation of the drill rig and steam blow testing, which will create noise, vibration and related wildlife disturbance;
- Operation of heavy machinery and vehicles for transportation, which will create noise, vehicular mortality, accidental fuel spills, and related wildlife disturbance;
- Accidental spills of uncontrolled discharges of geothermal fluids and other hazardous wastes,
- Erosion and sedimentation of water courses;
- Introduction of invasive species during vegetation removal and transportation of vehicles, equipment and soil; and
- Use of artificial night light during construction activities, which will create wildlife disturbance and mortality.

Operations phase:

- Operation of the air cooler condenser fans, which will create continuous noise and related wildlife disturbance;
- Brine ponds to collect geothermal fluids, which may create wildlife injury and mortality;
- Use of artificial night light during operations, which will create wildlife disturbance and mortality; and
- Unexpected event of well blow out, which will result in vegetation loss and disturbance, noise, wildlife displacement, injury and mortality.

The most significant Project impacts on terrestrial biodiversity will occur during the construction phase, which includes onsite vegetation clearing, an increase in noise and vibrations, and the potential for accidental spills of geothermal brine fluid. During operations, the most significant Project impact to flora and fauna biodiversity are noise, fragmentation/reduction in ecological connectivity, and an unlikely scenario of a well blowout vapor explosion, which will cause additional direct impacts of disturbance, injury and/or mortality of terrestrial wildlife species..

The primary species of concern with respect to direct mortality and injury include:

1. Endemic amphibian and reptiles present in the BAOI that will be subject to injury or mortality during ground disturbing activities, such as Martinique Robber Frog (*Eleutherodactylus martinicensis*, NT) and the Dominica ground lizard (*Ameiva fuscata*).
2. Threatened birds species present in the BAOI, such as the Red-necked Amazon (*Amazona arausiaca*, VU), the Imperial Parrot (*Amazona imperialis*) and endemic bird species such as the blue-headed hummingbird (*Cyanophaea bicolor*), and plumbeous warbler (*Dendroica plumbea*). These bird species regularly use or have been recorded within the Project area; foraging and nesting areas may be impacted by vegetation clearing.
3. Bats that regularly forage in the Project area that may include the Dominican Myotis (*Myotis dominicensis*) a Dominican endemic.

1.4 National/International Standards

National standards and action plans relevant to biodiversity protection and management that are established under the **Dominica** laws and regulations include the following:

- **Forestry and Wildlife Act No 12 (1976):** An Act to make provision for the protection, conservation and management of wild animals, amphibians, crustaceans, freshwater fishes, and reptiles, and for purposes connected therewith. States that the Forestry and Wildlife Division of the Ministry of Agriculture and Fisheries' shall promote forest and wildlife conservation and management in Dominica under the general supervision of the Permanent Secretary of Agriculture and Fisheries' and under the authority of the Minister.
- **Forest Act (1959):** An Act to make provision for the conservation and control of forests, defines the power of the President, the Director of Forestry and Wildlife and forest officers, which are assigned by this Act
- **National Parks and Protected Areas Act (1975):** provides for the establishment of National Park's Section under the Forestry and Wildlife Division, consisting on a National Parks Service, a National Parks Advisory Council and a Director of National Parks, working together with several part-time and full time park officers and a Park Superintendent.

Dominica is a signatory to various international conventions related to biodiversity:

- **The Convention on Biological Diversity (CBD):** Objectives of the CBD include conservation and sustainable use of biological diversity, access to and equitable distribution of the benefits of genetic resources, and appropriate transfer of technology.
- **The Convention on the International Trade in Endangered Species (CITES):** CITES's goal is to safeguard against threats to the survival of listed species arising from international trade in specimens, parts, or products of those species.
- **The International Plant Protection Convention (IPPC):** IPPC is an intergovernmental treaty with the goal of protecting the world's plant resources from the spread and introduction of pests and promoting safe trade.
- **UN Framework Convention on Climate Change:** International environmental treaty addressing climate change, negotiated and signed by 154 states at the United Nations Conference on Environment and Development, informally known as the Earth Summit, held in Rio de Janeiro from 3 to 14 June 1992; and

In addition to the above international conventions, the World Bank Performance Standard 6 (WB PS 6) analogous to the International Finance Corporation's Performance Standard 6 (IFC PS6) requires that project sponsors avoid, minimize, and restore threats to biodiversity arising from their operations. WB PS 6 specifies that mitigation measures should be designed to achieve 'no net loss' of biodiversity and favor impact avoidance and prevention over reduction and compensation (offsetting). WB PS6 also requires project developers to develop and implement a monitoring and evaluation program to document the project's progress at implementing the agreed-upon controls, restoration, and mitigation measures, and their effectiveness at mitigating for impacts.

1.5 Mitigation Measures

1.5.1 Minimize Project Footprint

According to the Jacobs ESIA (2018) and Eclipse ESIA (2020), DGDC has redesigned the Project footprint and proposed equipment to minimize overall Project impacts with the reduced reinjection

pipeline length and drilling of a closer reinjection well. The Project modifications consist of minimizing the Project footprint and vegetation clearing from 5.4 ha (1.4 ha cleared for power plant and 4 ha for the 10 m RoW reinjection pipeline) to 3.57 ha.

Habitat cleared will be the minimum possible, with any RoW area required maintained at the minimum width necessary. Temporary fencing will be used to prevent inadvertent damage outside designated construction areas.

1.5.2 Pre-clearing Surveys, and Rescue and Relocation

Once the area slated for vegetation removal has been demarcated, terrestrial plant and fauna specialists will conduct pre-vegetation clearing surveys. Specialists with demonstrated experience and knowledge of terrestrial plant and fauna species will be required to confirm whether any endangered or endemic fauna are present in the area to be cleared, and to be handled appropriately. The following management measures will be utilized:

- Acoustic deterrents will be used to disperse terrestrial ground-dwelling and flying fauna;
- Specialists will record any fleeing fauna by type and number of individuals, as feasible, to supplement baseline records;
- Bat specialists will survey the Project area demarcated for vegetation removal as well as a 50 m buffer for roosts to be humanely excluded from the area;
- Any reptiles, amphibians, or small mammals remaining in the area slated for vegetation removal will be captured, photographed, measured, and relocated to suitable nearby habitat. This will be performed by specialists and trained locals. Suitable habitat will be determined prior to clearing surveys and will be within similar ecological characteristics and requirements;
- A chytrid protocol will be utilized when handling all amphibians due to previous reported cases occurring within the Mountain Chicken Frog (*L. fallax*). Separate containers and gloves will be utilized by specialists when handling amphibians and boots will be washed after each rescue and relocation period to avoid spreading the invasive fungus (*Batrachochytrium dendrobatidis*).
- If Project vegetation removal and ground-disturbance activities cannot avoid the bird-nesting and bat-breeding season (April through August), pre-clearing surveys will identify features to be avoided and 20 m buffers will be set up around sensitive areas during the construction phase. In this situation, the Environmental Coordinator will be notified and specialists will be contacted to identify species and determine how to avoid or relocate;
 - Examples of sensitive features and areas are active endemic or threatened bird nests, maternal bat roost colonies and other microhabitats that are being used for reproduction and raising young.
- Rescue and relocation efforts will be recorded within a monitoring database. Every individual rescued will be provided an ID number. Rescue and relocation records will include a photograph, time, date, collector, and location coordinates and mortality (if any).

1.5.3 Best Practice Vegetation Removal

DGDC will implement and manage activities related to the vegetation removal and tree felling process. The specific objectives of this project are to implement best-practice vegetation clearing methods. To minimize impacts, DGDC will implement the following best-practice measures:

- Technical delimitation of authorized clearing areas, using security tape at a height of 1.5 m, visible enough to isolate the intervention area, and implementation of enforcement measures to avoid footprint “creep” into surrounding areas;

- Minimize cleared areas and any temporary work camp sites;
- Maintain vegetation barriers and trees where feasible;
- Inspection of each target tree to identify risks and potential emergency situations, considering the location, inclination, physical state, extraction trails, wind conditions, and determination of the desired fall path;
- Completion of vegetation removal and tree felling by workers with experience and training in tree felling;
- Biologist identification of any sensitive fauna species in the area where tree felling will occur;
- Tree felling during a time when impacts to fauna (breeding birds and bats) are minimal;
- Whenever possible, vegetation clearance activities should commence outside the breeding season of the key threatened species. The breeding season of the key bird species are between January and August; Bats breed between April and August; Amphibians breed year round, but primarily between May and July. Advice should be sought from local authorities and experts on this matter;
- One days prior to tree felling and vegetation removal, fauna dispersal utilizing noise (i.e., horns, machine equipment-chainsaws or other appropriate measures, etc.); Refer to section 1.5.2 above;
- Presence of wildlife specialist onsite as observers during vegetation removal to capture and relocate fauna offsite to undisturbed nearby habitat;
- Use of low-impact and directed logging techniques;
- A phased, directional approach to tree felling to allow mobile animals to escape from forest clearing activities; trees will be felled in a direction that will minimize damage to neighboring vegetation;
- Avoid piling of clear-felled vegetation on standing live vegetation, and
- Manage cleared material to minimize potential bush fire sources.

1.5.4 Revegetation of Temporary Areas

DGDC will support measures designed to conserve and revegetate as much cleared vegetation as possible within the Project Area. The details of these measures are described herein:

- Rehabilitation of all disturbed areas (e.g., temporary laydown areas) will be undertaken following construction. This will be done in such a way as to facilitate natural regeneration of vegetation;
- Specialists will determine selection of native trees and shrubs to replant to ensure appropriate succession of native trees and reduce the potential for bush fires;
- In appropriate areas, native and endemic trees that may be used as food sources by native bats and birds will be planted in temporary cleared areas; and
- Habitat will also be restored and/or enhanced to increase the value to wildlife. For example, rocks and woody debris can be added to areas to increase availability of wildlife refuges.

1.5.5 Habitat Management Biodiversity Offset

DGDC will implement a Habitat Management Procedure (HMP) to offset impacts to terrestrial natural habitat by the Project components. The Project modifications consist of clearing vegetation within 4.62 ha, of which 2.7 ha is natural tropical forest habitat.

The objectives of the HMP is to i) provide enhancement measures for post-Maria terrestrial biodiversity of the area, and ii) establish biodiversity offset required to achieve No Net Loss of Natural Habitats, with input from local specialists and stakeholders as appropriate.

The activities to be undertaken include:

- Plant native tree species and native grasses with organic fertilizer in areas where trees have fallen to stabilize ground conditions on bare slopes, improve ecological resilience, and reduce rainwater runoff and erosion;
- Plant native tree species in areas surrounding well pads and other infrastructure to reduce erosion and improve landscape connectivity;
- Support local nurseries to grow more trees to be planted and used by local community, as possible;
- Restore river courses by planting native trees, removing fallen trees and large rocks that may cause flooding and increased erosion; and
- Create microhabitats and hibernacula for animals impacted by the loss of tree canopy cover.

DGDC will identify degraded areas due to Hurricane Maria for restoration based on reduced and broken habitat cover, bare exposed ground, downed or damaged trees, and areas of debris build up due to Hurricane Maria. DGDC will restore 2.7 ha to compensate for the loss of natural habitat, and adhere to the “like-for-like or better” principle. Additional areas for restoration include sloped areas without trees or vegetation exposed by Hurricane Maria and landslides, as well as restoring connectivity of forest fragments to WHS.

1.5.6 Habitat Fragmentation Management

DGDC will manage activities to mitigate fragmentation and reduce ecological connectivity by the RoW of the pipeline, power plant, new access road, well pads and other associated infrastructure. DGDC will implement the following:

- Design the reinjection pipeline such that smaller animals can pass under it;
- Install under/overpasses at intervals along its length to minimize fragmentation effects and allow passage of animals across the corridor;
- Tree barriers surrounding the perimeter of Project components will be maintained; and
- Temporary laydown areas will be replanted with native species as soon as possible after construction

1.5.7 Artificial Lighting Management

Impacts due to artificial lighting at night for wildlife are wide ranging. In the natural world, light serves as an information source to wildlife and artificial lighting can provide misleading cues (Gaston et al., 2013)¹. Impacts include changes to behavior that occur at night, such as foraging, reproduction and migration of fauna, such as the endangered Black-capped Petrel. Artificial nighttime lighting can also disrupt plants through disruption of the natural day-night cycle and can affect the circadian rhythms of animals. Night lighting can cause significant mortality to insects (Longcore and Rich, 2004)² and even negatively impact pollination, resulting in less fruit production and impacts on the terrestrial food chain as well as ecosystem services (pollination benefits to people). While exact impacts to particular species are often unstudied, it is

¹ Gaston, K.J., Bennie, J., Davies, T.W., Hopkins, J. 2013. The Ecological impacts of nighttime light pollution: a mechanistic appraisal.

² Longcore, T. and Rich, C. Ecological light Pollution. *Frontiers in Ecology and the Environment*. Vol. 2. 191-198.

reasonable to assume that adding significant amounts of nighttime light to a formerly dark area will result in some ecological impacts.

The Project will implement measures to minimize the impacts due to artificial nighttime lighting, which will be designed to ensure lighting is placed strategically and implemented throughout the duration of the Project lifetime. The Project will consider light intensity and configuration, spacing, height, and directionality to reduce the intensity and spillage of light to minimize overall illumination. The following measures will be implemented to minimize the impacts of artificial nighttime lighting:

- Reduce the duration of light to extent possible via the use of timers and motion detectors;
- Avoid ultraviolet (UV) light and shorter wavelength light;
- Use low wattage lamps (<70 Watts (W));
- Use yellow light or red light that does not contain blue, violet, or UV wavelengths, as these attract fewer insects than UV or bluish/white lights;
- Plan and design light intensity and configuration, spacing, height, and directionality to reduce the intensity and spillage of light to minimize overall illumination;
- Use light only when needed and preferably turn off lights during times of peak bird migration;
- Ensure there are light-exclusion zones within the Project property;
- Avoid upward pointing lights and install directional accessories on existing light units to direct light away from sensitive areas and minimize light spill, if necessary; and
- Adapt mitigation measures if lights are shown to have an impact based on bird, bat, and invertebrate monitoring reports.

1.5.8 Noise and Vibration Mitigation

Noise impacts from the Project construction is expected to impact nearby fauna due to its magnitude and duration, which will occur for at least one reproductive cycle. Therefore, the Project will implement measures to minimize the impacts due to noise and vibration for each Project phase.

During Construction phase:

- Implement Noise Management Plan to provide a framework for addressing construction noise levels within IFC EHS limits;
- Adopt construction works Best Management Practice (BMP) and Best Available Technology practices;
- Use well maintained equipment to reduce noise emissions;
- Implement noise screening in areas where sensitive receivers are located, and assess the use of sound barriers when not simultaneous to hurricane season;
- Maintain existing trees and vegetation along Project boundaries and undeveloped areas;
- Restrict high noise activities to daylight hours (7 am to 5 pm), where possible;
- Sequence drilling operations so that the vibration-intensive activities do not occur simultaneously;
- Install sound-suppressive devices such as silencers and mufflers on heavy equipment and trucks as necessary;
- Install shock absorbers on drill machinery, as necessary; and

- Where applicable, avoid well blow venting and drilling during breeding season of birds and bats (End of January to August).

During Operations Phase:

- Adjust air-cooled condenser units speed drives to reduce noise if necessary;
- Ensure and maintain all fixed and mobile equipment in good working order; and
- Maintain tree barriers and plant dense vegetation near air cooler condensers.

1.5.9 Invasive Species Management

Invasive species are considered the greatest threat to biodiversity in geographically and evolutionarily isolated systems such as islands of the Caribbean, due to their unique endemism and high vulnerability (Kairo *et al.*, 2003)³. Several examples of invasive species that have been brought to the island include lemon grass (*Cymbopogon citratus*), wild ginger (*Hedygium coronarium*) and the Puerto Rican Crested Anole (*Anolis cristatellus*). Early detection and control of species invasions are more likely to prove effective and sustainable than remediation measures. Following with Article 8 of the Convention of Biological Diversity, DGDC will implement measures to “prevent the introduction of, control or eradicate those alien species which threaten ecosystems, habitats or species” (CBD, 1992).

In addition to following the Dominica entry port control measures and regulations against pests and invasive species, the Project will implement the following measures to avoid and mitigate possible introductions of invasive flora and fauna:

- Machinery and vehicles will be cleaned upon entry/exit, and any soil brought on or off site screened for invasive species or plant pathogens.
- Disturbed areas will be rehabilitated at the earliest opportunity with native and endemic species to minimize the establishment of invasive plant species;
- Source areas such as vehicle parking and construction lay down areas will be kept clean of invasive plants to minimize the presence of seeds that can be dispersed unintentionally;
- Prohibit the use of pesticides or herbicides on site; and
- Regular and ongoing monitoring of the presence of invasive plant species will be conducted within construction and rehabilitated sites and removal operations implemented according to the results.

1.5.10 Worker Education and Conduct

To minimize disturbance and harassment to wildlife or extraction and damage to plants, DGDC will implement the Workers Safety, Health and Environmental Policies and Procedures and train workers regarding the importance of limiting interactions for with plants and animals.

The Workers Safety, Health and Environmental Policies and Procedures establishes Health and Safety instructions and regulations in regards to hunting and harassment, prevention of wildlife vehicle collisions, and safety procedures when finding injured, sick or trapped wildlife. These measures are included in the mitigation measures below.

To mitigate potential impacts of increased access to the Project site and a potential increase in hunting of wildlife, the following management and mitigation measures will be implemented:

³ Kairo, M., Ali, B., Cheesman, O., Haysom, K. and Murphy, S., 2003. Invasive species threats in the Caribbean Region. Report to the Nature Conservancy, Arlington

- Inductions/tool-box talks for staff will include reference to measures required to protect biodiversity, including:
 - Restrictions and prohibitions on harassment, hunting, trapping, gathering, buying, and/or selling of flora and fauna species (included contractors) on the project site;
 - Construction workers should be oriented not to engage in any illegal hunting or poaching in the project area and must be made aware of Dominica's Wildlife Laws;
 - Information on species present within the area, especially endangered or threatened species;
 - Procedures regarding how to proceed if alive, injured, or dead animals are found;
 - Delimitation of work areas; and
 - Information regarding appropriate behavior prior to beginning construction.
- Install signs along roads which indicate speed limits, as well as speed bumps;
- Along roads frequently crossed by animals, DGDC and its contractors will install wildlife crossing signs within the Project;
- Prohibit the possession of personal firearms or other hunting weapons by personnel and contractors within the Project area; and
- Procedures for flora and fauna incident reporting and follow up.

1.5.11 Protected Area and Area of Conservation Importance

The Morne Trois Pitons WHS has been designated for its OUV, including as 'one of the very rare and largely intact forest areas remaining in the Insular Caribbean', within 'a largely undisturbed setting of stunning scenic value' (TBC 2020). Although the Project will not directly impact the Morne Trois Pitons National Park (MTPNP) and World Heritage Site (WHS), as the footprint falls outside of this protected area, potential impacts may be received due to noise and potential increases in hunting. The UNESCO Mission Report (UNESCO, 2017b) considered that habitat loss required for the construction of the power plant and installation of the pipeline could negatively impact the red-necked parrot, and potentially other threatened species. Mitigation measures will minimise habitat loss in the vicinity of the Project infrastructure and no habitat loss will take place within the WHS. Ongoing close engagement with the World Heritage Commission is recommended to ensure concerns are appropriately considered and addressed.

The Project will commit to the following actions:

- Participation and collaboration with the Management Committee and western sub-committee of the Park to maintain a buffer zone management plan for MTPNP WHS;
- Support proposed activities and programs to implement the objectives of the buffer zone;
- Participation, collaboration and support of an initiative to restore bare ground and forest cover; and
- Collaborate and support community awareness programs and monitoring of key biodiversity values within the buffer zone and WHS.

DGDC will monitor flora, mammals, birds, amphibians, reptiles, fish and aquatic invertebrates with special focus for species of concern listed in section 1.3 within the BAOI (refer to details in section 1.8). As the BAOI includes 11.8 ha of the MTPNP WHS and an additional 22.7 ha of the buffer boundary, monitoring will include the presence of at least four additional priority species supported by habitat in MTPNP and considered threatened by IUCN, the giant ditch frog (*Leptodactylus fallax*), imperial parrot (*Amazona*

imperialis), forest thrush (*Turdus lherminieri*), and a species of tree frog (*Eleutherodactylus amplinympha*).

1.6 Roles and Responsibilities

All contractors are required to incorporate these mitigation measures and management controls into their own procedures and work plans. The Engineering, Procurement and Construction (EPC) for each Project component (well pads, reinjection pipeline, power plant, and associated infrastructure) and all operation mitigation measures recommended in the ESIA will be the responsibility of the Operation and Maintenance (O&M) Contractor. DGDC's Environmental Coordinator will be responsible for verifying monitoring of mitigation measures implemented.

DGDC will provide oversight to Contractors to ensure that the mitigation measures and controls are implemented and that measurements comply with the standards listed in Section 1.4 of this BMP. This will be achieved through planned periodic inspections, audits of Project sites, and the implementation of monitoring programs. DGDC's Project Manager and Environmental Coordinator will be responsible for maintaining records of corrective actions and associated reports. They will also be responsible for supervising the implementation of corrective actions and/or training programs to avoid the repetition of non-conformities and non-compliance with standards.

1.7 Summary Table of Verification of Mitigation Measures and Key Performance Indicators

Table 1-1 presents the impact avoidance, minimization, and mitigation activities that are specific to biodiversity to be implemented during the pre-construction, construction, and operations phases of the Project. Impacts and mitigation measures are summarized here that include the Jacobs ESIA (2018), Eclipse ESIA (2020), the Habitat and Biodiversity Management plan, and additional measures defined per impacts in the Addendum to the ESIA.

Table 1-1: Summary of Biodiversity Impacts, Mitigation Measures, Timing, Monitoring, KPIs, and Responsibilities

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
Clearing of vegetation during construction of Project Infrastructure	Direct loss and disturbance of vegetation, secondary natural forest, and terrestrial wildlife habitat	Minimize	Minimization of Project Footprint	Pre-construction	Documentation of project footprint	Project footprint reduced to 4.6 ha	DGDC/Environmental Coordinator and EPC Contractor
		Avoid	Avoid removal of trees, where possible, and vegetation along Project boundaries and in undeveloped areas	Construction	Daily vegetation clearing reports	Vegetation disturbance is limited to RoW and footprint	DGDC/Environmental Coordinator; and EPC contractor
		Avoid and Minimize	Minimize impacts by demarcating area of removal with fences to avoid “creep” into surrounding areas and have technical specialist implement best-practice vegetation clearing methods	Construction	Daily vegetation clearing reports	100% of minimization measures are implemented successfully	DGDC/Environmental Coordinator and specialized contractor

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
		Avoid and Minimize	Employ an environmental/biodiversity construction monitor during site preparation activities to ensure proper implementation of the measures defined herein, identify potential unforeseen impacts to terrestrial, and to apply adaptive management where needed to minimize impacts on vegetation and wildlife, particularly rare species	Pre-construction	Daily reports documenting the day's activities and findings	Specialist hired with biology/environmental training	DGDC
		Restore	Restore and revegetate temporary laydown areas post construction with native trees and shrubs	Post-construction and operations	Revegetation activity reports	100% revegetation of temporary laydown areas with native species	DGDC/Environmental Coordinator,
		Offset	Implement the Habitat	Operations	<ul style="list-style-type: none"> ■ Forest cover 	Goals for offset plan are	DGDC/Environmental

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
			Management Plan		monitoring reports <ul style="list-style-type: none"> Restoration management reports 	achieved; all identified areas impacted by Hurricane Maria are restored/reforested	Coordinador, EPC or O&M Contractor
	Mortality, Injury and Disturbance to Fauna	Avoid and minimize	Pre-clearing surveys will deter fauna from Project clearing areas using acoustic deterring methods	Pre-construction	Pre-clearing activity reports and records	<ul style="list-style-type: none"> 100% Implementation of humane wildlife acoustic deterring devices Number of species recorded in database 	DGDC/Environmental Coordinator, contracted wildlife specialists
		Avoid and minimize	Implement a Chytrid Prevention protocol when handling all amphibians	Pre-construction	Pre-clearing activity reports and records	Use of a Chytrid prevention protocol	Contracted wildlife specialists
		Avoid	Conduct bat roost census and implement humane physical or acoustic exclusion measures to	Pre-construction	Bat roost census reports and records	100% Implementation of humane exclusion measures for existing bat roosts	DGDC/Environmental Coordinator and contracted bat specialist

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
			keep bats away from site				
		Avoid and Minimize	Rescue and relocate sessile species to undisturbed sites	Pre-construction	Rescue and relocation records to be prepared for all individuals	<ul style="list-style-type: none"> ■ Identification and successful translocation of sessile fauna from the pad sites prior to site preparation activities ■ No mortality during rescue and relocation 	DGDC/Environmental Coordinator, contracted wildlife specialists
		Avoid	Avoid vegetation clearing and site preparation activities, as feasible, between January and August to avoid impacts on bird breeding season	Construction	Daily vegetation clearing reports	No nests impacted	DGDC/Environmental Coordinator and EPC Contractor
	Spread invasive and exotic plant species in temporary laydown areas	Avoid, Minimize	Revegetation and restoration of temporary laydown areas with native and endemic species	Operations	Revegetation activity reports	100% revegetation of temporary laydown areas with native species	DGDC/Environmental Coordinator

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
Vehicular traffic and use of heavy machinery along access roads	Direct mortality or injury of wildlife	Avoid	Assess areas for frequent wildlife crossing, install wildlife crossing signs and speed bumps	Construction and Operations	Photographic documentation of signs; wildlife-vehicle incident reporting	<ul style="list-style-type: none"> ■ 100% of wildlife crossing signs installed along Project property, if necessary ■ No injury or mortality of wildlife due to Project-related traffic 	DGDC/Environmental Coordinator and EPC Contractor
		Minimize	Implement Road Safety Plan in regard to traffic (<i>i.e.</i> Install road signs and enforce speed limit)	Construction and Operations	Photographic documentation of signs; wildlife-vehicle incident reporting	<ul style="list-style-type: none"> ■ 100% of road signs installed along Project property 	DGDC/Environmental Coordinator and EPC Contractor
		Avoid	Induction toolbox talks include importance of Road Safety Plan in regard to wildlife	Construction and Operations	Photographic documentation of talks and ESMS reporting documentation	<ul style="list-style-type: none"> ■ All staff attend toolbox talks ■ No injury or mortality of wildlife due to Project-related traffic 	DGDC/Environmental Coordinator and EPC Contractor
	Spread invasive and exotic plant species in	Avoid	Inspection of all equipment with arrival of	Pre-construction	Inspection reports	100% of inspection of all foreign	DGDC/Environmental Coordinator

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
	temporary laydown areas		overseas equipment following port regulations	and construction		equipment and supplies	and EPC Contractor
		Avoid	Machinery and vehicles cleaned upon entry/exit,	Construction and Operations	Vehicle and parking area washing logs	100% cleaning and clearing of all invasive species	DGDC/Environmental Coordinator and EPC Contractor
	Traffic and site preparation activities may create dust	Minimize	Regular watering of Project areas to minimize dust	Construction	Documentation of Project footprint through monitoring.	No vegetation degradation from dust accumulation as documented through monitoring.	DGDC/Environmental Coordinator and EPC Contractor
Transportation of equipment, and soil off/onsite	Introduce invasive insect pests and flora that could cause disturbance to natural vegetation species in the BAOI	Avoid	Screening of soil brought on or off site for invasive species or plant pathogens.	Construction and Operations	Soil management records	100% screening of all soil	DGDC/Environmental Coordinator and EPC Contractor
Operation of the drill rig, blow testing, and other construction activities	Generated air emissions which could adversely affect susceptible wildlife	Avoid and minimize	Implement air quality management plan and monitor air quality to	Construction	Air quality monitoring reports	Air quality does not exceed IFC EHS thresholds	DGDC/Environmental Coordinator and EPC Contractor

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
			meet IFC EHS standards				
	High Noise levels causing wildlife displacement and mask acoustic calling, thus affecting mating and feeding behaviors, within the BAOI	Minimize	Install sound-suppressive devices and/or screens where necessary	Construction	Photographic documentation; pre-drilling and construction preparation reports	NA	DGDC/Environmental Coordinator and EPC Contractor
Minimize		Maintain vegetation barriers surrounding Project Area	Construction	Vegetation clearing daily reports	Vegetation disturbance is limited to well and injection pad sites	DGDC/Environmental Coordinator and EPC Contractor	
Minimize		Provide regular maintenance to all vehicles and Install silencers to vehicles and heavy equipment	Construction and Operation	Maintenance and inspection logs	Vehicle noise does not cause exceedance of IFC EHS noise thresholds	DGDC/Environmental Coordinator and EPC Contractor	
Avoid		Avoid drilling and steam blow testing, as feasible, between January and August to avoid impacts on maternity colonies of bats, and parrot breeding season	Construction	Scheduled construction timeline;	<ul style="list-style-type: none"> ■ No abandonment of breeding territories in and around the Project ■ No significant population decrease in threatened 	DGDC/Environmental Coordinator and EPC Contractor	

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
						Red-neck Amazon colonies surrounding Project site	
		Avoid and Minimize	Survey areas for existing bat roosts and implement humane physical or acoustic exclusion measures to keep bats away from site	Pre-construction	Bat survey census reports and records	100% of roosts are cleared prior to construction, if found within Project boundaries	DGDC/Environmental Coordinator and contracted bat specialist
	Generation of localized vibrations sufficient to harm ground-dwelling terrestrial wildlife.	Minimize	Assess the need of a shock absorber, or damper on the drill	Construction	NA	Vibration ground disturbance is monitored	DGDC/Environmental Coordinator, drilling contractor
		Minimize	Sequence drilling operations so that the vibration-intensive activities do not occur simultaneously	Construction	Scheduled drilling timeline	Drilling timeline is schedule to reduce overlap of drilling activities, as feasible	DGDC/Environmental Coordinator, Drilling contractor
		Avoid/Minimize	Implement pre-construction surveys to relocate ground	Pre-construction	Pre-clearing activity reports and records; Rescue and	<ul style="list-style-type: none"> ■ Identification and successful translocation 	DGDC/Environmental Coordinator

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
			dwelling wildlife from the activity sites to the extent practicable		relocation records	<p>of sessile ground fauna from the pad sites prior to site preparation activities</p> <ul style="list-style-type: none"> ■ No mortality during rescue and relocation 	
Operation of air cooler condenser fans	High Noise levels causing wildlife displacement and mask acoustic calling adjacent to the Project	Minimize	Adjust air-cooled condenser units speed drives to reduce noise if necessary;	Operations	Operations noise monitoring logs	Operations noise is monitored and speeds are adjusted, if necessary	DGDC/Environmental Coordinator and EPC Contractor
		Minimize	Maintain tree barriers and dense vegetation near air cooler condensers.	Operations	Vegetation clearing and revegetation activity reports	Vegetation disturbance is reduced to well and injection pad sites	DGDC/Environmental Coordinator and EPC Contractor
Artificial Night lighting during construction and operations	Introduced artificial night lighting could act as attractants for night-migrating or nocturnal species, increasing the potential for collision with	Minimize	<ul style="list-style-type: none"> ■ Assess and design light intensity and configuration, spacing, height, and directionality to reduce the intensity and spillage of 	Pre-construction	NA	No impacts to birds and bats due to artificial light night	DGDC/Environmental Coordinator and EPC Contractor

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
	lighting structures, increased energy expenditure, or increased predation		light to minimize overall illumination				
		Minimize	<ul style="list-style-type: none"> ■ Minimize the amount of artificial lighting used at the pad sites with the following: ■ Use directional lighting (downward facing lighting) and direction accessories ■ Avoid the use of UV light 	Pre-construction	Lighting design	<ul style="list-style-type: none"> ■ Assessment of all lighting structures and areas ■ Demonstrated reduction of impacts for nocturnal fauna, including bats, birds and mortality to insects. 	DGDC/Environmental Coordinator and EPC Contractor
Installation of a brine ponds	Holding of geothermal fluids may cause injury or mortality to terrestrial wildlife	Avoid	Installation of screen or nets over the brine collection pond to prevent wildlife contact with fluids	Construction and Operations	Photographic documentation	No mortality or injury to fauna associated with brine pond	DGDC/Environmental Coordinator and EPC Contractor

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
Worker Harassment	Disturbance, injury and mortality to fauna and flora	Avoid/Minimize	Provide training to Project field staff on the biodiversity features of the Project area, particularly the rare and endemic species potentially present in the area, wildlife management, and the procedures defined in this Biodiversity Management Plan	Worker Induction, tool-box talks	Documentation of Training provided to Staff, provision of written training materials, and attendance records	<ul style="list-style-type: none"> ■ 100% of workers trained 	DGDC/Environmental Coordinator and EPC Contractor
		Avoid/Minimize	Implement Worker Safety, Health and Environment Plan and procedures which prohibits wildlife hunting activities, poaching, or any form of harassment	Worker Induction, and pre-construction	Documentation of induction training provided to staff	100% worker attendance of trainings and safety inductions	DGDC/Environmental Coordinator and EPC Contractor

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
	Disturbance, injury and mortality to fauna and flora	Avoid/Minimize	Installation of no disturbance, no hunting or harassment of wildlife signs in work areas	Pre-construction	Photographic documentation	Signs installed in frequently viewed areas	DGDC/Environmental Coordinator
Solid and liquid Hazardous and non-hazardous waste	Injury and mortality to fauna and flora, and destruction of habitat	Minimize and avoid	<ul style="list-style-type: none"> ■ Implement waste management and hazardous waste management plans ■ Ensure standard safe storage measures for n-pentane 	Construction and operations	<ul style="list-style-type: none"> ■ Documentation of Storage facilities for waste ■ Waste maintenance logs 	<ul style="list-style-type: none"> ■ Use of Designated waste facilities ■ 100% of workers following waste management procedures ■ Water quality standards do not exceed IFC EHS Thresholds 	DGDC/Environmental Coordinator and EPC Contractor
Pollutants and surface water runoff	Destruction of habitat quality and mortality to fauna	Avoid and minimize	Implement standard construction site practices to avoid surface runoff	Construction and operations	<ul style="list-style-type: none"> ■ Construction site maintenance logs ■ Photographic documentation 	<ul style="list-style-type: none"> ■ Water quality standards do not exceed IFC EHS Thresholds 	DGDC/Environmental Coordinator and EPC Contractor

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
		Avoid and minimize	Install sediment barriers	Construction and operations	<ul style="list-style-type: none"> ■ Construction site maintenance logs ■ Photographic documentation 	<ul style="list-style-type: none"> ■ No evidence of sedimentation in rivers and stream below Project ■ Water quality standards do not exceed IFC EHS Thresholds 	
Indirect Impacts to MTPNP WHS or habitat downstream of Project	Noise impacts, increased hunting and reduced ecological connectivity	Minimize and restore	Participate, collaborate and support Management committee and sub-management committee of WHS buffer zone to i) support and coordinate proposed activities and programs, ii) assist in maintenance, iii) Provide monitoring research of key biodiversity	Operations	<ul style="list-style-type: none"> ■ Photographic documentation ■ Meeting attendance 	<ul style="list-style-type: none"> ■ 100% support and participation in buffer zone management and maintenance programs 	DGDC

Source of Impact	Impact	Mitigation hierarchy	Mitigation Measure	Timing	Monitoring	KPI	Responsibility
			<p>values (threatened and endemic species) and support, and iv) participate in community public awareness programs.</p> <p>Implement standard construction site practices and sedimentation barriers to avoid surface runoff</p> <p>Implement waste management plan and air quality management plan</p> <p>Maintain vegetation barriers along perimeter of footprint</p> <p>Installation of no disturbance, no hunting or harassment of wildlife signs in work areas</p>				

1.8 No Net Loss (NNL) Biodiversity Monitoring and Reporting

DGDC will monitor the flora and fauna within the BAOI to assess effectiveness of mitigation measures and evaluate impacts on flora, fauna, and the MTPNP WHS. Monitoring of the biodiversity priority values within the BAOI will demonstrate No Net Loss (NNL) with regards to biodiversity, as per IFC PS 6. NNL will be quantified and compared to baseline data collected by Caraïbes Environnement Développement & Collaborators in 2015, and Eclipse Inc. in 2017 and 2020.

DGDC will hire local field specialist to design specific monitoring protocols for each taxonomic group and components based on the recommended framework found in Table 1-2. Specialists will analyze data using baseline field data to compare and quantify NNL. It is recommended that contracted specialists include baseline survey locations in monitoring design for adequate and statistically relevant comparisons.

Table 1-2. Summary of Biodiversity Values to Monitor to demonstrate NNL

Biodiversity Priority Value/ Parameter	Metrics	Frequency
Revegetation and reforestation of riparian and forest habitat impacted by Hurricane Maria	<ul style="list-style-type: none"> ■ Percent vegetation cover over time ■ Flora species richness ■ 	<ul style="list-style-type: none"> ■ Annually during construction and Operations up to year 5
Avifauna, with focus on Red-necked Amazon (<i>Amazona arausiaca</i>)	<ul style="list-style-type: none"> ■ Species richness ■ Abundance ■ Presence of <i>A. arausiaca</i> 	<ul style="list-style-type: none"> ■ Biannually during construction ■ Annually during operations up to year 5
Bats	<ul style="list-style-type: none"> ■ Species richness ■ Abundance 	<ul style="list-style-type: none"> ■ Pre-construction Baseline census ■ Annually during construction ■ Annually during operations up to year 3
Reptiles	<ul style="list-style-type: none"> ■ Species richness ■ Abundance 	<ul style="list-style-type: none"> ■ Annually during construction and operations up to year 5
Amphibians	<ul style="list-style-type: none"> ■ Species richness ■ Abundance ■ Number of tadpoles 	<ul style="list-style-type: none"> ■ Biannually during construction ■ Annually during operations up to year 5
Fish and aquatic invertebrates	<ul style="list-style-type: none"> ■ Species richness ■ Abundance ■ Presence of invertebrate ecological indicators 	<ul style="list-style-type: none"> ■ Biannually during construction ■ Annually during operations up to year 3

2. EROSION AND SEDIMENT CONTROL PLAN

2.1 Introduction

The Erosion and Sediment Control Plan (ESCP) has the purpose of ensuring the reduction of the project's potential impacts on the soils and the water resources in its area of influence, as well as documenting and monitoring the mitigation measures that will be implemented. The plan includes methods that will guide the personnel involved in the project to manage, mitigate and / or avoid (as much as possible) adverse effects with regards to soils. In general, erosion and sediment control is part of the design for construction activities that the contractor must prepare for any project.

2.1.1 Objective

The key objective of this Plan is to ensure that the effects of erosion and sedimentation on the environment are minimized by minimizing soil disturbance, degradation and erosion resulting from Project activities. The more general objectives of this plan include:

- Comply with the relevant country regulatory requirements;
- Avoid and control soil erosion and contamination;
- Follow best international practices guidelines;
- Define the procedures, integrated controls and mitigation measures to be used in construction activities and project operation phases that have the potential to cause adverse impacts;
- Define the roles and responsibilities for the implementation of this Plan; and
- Define procedures for monitoring the efficiency of the mitigation measures, the generation of reports, interventions, and the adaptation of the plan.

2.1.2 Scope of Application

This procedure will apply during the development of DGDC's activities and during the Project's life cycle (construction, operations and decommissioning). It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's Environmental and Social Management System (ESMS) policies and procedures, which are aligned to international best practices.

The Erosion and Sediment Control Plan includes measures to ensure that direct impacts (land disturbance) are limited to the works area, and that secondary impacts do not impact adjacent areas. This plan shall be distributed to all contractors / subcontractors, and it shall be included in all contractual documentation or as a contract amendment, if the Company was contracted before the creation of the ESMP, and used as a basis for all specific Erosion and Sediment Control Plans to be prepared by all engaged parties. Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

2.2 Roles and Responsibilities

In order to properly implement the Erosion and Sediment Control Plan, DGDC requires the involvement of the people listed in Table 2-1.

Table 2-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> Be familiarized, review and approve the Erosion and Sediment Control Plan
Director of Accounts	<ul style="list-style-type: none"> Ensure the availability of resources necessary for the implementation of the Erosion and Sediment Control Plan
Head of Environmental, Social and Governance (ESG)	<ul style="list-style-type: none"> Assure the correct implementation of the Erosion and Sediment Control Plan
ESG Manager	<ul style="list-style-type: none"> Assure the correct implementation of the Erosion and Sediment Control Plan Update the Erosion and Sediment Control Plan Review and approve the contractor project-specific Erosion and Sediment Control Plan
Environmental Coordinator or H&S Manager	<ul style="list-style-type: none"> Ensure the generation of evidence and reports for compliance with the IFC PS as well as maintaining DGDC's KPIs. In addition, ensure the internal coordination to follow the Erosion and Sediment Control Plan
Contractor Company	<ul style="list-style-type: none"> Develop a project-specific Erosion and Sediment Control Plan
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> Understand and carry out the activities set out in the Erosion and Sediment Control Plan

2.2.1 Construction

Contractors are required to incorporate proposed mitigation measures and management controls in their own procedures and work plans, and in the Management Plans for each project. Their roles and responsibilities with regards to monitoring and implementation of mitigation measures will be clearly defined in these plans.

2.2.2 Operation

Monitoring of the condition of stormwater management structures will be performed during the routine site inspections to be performed by the Plant Managers. Any corrective actions will be implemented by the site General Maintenance personnel.

2.3 Key Impacts

The earth movement activities during land clearance and construction can lead to erosion, landslides, and sedimentation which can have the following impacts:

- Airborne dust
- Damage to native plants
- Pollution to local waterways and harm to aquatic animals within the local waterways
- Increase in flooding conditions.

Construction activities at the site include:

- Site clearing for drilling pads, plant infrastructure, and pipelines

- Movement of heavy equipment
- Construction of infrastructure
- Installation of pipelines

Once sites have been restored and/or rehabilitated, no erosion or sedimentation is expected during operational activities.

2.4 Mitigation Measures

2.4.1 Pre-Construction

During the design stage, erosion and sediment control measures will be included in the Project design to control runoff from construction areas. These designs will include temporary (for construction) as well permanent drainage systems (construction and operation), and will include gulleys and stormwater conveyance systems with gentle slopes with the purpose of diverting stormwater away from the project infrastructure in a manner which does not cause soil erosion or sedimentation. Deforestation and site clearance activities will be minimized to the extent possible.

2.4.2 Construction

The EPC Contractor will develop an Erosion and Sediment Control Procedure that they and all Subcontractors will implement during all Project construction works. The Erosion and Sediment Control Procedure will incorporate a Landslide Management Procedure, which will contain measures to reduce potential impacts of landslides (slope stabilization, planting, sandbags etc.), and Stormwater Management Procedures (SMP).

In order to reduce erosion and sedimentation during Construction, the following general mitigation measures should be applied:

- The laying of overland flow diversion drains and preload fill should be completed preferably during the dry season and prior to the power plant construction earthworks commencing.
- Disturbance area will be minimized and clearly demarcated.
- Works will only be conducted within the works zone.
- Vehicle movements will be restricted to the defined roads/tracks.
- Where possible, works area will be designed to ensure stormwater runoff drains into the site.
- Where runoff from the site is required, it will be via the longest flow path possible to ensure maximum sediment retention. Flows to undisturbed areas will be prioritized.
- Where required, sediment controls will be put in place. These will include, but not be limited to, sediment ditches, regulating dams such as rock check dams, sediment basins, sediment fences and silt socks. Silt curtains, fibrous mats etc. will be placed across as temporary stormwater drains to reduce the efflux velocity of the water and to aid settling of suspended sediment from the water.
- Develop banks and excavation slopes in accordance with the guidelines for geotechnical stability. All soil stockpiles that will not be immediately re-used will be seeded. Temporary stockpiles will be watered as required to suppress dust. Excavated earth should be strongly compacted and cut-off ditches should be dug in erosion prone areas to divert water away for the earthworks and to settling ponds before discharge to nearby water courses.
- Avoid building roads or access roads on slopes greater than 15% as a soil conservation measure.

- Deposit surplus material in previously approved areas or reuse it as fill material.
- Stabilization and progressive reforestation of affected areas with plants and vegetation native to the island.

Once the construction stage is complete, all areas, including access and service roads, which are not necessary for the project's operation will be restored to their original or better conditions.

2.4.2.1 Power Plant Construction

Following surveying of the boundary of the construction pad, diversion drains should be excavated around the perimeter of the site to convey overland flow to appropriate locations downstream. During construction these could be temporary excavations, rock or geotextile lined to reduce erosion.

Direct site runoff should be captured via interceptor ditches and sumps/sediment ponds. In localized areas, sediment runoff could be managed through silt fences. Grading the construction site to ensure runoff is captured and detained in these locations is essential, as its highly likely surface water will be sediment laden and will need some settling before discharge to the nearby Titou Gorge Stream (likely through a decant structure or overflow spillway in a sediment pond).

Any discharges of concentrated flow should be to watercourses that have adequate erosion protection in place to prevent gulying of channels, bank collapse and increased sedimentation downstream. This may require installation of reno mattresses or rock rip rap (adequately sized to convey flows and velocities) at the discharge point. The remaining channel (if it exists) may require further excavation to convey the increased flows, and subsequently the installation of a permanent channel draining from the construction pad settling ponds to the Titou Gorge Stream would be recommended.

Should local water sources be required for meeting some construction demands including vehicle and equipment washdown, the use of a temporary portable storage tank is advised. A 25,000 L plastic tank (3.6 m x 2.8 m) could provide storage for firefighting and water supply, and be topped up from local streams at low abstraction rates (<2 L/s) to minimize environmental impact.

2.4.2.2 Reinjection Pipeline Construction

Along the reinjection pipeline route catchment areas will be kept to small sizes with their own temporary drains and specific treatment devices.

Near stream works will require local sediment controls such as silt fences or downstream sediment traps to reduce the effects of disturbance. Water supply for concrete mixing will be minimal and infrequent, primarily used for support foundations

2.4.3 Operation

The O&M Contractor will develop an Erosion and Sediment Control Procedure that they and all Subcontractors will implement.

The O&M Contractor will ensure the following provisions are satisfied:

- Power plant site and laydown area will have a stormwater system designed to capture and treat any runoff. Stormwater conveyance systems will be adequately maintained in order to ensure stormwater flow does not lead to erosion and sedimentation.
- The power plant's stormwater system will drain through a sump or settling pond. This would capture any runoff from the pad and settle out rubbish and sediment, while reducing flow velocities.

- Areas of the plant that are at risk of having contaminant discharges (such as oil leaks from vehicles or fluid spills) should be isolated, with their flows first draining through an oil water separator. The outflows from this separator could then drain to the sump/settling pond for further treatment.
- Diversion drains will be installed around the site, the capacity of these drains needs to convey adequate flood events to reduce the likelihood of this occurring.
- Stormwater collected in secondary storage facilities will be discharged once it has been inspected for contamination, at low flow rates through the existing stormwater conveyance systems to allow for infiltration into the ground at the site. If any signs of oil sheen or contamination are observed in the collected stormwater, then it shall be handled in accordance with the Waste Management Plan.
- Sourcing a water supply for firefighting will be infrequent, however would require >500 m³ stored in a tank.
- The O&M Contractor will ensure a Subsidence Management Plan will be prepared and implemented.

2.5 Monitoring and Reporting


2.5.1 Construction

Each construction Contractor will establish an inspection and audit program that will include:

- Identification of performance indicators to be monitored
- Periodic audits and inspections of the contractors' work front to verify the correct implementation of the erosion and sediment control measures and plans, as well as the installation of erosion control systems.
- Inspections (periodic and unannounced) of clearing activities (felling and pruning).

The following figure present the typical audit process flow diagram for erosion and sediment control.

Figure 2-1: Erosion and Sediment Control Audit Flow Diagram



Monitoring during construction activities will be a constant occurrence, with daily visual inspections of work site. Sediment controls will be reviewed during site inspections and/or after significant rainfall (more than 10mm in 24hrs resulting in site runoff).

If erosion or sedimentation resultant of the construction activities taking place is observed during the site inspections, an incident report for non-conformance of sediment control will prepared. In addition, during week like site inspections, the location and condition of sediment control structures will be recorded.

If necessary, corrective actions will be carried out which will:

- Investigate cause of sediment control failure.
- Review flow path and determine most appropriate controls are in place, additional controls which can be place in-stream and/or changes that can be made to flow path
- Review similar controls on-site (even though these may not have failed) for similarities.

Specific Monitoring requirements are described below.

2.5.1.1 EPC Contractor Responsibilities

The EPC Contractor will ensure the following are satisfied.

- Inspection and maintenance – the ESCP shall specify who is responsible for inspecting all physical elements of the erosion and sediment control measures. These shall be inspected daily to ensure they are installed and working correctly. Any defects shall be rectified before earthworks occur in that area of the site. Accumulated sediment shall be removed from all features when it reaches 25% of the available space. Records of all inspection and maintenance shall be kept.
- Visual inspection of the raw water intake spring – the ESCP shall specify who is responsible for inspecting the unnamed spring upstream and downstream of the raw water intake works on a daily basis. The inspection should identify whether any visible change in water clarity or turbidity occurs after the works. If visible changes are observed, then modification of site operations and/or site erosion and sediment control practices should be made to reduce the impact. Records of all inspection and response activities shall be kept.
- The EPC Contractor will ensure that visual monitoring is undertaken at raw water intake spring banks and the construction of any diversion channels to identify any areas that may be performing inadequately (resulting in bank collapses, localized erosion hot spots and scouring).
- Prior and during construction it is recommended that monitoring of the flow rates be conducted at the small stream used for abstraction of water.
- The discharge from the sedimentation ponds should be monitored during rain events. At least once per month for total suspended solids for comparison with the discharge limit of 50 mg/l and to determine the effectiveness of the pond.

2.5.1.2 DGDC Responsibilities

The DGDC shall review and approve the EPC Contractor's Erosion and Sediment Control Procedure, including its Stormwater Management Procedure and landslide management procedure.

The DGDC shall continuously audit the EPC Contractors adherence to their Procedure and to monitoring requirements and shall upon finding any non-compliance, provide an immediate written notice to the EPC Contractor requiring them to correct the issue within a defined time period. The DGDC shall monitor that the EPC Contractor does in fact address all such matters; if the DGDC finds the EPC Contractor fails to

address the matters within the time period, the DGDC shall advise the Engineer to the EPC Contract, whom shall consider the issuance of a “stop work” notice.

2.5.2 Operation

The DGDC shall review and approve the O&M Contractor’s Erosion and Sediment Control Procedure.

The DGDC shall continuously audit the O&M Contractor adherence to their Procedures and monitoring requirements and shall upon finding any non-compliance, provide an immediate written notice to the O&M Contractor requiring them to correct the issue within a defined time period. The DGDC shall monitor that the O&M Contractor does in fact address all such matters; if the DGDC finds the O&M Contractor fails to address the matters within the time period, the DGDC shall use whatever mechanisms are available within the O&M Contractor’s contract to enforce compliance.

2.6 Training

All personnel will be trained on:

- General awareness and procedures concerning water management and the prevention of erosion and sedimentation;
- General awareness on key indicators of erosion and sedimentation in order to apply corrective actions;
- The appropriate disposal methods of collected stormwater.

2.7 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 2-2: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method / Tool / Frequency
Soil and Water Resources	No evidence of significant sediment deposition outside the works area.	100% of inspections	Construction	Site inspections, Weekly and after rain events
Soil and Water Resources	Total Suspended Solids in discharges	< 50 mg/L	Construction	Monthly
Soil and Water Resources	No evidence of significant drilling, gullies or other instances of run-off erosion.	100%	Construction and Operation	Site inspections, Construction: Weekly and after rain events, Operation: Monthly and after major rain events.
Soil and Water Resources	Employees must have the appropriate training	100%	Construction and Operation	Documentation verification. Construction: Induction training, Operation: Yearly

3. WASTE MANAGEMENT PLAN

3.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensure the compliance of the implementation of the Environmental and Social Management Plan (ESMP) policies and procedures.

To promote the Project’s alignment to best international practices, DGDC acknowledges that waste management measures are an essential part of any project. This Waste Management Plan details the steps to minimize environmental impacts through appropriate controls and site inductions of employees and sub-contractors. During the construction and operation phase of the Project, there is the possibility of generating solid, liquid, and hazardous wastes. This plan defines the various potential sources of waste, and sets out how they will be controlled and monitored for the duration of the projects.

3.1.1 Objective

The objective of this plan is to comply with all relevant host-country environmental regulations, reduce waste volume, maximize recycling, reuse and recovery, and prevent any construction waste/litter entering the environment. In general, the objectives of this plan include:

- Avoid and control the generation of waste related to the Project during the construction and operation phases;
- Define the procedures, integrated controls and mitigation measures to be used during the activities from the construction and operation phases that have the potential to affect the environment and the neighboring communities; and
- Comply with the requirements of the host country regarding the management and disposal of different types of waste.

3.1.2 Scope of Application

This procedure will apply during the development of DGDC’s activities and during the Project’s life cycle. It is DGDC’s responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC’s ESMP policies and procedures, which are aligned to international best practices.

The Waste Management Plan includes measures related to the management of waste derived from Project activities. This plan shall be distributed to all contractors / subcontractors, and it shall be included in all contractual documentation and used as a basis for all specific Waste Management Plans to be prepared by all engaged parties. Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

3.2 Roles and Responsibilities

In order to properly implement the Waste Management Plan, DGDC requires the involvement of the people listed below.

Table 3-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> ■ Be familiarized, review and approve the Waste Management Plan.

Director of Accounts	<ul style="list-style-type: none"> ■ Ensure the availability of resources necessary for the implementation of the Waste Management Plan
Head of ESG	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Waste Management Plan
ESG Manager	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Waste Management Plan ■ Update the Waste Management Plan ■ Review and approve the contractor project-specific waste management plan.
Environmental Coordinator or H&S Manager	<ul style="list-style-type: none"> ■ Ensure the generation of evidence and reports for national compliance and compliance with the IFC PS as well as maintaining DGDC’s KPIs. In addition, ensure the internal coordination to follow the Waste Management Plan ■ Approve the Contractors project-specific Waste Management Plan
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Waste Management Plan
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Waste Management Plan

Typical roles and responsibilities are as follows:

- As project phases unfold, Contractors will be responsible for overseeing the implementation of the waste management plan. Contractors must develop and deliver a list of all waste management procedures, specific to each function.
- Prior to the start of work involving the generation of waste, each Contractor must prepare its own management plans and inspection procedures. Said management plans will be reviewed and approved by the DGDC before the works begin, in order to ensure consistency between the waste management plans. In addition, Contractors will need to comply with all local rules and regulations including the correct classification, disposal and reuse of waste.
- Workplace supervisors will oversee health and safety factors for Contractors in relation to waste management and enforce established environmental incident prevention and safety practices. They will supervise waste activities comprised of classification, control, mitigation, transportation and disposal of all the waste generated by the projects.

3.3 Sources of Impacts

Most of the waste is expected during construction activities. The construction of the Project will generate typical industrial construction waste as well as typical household waste. During operation, personnel at the administration and control building, and the security building will generate typical office and household wastes.

If not properly managed, the potential impacts associated with the waste include:

- Visual impacts in the areas of the construction works;
- Contamination of soils and water resources;
- Impacts on animals;
- Impacts on human health;
- Odors from residues in surrounding areas; and
- Waste due to poor management of recyclable waste.

3.4 Waste Generation

A number of wastes generated during the construction and drilling activities will be transported off-site for disposal. These wastes will be recycled or re-used if possible or transported and disposed of at an appropriate licensed municipal landfill facility or at an alternative approved site.

Where practicable, the following waste types will be recycled or reused:

- Recyclable waste materials such as paper, plastic, wood and glass;
- Scrap metal and other material; and
- Used oil, including lubricating and gear oil; solvents; hydrocarbon based detergents, possible drilling fluids and machine oil.

A licensed waste contractor at licensed waste facilities will dispose of the following wastes:

- Drums and containers containing residues (e.g. lubricating oil) that may have environmental effects; and
- Hazardous wastes.

3.5 Approach

The Project will comply with national laws and standards, as well as with the best international practices for waste management. It is important to minimize the generation and transportation of waste to disposal facilities. The general approach to waste management is described below:

- **Reduction:** Whenever possible, waste generation will be minimized, not only to save money but also to reduce the need for storage and transportation resources, and to promote sustainable work environments. During the construction phase of the projects, the contractors and operators of the construction works will be required to supply specific waste reduction plans and procedures. Workers and operating companies will avoid the excessive use of materials in their work activities. During the operation phase of projects, operators, those responsible for maintenance, and users will work in a sustainable way and encourage members of the surrounding communities to do the same.
- **Reuse:** it is expected that during the construction and operation phases of the projects multiple types of waste will be generated. When possible, all waste material that is salvageable and practical will be reused.
- **Recycling:** Recycling not only reduces the volume of waste, it also protects wildlife, reduces water pollution, creates jobs, and encourages sustainable behavior. When possible, the following items will be recycled: plastics, cans, glass, paper, cardboard, wood and metal. All recycling items will be collected, sorted and stored at the point of origin and placed in different containers or containers clearly identified with markings and colors. After sorting, items will be transported to pre-approved recycling centers.
- **Classification:** all waste materials (hazardous and non-hazardous) will be classified at the point of origin in separate areas for each type of waste. Materials that can be reused or recycled will be separated in additional locations or containers to minimize transportation and disposal of waste. Examples of acceptable materials for recycling were listed above. Hazardous and non-hazardous waste will be monitored and managed separately. Wastes can be classified in the following classifications:

- General Waste: Waste must be considered as general waste when it does not have the characteristics to be classified as special handling waste or it does not have any specification included in the local regulation.
 - Special Handling Waste: The waste that is required to have special handle during its disposal process and is not classified as hazardous waste must be considered as special handling waste.
 - Hazardous Waste: The waste that have any danger specification or characteristics according to the local regulation, it must be consider as hazardous waste.
- **Disposal Transportation:** Waste materials that cannot be reused, recycled, or salvaged will be taken to a previously designated landfill and waste management facilities. Such facilities must meet and comply with all relevant regulations; as established by local laws. Contractors will document and record all transportation of waste, which will include information such as: type of waste, quantity, source of the waste, location of disposal site, and receiving facilities.

Household waste, such as garbage (bottles, cans, clothing, compost, disposable items, food packaging, food waste, newspapers, magazines, etc.) will be classified at the point of origin, placed in containers of different colors (supplied by contractors during construction and by DGDC during operation) and clearly identified, for example:

- Blue: plastic items;
- Green: cans and glassware;
- Red: residual waste;
- White: paper and cardboard; and
- Brown: food waste.

Industrial waste generated during the construction, operation and decommissioning phases of projects shall be classified at the point of origin in piles or in properly identified steel bins. Examples of the types of industrial solid and liquid wastes expected include:

- Drilling muds;
- Metal waste;
- Plastics;
- Concrete;
- Wood waste;
- Oil-contaminated rags;
- Cardboard;
- Used oils and fats;
- Batteries;
- Paint containers; and
- Residues of chemical compounds (paints, adhesive materials, etc.)

3.6 Mitigation Measures

3.6.1 Construction

3.6.1.1 General Measures for Waste

The EPC Contractor is required to develop a Waste Management Procedure that they and all Subcontractors will implement during all Project construction works. During construction, the EPC Contractor shall be responsible for the clean-up of the Site on a daily basis. The Site is to be kept clean and tidy at all times and clean-up shall be performed throughout the day with a final emphasis on site clean-up at the end of each shift. This clean-up emphasis is to contribute to the safe working conditions at the Site. Disposal of waste materials, both solid and fluid, shall be in accordance with local regulations, good hygiene and good construction practice, including the avoidance of oil or chemical spillage or run-off into local water ways. At a minimum, the waste management plans, specific to each activity, shall demonstrate compliance with the following:

- Particular attention should be given to the use and re-use of materials to minimize waste and, whenever practicable, using materials and products from sustainable sources. The Waste Management Procedure will be prepared in accordance with the waste hierarchy described above.
- Mechanisms for the collection, identification, temporary storage, and transportation of the waste before its transfer outside the Project areas. Waste will be stored in closed containers away from direct sunlight, wind and rain. Waste packaging will be in good condition, undamaged, corrosion and leak free. Waste will be stored so as to prevent or control accidental releases to air, soil, and water resources. In addition, waste will be stored in a manner that prevents the commingling or contact between incompatible wastes. Sufficient space is needed between incompatibles or physical separation such as walls or containment curbs.
- Waste signs will be put on all waste containers and collection areas. Each sign will be highly visible and easily seen by the person using the waste container or area. Each container or waste area sign will be labelled as Domestic Waste, Non-Hazardous Waste or Hazardous Waste and include the responsible person with contact information and how to handle the waste.
- Descriptions of responsible parties, procedures for registering and documentation of waste transfers, options for recycling, treatment and disposal of waste, including the proposed final destinations of those that cannot be reused, and measures for the reuse of waste;
- Solid waste produced during construction will be disposed of in compliance with the regulatory requirements and classification regulations and will be outlined in the Waste Management Procedure. Expected types and estimation of waste volumes should be provided in the Waste Management Procedures. And,
- Trainings for staff awareness.

The following information was obtained from Dominica Solid Waste Management Corporation (DSWMC) and shall be used as a guideline to develop the Waste Management Procedure (DGDC, 2020).

Table 3-2: Waste Management Procedures in Dominica

Waste Material	Disposal Route
Bio solids	Landfill (close to the seaport)
Construction Waste	Metal: to be recycled (exported) HDP plastic: can be recycled in Dominica

Waste Material	Disposal Route
	Other plastics and material : if possible, organize a place for local people to consider re-use (to be duly organized), or landfilled
Cooling water pipe debris	Same as above
Earthworks overburden	Stockpiled for future use, or revegetated as permanent landscaping.
General waste	Recycling and Disposal in landfill
Oils	Oil: to DCP Oily waste (such as oily rags): to the landfill
Vegetation	On site decomposition, burning, or be recycled as fire wood or building material where possible. This is acceptable according to Dominican law.

Note: Burning of chemicals, treated wood, and/or plastic is forbidden

As there is only one certified/recognized waste disposal facility in Dominica managed by the DSWMC, all solid waste to be disposed of off-Site shall be directed to them.

Project contractors will need ensure that the transportation, treatment and/or disposal of waste are done correctly, and will implement the following controls:

- All loads arriving or leaving the site will be appropriately secured.
- Provide information regarding waste management in site-specific inductions, including waste separation and importance of securing vehicle loads.
- Ensure licensed contractors are used to collect controlled wastes.
- Sewage and other effluents generated must be discharged to the septic tanks

3.6.1.2 Excavated Material

The EPC Contractor will make sure that excavated material is managed accordingly, as per the following provisions.

- Excavated topsoil will be transported to, and stockpiled in, designated topsoil storage areas.
- Prior to filling, sub-grade surfaces of depressions will be free of standing water and unsatisfactory soil materials will be removed.
- All unnecessary excavated materials will be transported and deposited outside of the site at an approved facility.
- Where excavated material is suitable to be used for fill and backfill, the material will be segregated and transported to a stockpile location at the construction site.

3.6.1.3 Hazardous Substances and Waste

The EPC Contractor will develop a Hazardous Substances Management Procedure that they and all Subcontractors will implement during all Project construction works. Under the Hazardous Substances Management Procedure, the EPC Contractor will induct their workforce to be made aware of hazardous substances, with reference to the applicable Safety Data Sheets (SDS). They will also attend mandatory safety training in the correct way to use and handle the hazardous substances. Training must be adjusted to be compliant with the laws of Dominica and any other relevant regulations prescribed by the competent authorities. For the handling of hazardous materials and waste:

- Workers will be provided with the appropriate Personal Protective Equipment (PPE) for the handling and use of hazardous substances.
- Emergency facilities, first aid points, clinics, eye wash fountains, emergency showers will be identified/provided where required.
- Other facilities that will be available include fire extinguishers, first aid, communication equipment, emergency doors and alarms.
- Smoking will be restricted to designated areas and all flammable liquids will be kept away from hot work areas.
- Oil, fuel and lubricants storage and dispensing stations will be restricted to established locations. Dispensing area should be located on an impervious surface and under shelter where possible.
- Oily and/or hazardous waste will be separately collected and disposed of by an appropriately licensed operator.
- Storage areas will be identified and unauthorized entry will be controlled by use of barriers warning signs and close supervision. All hazardous substances will be stored away from construction activities under covered stores. 'No Smoking' signs will be placed at these locations and all storage areas shall have minimum one dry powder type fire extinguisher.
- Hazardous and toxic wastes stored on site will be minimized by increasing the frequency of pick-ups where necessary. The producer of hazardous waste may store hazardous and toxic waste on-site for a maximum of 90 days. This period may be extended if the amount that is produced is less than 50 kg/day.
- Adequate ventilation will be provided where volatile wastes are stored.
- Secondary containment should be included wherever liquid wastes and hazardous substance are stored in volumes greater than 220 liters. The available volume of secondary containment should be at least 110% of the largest storage container, or 25% of the total storage capacity (whichever is greater), in that specific location.
- Triple rinsing must be undertaken before empty chemical containers can be treated as non-hazardous solid wastes.
- Hazardous waste will be directed to the DSWMC for proper disposal.
- Wherever possible, less hazardous substances will be obtained as substitutes.

DGDC will include contractual clauses that describe the requirements for transportation and disposal instructions so that they are handled appropriately and implement a “cradle-to-grave” approach where documentation for accountability is maintained from removal all the way to final disposal (noting quantities, types of materials, and names of people and companies handling the material).

3.6.1.4 Spill Management

The EPC Contractor will develop an Emergency Response Plan that they and all Subcontractors will implement during all Project construction works. Emergency procedures are provided in DGDC's Occupational Health and Safety Manual. General mitigation measures include:

- Vehicles will only be fueled in designated locations where the area is hard paved and the collection sump is connected to the wastewater treatment system.
- All vehicle maintenance should be done in garages with appropriate measures to capture oil.

- In the event of a spill during construction, spill containment and clean up equipment will be located onsite. This will include equipment for:
 - Containing and cleaning any spill such as a shovel, broom, drain covers, sandbags, booms and absorbent material. All spills will be handled with compatible materials.
 - Storing and disposing of spilled material such as safe containers, bags, and drums.
 - Protecting the safety of staff through PPE.

Any spills will be contained and cleaned up immediately and disposed of at an approved facility. Soil contaminated with hazardous substance should be excavated, disposed of as a hazardous waste and replaced with clean fill to minimize (or prevent) groundwater contamination with treatment of any stormwater runoff or process water prior to disposal.

Incidents will be recorded and reported following the accident reporting system. This includes the preparation of an Accident/Incident Report.

3.6.2 Operation

The O&M Contractor shall adopt the EPC Contractors Waste Management Procedure and the Hazardous Substances Management Procedure and shall update them to ensure they are relevant for the ongoing operations and maintenance of the Facilities.

3.7 Documentation and Monitoring

Monitoring and “cradle-to-grave” documentation of the generation, transportation, and disposal of waste materials is essential to projects. Measures and standards must be implemented to ensure compliance and to detect non-conformities with said standards. When a nonconformity is detected, a formal investigation will be conducted to determine its origin and establish the necessary corrective actions to comply with the standards.

3.7.1 Contractor Monitoring Responsibilities

In general, Contractors will carry out daily inspections, audits, monitoring and sampling activities (if necessary) in all areas associated with the generation and reception of waste. As part of the Waste Management Procedure a monitoring plan will be developed to inspect waste collection skips, to check wastes are being separated correctly and hazardous wastes are not being included with non-hazardous. Additionally, contractors will keep logs of waste volumes leaving the site with contractors and information on waste’s final destination. Checklists will be prepared for use during the inspections, which will be documented for reporting and monitoring purposes.

Inspection lists will include:

- Any spill, leak, absence of identification markings, containment problems and any other factor that may require corrective actions. The inspections should include a check of the waste skips and bins condition to be sure waste is being held securely and not able to impact the environment through leakage or being blown away. Regular inspections will check that wastes are being separated and deposited in the correct bins for recycling and disposal.
- Records and documentation of any corrective and follow-up action on issues identified.
- All bund enclosures will be regularly inspected for water and sheens prior to the collected water being discharged.

- Monitoring of treated effluent from the Workers' Accommodation package sewage treatment plant shall be performed on a monthly basis.
- Prior and during construction it is recommended that water quality and ecological (i.e. aquatic invertebrates) monitoring will be conducted at the small stream used for abstraction of water.
- Additionally, inspections of all buildings related to the facilities will be carried out in order to establish their current conditions and maintenance, cleanliness and order, the contractor's performance, the classification process, and the assessment of additional processing areas. Housekeeping procedures are provided in DGDC's Occupational Health and Safety Manual.

Any environmental incident involving wastes generated on site will be documented via an incident report. Corrective actions will include:

- Investigate cause of inappropriate waste disposal.
- Review cause of issue and develop response, such as variation to bin size, service schedule or waste separation awareness.
- Implement controls.

3.7.2 DGDC Monitoring Responsibilities

The DGDC shall review and approve the EPC Contractor's Waste Management Procedure and the Hazardous Substances Management Procedure.

The DGDC shall continuously audit the EPC Contractors adherence to their Procedures and shall upon finding any non-compliance, provide an immediate written notice to the EPC Contractor requiring them to correct the issue within a defined time period. The DGDC shall monitor that the EPC Contractor does in fact address all such matters; if the DGDC finds the EPC Contractor fails to address the matters within the time period, the DGDC shall advise the Engineer to the EPC Contract, whom shall consider the issuance of a "stop work" notice.

3.8 Training

Before the start of the construction works for each project, all project personnel must have received specific training for their tasks, as well as participated in various induction training sessions. Employees and contractors will be provided detailed information about the importance of proper waste management, including its classification.

3.9 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 3-3: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
Soil and Water Resources - Accidental release of hazardous materials into the environment during transportation and/or storage. Inappropriate disposal of hazardous materials.	Hazardous materials all appropriately disposed	100%	Construction and Operation	Monthly Inspections, Documentation verification.

Soil and Water Resources	Waste materials appropriately disposed at landfill	100%	Construction and Operation	Monthly Inspections, Documentation verification.
Soil and Water Resources	Recycling of all recyclable construction waste	100%	Construction and Operation	Monthly Inspections, Documentation verification.
Soil and Water Resources	Waste Records maintained on site	100%	Construction and Operation	Monthly Inspections, Documentation verification.
Soil and Water Resources	Employees must have the appropriate training	100%	Construction and Operation	Documentation verification. Construction: Induction training, Operation: Yearly
Soil and Water Resources	% Waste reduction (all types)	Any % reduction	Operation	Documentation, monthly calculations
Soil and Water Resources	Increase in % recycled waste	Any % increase	Operation	Documentation, monthly calculations
Soil and Water Resources	100% Compliance with waste storage areas inspections	100%	Construction and Operation	Monthly Inspections
Soil and Water Resources	100% Compliance with local applicable permits and authorizations	100%	Construction and Operation	Documentation verification

4. WATER MANAGEMENT PLAN

The Dominica Geothermal Development Company (DGDC) is committed to ensuring the compliance of the implementation of the Environmental and Social Management System (ESMS) policies and procedures.

To promote the Project's alignment to best international practices, DGDC acknowledges that water management measures are an essential part of any project. This Water Management Plan details the steps to follow for the identification and the appropriate management of potential impacts to the water resources in the Projects AOI, including the necessary requirement for the water supply and wastewater discharged during activities associated with the geothermal Project.

4.1 Objective

The objective of this plan is to comply with all relevant host-country environmental regulations, identify project risks on water resources and provide appropriate mitigation. In general, the objectives of this plan include:

- Protect surface and groundwater quantity and quality for local users and the environment
- Define management procedures for all water-related functions including roles and responsibilities and training requirements;
- Comply with applicable regulatory requirements and recommended international guidelines (i.e., WHO, IFC, NOAA);
- Align with international best practices; and
- Define and implement monitoring and reporting procedures

In addition, identify project activities that require water consumption and minimize and monitor water usage, document the water sources, which must be authorized by local entities; and monitor wastewater discharge for compliance with the host country's Maximum Permissible Limits (MPL).

Stormwater that accumulates in secondary containment areas will be discharged in a way that does not lead to negative impacts and in accordance with the Erosion and Sediment Control Plan. Geothermal fluids extracted from the reservoir will be in closed loop system that will be re-injected into the reservoir and will not be used for any other purpose or released to the environment. Brine ponds have been designed to be able to hold enough geothermal fluids during plant shut-down activities or emergency response. Any geothermal fluids collected in the brine ponds will also be re-injected into the reservoirs.

4.2 Scope of Application

This procedure will apply during the development of DGDC's activities and during the Project's life cycle (construction, operations and decommissioning). It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's Environmental and Social Management System (ESMS) policies and procedures, which are aligned to international best practices.

The Water Management Plan includes measures related to the management of water and wastewater related to Project activities. This plan shall be distributed to all contractors / subcontractors, and it shall be included in all contractual documentation and used as a basis for all specific Water Management Plans to be prepared by all engaged parties. Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific Environmental and Social Management Procedures (ESMP) will be applied on the ground. DGDC will review and approve this document before any implementation.

4.3 Roles and Responsibilities

In order to properly implement the Water Management Plan, DGDC shall:

- Ensure the EPC Contractor implements the required heat and fire detection and suppression systems.
- Review and approve the O&M Contractor’s Waste Management Procedure and the Hazardous Substances Management Procedure (the Procedures).
- Continuously audit the O&M Contractor adherence to their Procedures and shall upon finding any non-compliance, provide an immediate written notice to the O&M Contractor requiring them to correct the issue within a defined time period. The DGDC shall monitor that the O&M Contractor does in fact address all such matters; if the DGDC finds the O&M Contractor fails to address the matters within the time period, the DGDC shall use whatever mechanisms are available within the O&M Contractor’s contract to enforce compliance

Typical roles and responsibilities are as follows:

Table 4-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> ■ Be familiarized, review and approve the Water Management Plan.
Director of Accounts	<ul style="list-style-type: none"> ■ Ensure the availability of resources necessary for the implementation of the Water Management Plan
Plant Manager	<ul style="list-style-type: none"> ■ Accountable for ensuring the right resources are available to manage water use and wastewater within the plant and deliver on procedure objectives. ■ Responsible for approving corrective actions to address issues associated with water use and management with a focus on reducing consumptive use, and wastewater discharge. ■ Responsible for ensuring that water use and management and wastewater discharge are compliant with the applicable regulatory requirements and IFC standards. ■ Responsible for appointing a competent person (Engineer or equivalent) to monitor and manage water use within the plant. ■ Responsible for working with Engineers to agree follow up action to address water use and any water leakage issues identified by the Engineer. ■ Responsible for identifying water minimization opportunities such as equipment changes. ■ Responsible for identifying opportunities for reducing the pollution loading on wastewater discharges.
Environmental Coordinator or H&S Manager	<ul style="list-style-type: none"> ■ Responsible for regular water management and usage monitoring, including analyzing the data to identify trends in water use (e.g. is water use in summer significantly higher due to raised air temperatures) and reporting results to the Plant Manager. ■ Responsible for meeting maintenance schedules for the septic system and any associated equipment. ■ Responsible for recommending, submitting to, and coordinating with the Plant Manager any identified changes/upgrades in response to any issues identified by the water usage survey program. ■ Responsible for identifying and responding to increased water use and water leakage, working with the Plant Manager. ■ Responsible for reviewing changes to the equipment that might require change management procedures and investigation.

	<ul style="list-style-type: none"> ■ Responsible for engaging suitably competent persons and contractors to undertake work to rectifying any leaks or other water and wastewater associated faults or maintenance.
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Water Management Procedure aligned with this Water Management Plan.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in this Water Management Plan.

4.4 Activities

Most of the water use is expected during construction activities. The construction of the Project would require water during well drilling and filling the firewater tank, and for the portable worker restrooms and workers camps. During operation, utility water will be required for the administration and control building.

Most of the wastewater generated on-site will be sanitary sewage resulting from the portable restroom facilities during construction and from the restrooms and kitchens in the administration and control building, and the security building during operation. Wastewater from equipment cleaning and process areas will pass through an oil interceptor prior to being discharged to the stormwater system.

4.4.1 Water

4.4.1.1 Construction

Facility and Site Construction

During construction activities, potable water for contractor will be sourced from a nearby stream as shown in the Figure below. DGDC will submit an authorization application to the “Minister for Housing Lands Settlement and Water Resource Management” for water abstraction. The EPC Contractor shall be responsible for the design, execution and completion of the raw water intake structure and piping required to transfer to the Site.




Figure 4-1: Proposed Water Source Location

Water take limits are as provided in the table below.

Table 4-2: Proposed Water Take Limits

Duration	Quantity	Unit
Daily	10,000	Liters
Monthly	200,000	Liters
Maximum Instant	5	Liters/second

Source: Jacobs, 2018.

No maintenance activities shall be performed on site. Vehicle and equipment washing on-site will be prohibited. In addition, the contractor must:

- Properly store and use of fuel and hazard materials so that they do not come into contact with water;
- Control soil erosion in construction areas (by use of hay bales and silt fences);
- Monitor and periodically remove accumulated silt from any sediment control ponds for proper disposal (landfill);

- Construct diversion drains and bunds to divert clean runoff away from construction areas and prevent contaminated water entering local water sources.

Well Drilling

Drilling Muds

Drilling will be conducted using water based drilling muds rather than oil based. Drill cuttings will flow into a temporary mud pit where drill cuttings are settled prior to the mud being recirculated back into the borehole. During short-term well testing, the mud is evacuated from the borehole into the temporary mud pits. Settled solids will be disposed of at the landfill while liquids will be re-injected into the reservoir. Once the storage ponds area available, fluid produced during testing activities would be directed into the storage ponds on-site prior to re-injection. During long term testing, when an injection well is then available, the produced fluid would be immediately re-injected via the injection wells. In order to prevent contamination of the drilling fluids, the contractor will:

- Recycle drilling muds where possible;
- Design adequate capacity ponds to manage waste water;
- Line ponds with HDPE/impermeable lining, and regularly check for rips and tears. Ponds will be regularly cleared of silt;
- Lining, casing and grouting the drilling wells;
- Reinjection of water (geothermal fluids) to avoid discharge of well brines to surface water
- Route effluent fluids to settling ponds; and
- Create bunded areas in low lying land around injection pads and provide diversion channels around these bunded areas.

Measurement of Water Intake

During drilling activities, the contractor will measure the amount of water supplied and discharged and will not go over the water take limits provided above. This information must be registered with the additional information described below:

- Description of the activity where water is consumed;
- The maximum permissible amount or the local equivalent of water discharged established by the internationally accepted regulatory organisms;
- Monthly amount of water consumed and discharged

In addition, the contractor must manage the potential circumstances where water is consumed or discharged (i.e. consumption reduction plans or strategies), and mitigate the potential water discharges by applying measures to control and reduce them.

Groundwater

Other than the geothermal fluid to be used for the plant, there will be no other use of groundwater at the facility. Wells will be designed to employ deep set surface casing to prevent blowouts (the uncontrolled discharge of deep aquifer water/steam into the upper aquifer or surface).

4.4.1.2 Operation

The water source to be used during operation remains unknown. Water to be used at the site during operation will be supplied by Dominica's Water and Sewerage Company Ltd. (DOWASCO). The options currently being considered are:

- Option 1. Extend the existing 2" line to the geothermal plant site. This is about 1,200 m, and would deliver potable water at a rate of approximately 8 m³/hr
- Option 2. Pump water from Titou Gorge to the plant site. The water would be extracted below the DOMLEC intake point, to minimize interference with DOMLEC's systems. The flow in the Gorge can support the target flow rate (10 m³/hr).
- Option 3: Truck water to the site

Selection of the final option is dependent on water capacity which is currently being assessed by DOWASCO.

Measurement of Water Intake

Depending on the water source option selected, unless water is trucked to the site, a water meter will be installed at the intake from the main prior to the water entering the facility. This water meter will measure and record the inlet water flow rate and calculate the total cumulative water flow/volumes. The measurement will be continuous and data will be recorded on a continuous basis.

Water Use Monitoring

The water usage for the plant as a whole will be calculated at least monthly based on the volumes of water abstracted from the local water main.

Consumption values will be compared to design calculations as well as previously recorded consumption values for those same operating conditions and the source(s) of any net loss/gain identified. Changes in consumption are accounted for to allow opportunities to identify leaks as well as to reduce consumptive use.

Recording of Leaks/Opportunities to Reduce Consumptive Use

By the implementation of a regular water monitoring program as well as facility inspections by the Engineers as part of relevant operational and maintenance procedures, significant leaks are identified and recorded, including their location, duration and approximate volumes of water lost. Corrective actions/nature of repairs undertaken are also recorded by the Engineers. Opportunities for reduction in consumptive water use are identified by the Environmental Department where possible and as part of annual environmental improvement initiatives.

4.4.2 Wastewater

4.4.2.1 Construction

Sanitary Sewage

Domestic wastewater from amenities at the power plant site including the worker's camp will need be collected and treated in a package plant to meet discharge requirements. The EPC Contractor will need to maintain the package plant and associated effluent disposal system to meet international guidelines discharge criteria (see section on Discharge Criteria below) and to prevent odor or other nuisance to the community during the period of construction. The EPC Contractor will typically be responsible for

decommissioning and removing the unit at the end of the construction period. All wastewater should be collected prior to discharge.

Portable toilets will be installed and used by workers to prevent contamination of waterways during construction of the reinjection pipeline.

Drilling

Drilling and injection works have the potential to affect water resources quality if geothermal liquid, wash water, mud and drill cuttings (collectively referred to as process wastewater) are not managed properly. Process wastewater resulting from the drilling will be re-injected into the reservoir once solids have been settled out in the sump pumps. Drilling muds will be disposed of at the local landfill. No onsite disposal of any waste material is allowed. No hazardous waste material is allowed to be disposed of at the local landfill. Any characteristic or listed hazardous waste produced by the drilling contractor will be containerized and disposed accordingly.

Discharge Criteria

Although the Project will not discharge directly to a neighboring water body, ESIA specifies that the water bodies near the site, such as the Roseau and Blanc rivers are of “good” quality (Jacobs, 2018). In order to prevent any potential impacts to area water bodies, sanitary sewage from restroom facilities and kitchens will be treated via a package plant for disposal. The package plant discharge would be to a sand filter or similar medium that allows the treated effluent to infiltrate to ground below the soil surface and receive further treatment. This infiltration system will be located close to the edge of the power plant area to maximize distances to watercourses. Although a specific permit is not required, plant design details will need to be included in the development application to be approved by the Ministry of Housing & Urban Development prior to construction.

Stormwater and any water collected from the settling ponds will be discharged via surface flow for infiltration to the ground from the stormwater collection system post treatment by settling ponds and/or oil interceptors (if required). Effluents from oil interceptors, settling ponds and package plant should meet the following criteria, as specified in Table 1.3.1 of the General IFC EHS Guidelines. Minimum parameters to be measured for each type of discharge are specified in the table below.

Table 4-3: IFC EHS Guidelines Water Discharge Criteria

Pollutant	Unit	Limit	Oil interceptor	Settling pond	Package plant
pH	pH	6 - 9			X
Biological Oxygen Demand - BOD	mg/l	30			X
Chemical Oxygen Demand - COD	mg/l	125			X
Total Nitrogen	mg/l	10			X
Total Phosphorus	mg/l	2			X
Oil and grease	mg/l	10	X		
Total Suspended Solids	mg/l	50		X	X

Total Coliform Bacteria	MPN*/ 100 ml	400			X
-------------------------	--------------------	-----	--	--	---

* MPN : Most Probable Number.

Temperature of wastewater prior to discharge should not result in an increase greater than 3°C of ambient temperature of the receiving surface water.

The effectiveness of the settling pond on sediment should be undertaken during construction and ongoing operations, with spot samples assessed for Total Suspended Solids (TSS) at the inlet and outlet locations. Imhoff settling cones offer a cheap and viable method for quick onsite estimates of TSS from the inlet and outlet.

Prohibitions

Any illicit discharges of industrial wastewater or chemicals/hazardous materials into the portable sanitary facilities is strictly prohibited. Equipment and vehicle washing is not allowed to be performed on-site.

4.4.2.2 Operation

Septic System

A septic systems would be installed onsite for treatment of sanitary sewage. This septic system will be:

- Properly designed and installed in accordance with local regulations and guidance to prevent any hazard to public health or contamination of land, surface or groundwater.
- Well maintained to allow effective operation.
- Installed in an area with sufficient soil percolation for the design wastewater loading rate.
- Installed in an area of stable soils that are nearly level, well drained, and permeable, with enough separation between the drain field and the groundwater table or other receiving waters.

Prohibitions

Any illicit discharges of industrial wastewater or chemicals/hazardous materials into the sanitary sewer system is strictly prohibited.

Maintenance

The facility's septic system will have to be operated, cleaned and maintained by a licensed contractor based on the schedule recommended by the manufacturer. There are no wastewater treatment facilities available on the Island, therefore pumped solids will be disposed of at the designated area of the landfill.

4.4.3 Stormwater

4.4.3.1 Construction

Stormwater will be diverted from the construction areas in accordance with the Erosion and Sediment Control Plan in order to avoid stormwater coming in contact with exposed soils or construction equipment. Stormwater collected in secondary containment areas will be checked for oil sheens and any signs of contamination before being discharged to the surrounding surface to allow for infiltration into the ground. The laying of overland flow diversion drains and preload fill should be completed preferable during the dry season and prior to the power plant construction earthworks commencing.

Drainage water collection and treatment systems should be installed as a priority to prevent discharge to the adjacent rivers and streams. If there are signs of contamination, the stormwater will be pumped out of the secondary containment areas and collected, transported, treated or sent to disposal in compliance with the federal, state or municipal regulations.

4.4.3.2 Operation

Stormwater collected in secondary containment areas will be checked for oil sheens and any signs of contamination before being discharged to the surrounding surface to allow for infiltration into the ground.

If there are signs of contamination, the stormwater will be pumped out of the secondary containment areas and collected, transported, treated or sent to disposal in compliance with the federal, state or municipal regulations.

4.5 Documentation and Monitoring

Implementation of this procedure is reviewed through internal and external (when applicable and available) audit results and other inspection processes.

4.5.1 Construction

During drilling activities, there will be daily site inspections and audit reports which shall be kept on-file. There will be no discharges of untreated water. Prepare Daily Geological Reports (DGR) which include a description of the cuttings and water use. In the event there is a discharge of untreated water or drilling muds, an incident report will be filled.

The EPC Contractor monitoring activities during construction will include:

- Regularly inspecting all bund enclosures for water and sheens prior to the collected water being discharged.
- Monitoring of treated effluent from the Workers' Accommodation package sewage treatment plant on a monthly basis.
- Monitoring at the small stream used for abstraction of water prior to and during construction for water quality and ecological indicators (i.e. aquatic invertebrates).
- As indicated above, measurements of water intakes will be performed and documents will be maintained on-site. Waste logs will also be maintained on-site.

4.5.2 Operation

Monthly reports on water usage would be maintained on-site to monitor water usage. Maintenance and inspection logs will be maintained on-site. There are no regulatory requirements to submit summary reports on water usage or wastewater to the Government.

Any permits relating to water supply will be maintained on site indefinitely.

Any wastewater resulting from industrial activities onsite will have to be disposed of off-site. Maintenance logs for the septic system will have to be maintained on site indefinitely.

4.6 Training

All activities will consider the reduction and adequate management of water consumption. All personnel will be trained to on

- General awareness and procedures concerning water management and conservation

- Emergency procedures in case of water leaks
- The appropriate disposal methods of hazardous materials or industrial wastewater to ensure they are not disposed of in the facility's sanitary sewer system.

4.7 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 4-4: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool
Water Resources	% Water consumption	Any % reduction	Construction and Operation	Record quantity of water consumed and timing of consumption
Water Resources	% Water savings	Any % savings	Construction and Operation	Record quantity of water consumed and timing of consumption
Soil and Water Resources	Daily Drilling Report (DDR) and Daily Geology Reports (DGR)	100% reports kept	Construction	Daily Report Logs
Water Resources	Monthly surface water quality monitoring upstream and downstream of the Project's water source Site – no deterioration in pre-project water quality	No impacts to water quality	Construction	Monthly water quality monitoring
Soil and Water Resources	Wastewater monitoring reports must be under the MPLs	100%	Construction and Operation	Monthly wastewater quality monitoring
Soil and Water Resources	Employees must have the appropriate training	100%	Construction and Operation	

5. AIR EMISSIONS MANAGEMENT PLAN

5.1 Introduction

This procedure details the steps to follow to implement the appropriate measures to prevent, minimize or mitigate the negative impacts on human health and the environment caused by the air emissions pollutants generate from Project activities, as well as to reduce the Greenhouse Gas Emissions.

5.1.1 Objective

The general objective of this Plan is to define framework and actions to implement mitigation measures to control and minimize potential sources of air emissions. This Plan also aims to:

- Comply with applicable local and international air quality standards as listed in the IFC EHS General Guidelines (whichever is more stringent);
- Identify the potential sources of air impacts during Project construction and operation;
- Define construction and operation procedures for emissions management in order to eliminate, minimize and/or mitigate any air emissions ensuring they are controlled to acceptable levels;
- Align with international best practices;
- Define the procedures and mitigation measures to be applied to construction and operation activities that have the potential to produce air emissions;
- Define training and communication commitments; and
- Define the monitoring, reporting, and adaptive management procedures for the Plan.

5.1.2 Scope of Application

The procedures identified in this Plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

This Plan includes measures related to the management of air emissions resulting from Project activities. This plan shall be distributed to all contractors / subcontractors, and it shall be included in all contractual documentation and used as a basis for all specific Air Emissions Management Plans to be prepared by all engaged parties. Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

5.2 Roles and Responsibilities

In order to properly implement the Air Emissions Management Plan, DGDC requires the involvement of the people listed below.

Table 5-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	■ Be familiarized, review and approve the Noise Management Plan.

Director of Accounts	<ul style="list-style-type: none"> ■ Ensure the availability of resources necessary for the implementation of the Air Emissions Management Plan
Head of ESG	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Air Emissions Management Plan
ESG Manager	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Air Emissions Management Plan ■ Update the Air Emissions Management Plan ■ Respond to detections of contaminants of concern ■ Review and approve the contractor project-specific Air Emissions Management Plan
Environmental Coordinator or H&S Manager	<ul style="list-style-type: none"> ■ Oversight and approval of the contractors emissions management plan ■ Ensure the generation of evidence and reports to ensure compliance with the recommended exposure limits as well as maintaining DGDC's KPIs. ■ Ensure the internal coordination to follow the Air Emissions Management Plan
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Air Emissions Management Plan ■ Develop and implement additional mitigation measures in the event of exceedances to the recommended limits or if a proposed mitigation measure does not result in sufficient air emissions control ■ Ensure that workers have access to personal protective equipment (PPE) and are trained in appropriate use and jobs with potential for exposure to elevated air emissions levels
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Air Emissions Management Plan

Typical roles and responsibilities are as follows:

- As project phases unfold, Contractors will be responsible for overseeing the implementation of the Air Emissions Management Plan. Contractors must develop and deliver a list of all air emissions management procedures, specific to each function. In the event of the detection of an exceedance or if a control measure does not result in sufficient air emissions control, Contractors will work with DGDC to identify and implement additional control measures to address the issue.
- Prior to the start of construction activities, each Contractor must prepare its own management plans and inspection procedures. Said management plans will be reviewed and approved by the DGDC before the works begin, in order to ensure consistency between this management plan.
- Workplace supervisors will ensure that air emissions management measures and BMPs are implemented prior to commencing Project activities and oversee health and safety factors for Contractors in relation to air emissions management and enforce established environmental incident prevention and safety practices.

5.3 Sources of Impacts

Project activities could result in the following negative impacts to social and environmental receptors located within the project's area of influence:

- Increase in the generation of gas and particle emissions from equipment, machinery and vehicles (mobile sources) that use hydrocarbons as a fuel source;
- Increase in the emission of vapors and gases from drilling and well testing activities on site;
- Dust emission from areas devoid of vegetation and gaseous emissions from construction equipment and machinery and vehicles that transport materials and/or waste; and

- Generation of vehicular emissions and suspension of particles during the operation phase, due to the circulation of mobile equipment involved in maintenance work.

5.4 National/International Standards

There are no national ambient air quality standards in Dominica; therefore, international limits for ambient air quality levels will be applied. Standards applicable to the Project include:

- The IFC's General Environmental, Health, and Safety (EHS) Guidelines for Air Emissions and Ambient Air Quality,
- The National Institute for Occupational Safety and Health (NIOSH) Recommended Exposure Limits (REL);
- Occupational Safety and Health Administrations (OSHA) Permissible Exposure Limits (PEL); and
- Best practices.

The following table presents the guidelines for ambient air quality.

Table 5-2: Guidelines for Ambient Air Quality for Typical Air Pollutants

Compound	Averaging Period	Guideline Value in $\mu\text{g}/\text{m}^3$
Sulfur dioxide (SO ₂)	24-hour	125 (Interim target-1) 50 (Interim target-2) 20 (guideline)
	10 minute	500 (guideline)
Nitrogen dioxide (NO ₂)	1-year	40 (guideline)
	1-hour	200 (guideline)
Particulate Matter (PM ₁₀)	1-year	70 (Interim target-1) 50 (Interim target-2) 30 (Interim target-3) 20 (guideline)
	24-hour	150 (Interim target-1) 100 (Interim target-2) 75 (Interim target-3) 50 (guideline)
Particulate Matter (PM _{2.5})	1-year	35 (Interim target-1) 25 (Interim target-2) 15 (Interim target-3) 10 (guideline)
	24-hour	75 (Interim target-1) 50 (Interim target-2) 37.5 (Interim target-3) 25 (guideline)
Ozone	8-hour daily maximum	160 (Interim target-1) 100 (guideline)

Hydrogen sulfide, mercury, and carbon dioxide are the main potential air pollutants associated with geothermal power generation. Potential emissions of these contaminants may occur during well drilling and

flow testing activities, and via the open contact condenser / cooling tower systems unless pumped out of the condenser. Vent mufflers can also be potential sources of hydrogen sulfide emissions, primarily during upset operating conditions when venting is required. Under normal operating conditions, binary technologies (with non-contact condensing technology) have close to zero emissions of hydrogen sulfide or mercury to the atmosphere because of reinjection of all geothermal fluids and gases.

In addition to the possible exposure to the above mentioned contaminants, the geothermal plant will also use and store a working fluid (n-pentane or isopentane) in the equipment. Although this is a closed system, a failure to this system could lead to pentane being released to the immediate surroundings.

The following table provides the NIOSH and OSHA recommended exposure limits to the possible air contaminants that could be released at the Site:

Table 5-3: Exposure Limits to Potential Air Contaminants

Compound	OSHA PEL	NIOSH REL
Hydrogen Sulfide (H ₂ S)	10 ppm (8-hour Time Weighted Average (TWA)), 50 ppm [10-minute maximum peak]	10 ppm (15 mg/m ³) [10-minute]
n-pentane	120 ppm (10-hour TWA) 610 ppm (15-minute short-term limit)	120 ppm (350 mg/m ³) [15-minute]

5.5 Approach

The Project will comply with the standards identified in Section 5.4, as well as implementation of management practices and mitigation measures identified in the ESIA. It is expected that the majority of the air emissions will be temporary in nature and will be related to construction activities. Typical construction type emissions have to do with fugitive emissions which include dust (particulate matter (PM)) and odors, and other contaminants mainly associated with combustion processes (nitrous oxides (NO_x), sulfur dioxide (SO₂) and carbon monoxide (CO)). As previously mentioned, hydrogen sulfide and carbon dioxide emissions are possible during well drilling and testing during the construction phase and upset conditions during operations.

The general approach to air emissions management is described below:

- **Minimization:** Whenever possible, air emissions will be minimized at the source.
- **Monitoring:** Monitors will be installed during both the construction and operation phases of the project in order to implement mitigation measures as necessary when contaminants of concern are detected. In case of detection, implement mitigation and response measures.
- **Mitigation:** DGDC will establish procedures for addressing the different emission streams. Procedures include dust control measures, vehicle and equipment specifications and chemical additives to reduce contaminants of concern.

5.6 Management/Mitigation Measures

5.6.1 Dust Control

The most common air pollutant expected during construction activities is the fugitive source emissions of dust, measured as particulate matter (PM). Dust is likely to be released during certain activities (i.e.

transport or outdoor storage of solid materials, uncovered land surfaces, or transit on unpaved roads). The EPC Contractor will implement the following dust suppression methods to minimize emissions:

- Watering unpaved roads/temporarily exposed bare soils - Construction dust will be suppressed with water applied by water sprinklers and/or water carts. For access tracks, it is recommended that water is sprayed on roads at least twice a day during the dry periods;
- Material from stockpiles of soil, aggregate, sand etc. prone to being windblown, will be held in bins or other enclosures, and stockpiles of material including soil, and where practicable covered with a tarpaulin;
- Dust on the wheels of vehicles will be removed through wheel washing prior to leaving the site;
- Vehicle speed on the construction site will be set to a maximum of 15 mph to reduce dust release from road surfaces;
- In the event of high winds during dry periods, it may be necessary to cease some construction activities until the wind subsides;
- Reseeding bare soils as soon as possible to establish grass coverage and limit soil dispersion - To reduce windblown material, the EPC Contractor will sow grass seed on soil stockpiles that will remain dormant for more than three months;
- Ensuring all trucks moving materials are covered - When transporting material that is prone to wind blow, vehicles will be equipped with a tarpaulin cover when passing through residential areas;
- Minimize earth movement activities.

5.6.2 Combustion Gases and Mobile Sources

Combustion emissions from equipment, machinery and vehicles used for Project activities include CO, NO_x, SO₂, PM and VOCs. In order to minimize these emissions, The Project will ensure that all contractors during construction and DGDC during operation adhere to the following:

- Regardless of the size or type of vehicle in question, fleet owners/operators must apply the mechanical maintenance programs recommended by the manufacturers;
- Drivers will receive training on the advantages of vehicle driving practices that reduce both the risk of accidents and fuel consumption, as well as the importance of avoiding sharp accelerations and respecting speed limits; and
- To the extent possible, the following methods will be considered for reducing potential impacts:
 - Replacement of old vehicles with modern alternatives, with greater energy control;
 - Adaptation of the most used vehicles to cleaner energies, whenever feasible;
 - Installation and maintenance of emission control devices, such as catalytic converters; and
 - Implementation of a periodic vehicle maintenance and repair plan.

5.6.3 Odors and Process Emissions

During construction activities, monitors for hydrogen sulfide and carbon dioxide will be available on the drilling equipment. In addition, monitors will be placed strategically around the site (see Monitoring Section below) to detect any contaminants of concern. Equipment utilized is designed to reduce the possibility of emissions at the source; however, during well flow tests, emissions will not be controlled. Any detections that may cause community complaints, shall be reported to the Environmental Coordinator for action.

During operation, monitors with audible alarms will be in place to detect emissions of contaminants of concern; however, emissions are not expected from the closed binary system.

5.6.4 Greenhouse Gas Emissions

Emission of greenhouse gases (GHG) such as CO₂, methane (CH₄), NO_x, and chlorofluorocarbons (CFCs) will be temporary and will come mainly from vehicle and machinery used during construction. In order to reduce GHGs, the measures described above will be applied.

5.7 Air Emissions Monitoring and Response

Air emissions monitoring will occur during two phases of the Project, during construction operation as described below.

5.7.1 Construction

5.7.1.1 Dust and Particles

To determine the effectiveness of dust mitigation measures used during construction, the EPC Contractor will ensure that ambient air monitoring is undertaken on the site boundary.

- Visual dust inspection of the site on a daily basis during the dry season to gauge the effectiveness of dust mitigation measures will occur at least 400 m from construction works.
- Monitoring should be undertaken by a qualified laboratory using appropriate sampling equipment; it should verify that control systems such as dust suppression sprays are operating correctly.
- Visual inspections of cleaning truck tires and road watering activities will also be performed and recorded.
- The results will be reported on a monthly basis and included in publicly available reports.

Site personnel will be trained in identifying potential activities that could lead to dust and particle emissions in order to implement the appropriate preventive measures. As part of good working practice the EPC Contractor will complete routine checks on dust generation from construction activities, and confirm that dust suppression and appropriate storage is being used where required. In addition, a mechanism for complaints regarding dust will be available to locals, and due regard given to any issues raised.

If personnel observe dust and particle emissions during construction activities, they will assess the situation and implement the appropriate mitigation measures as described above.

5.7.1.2 Odors and Process Emissions

Signs of hydrogen sulfide gas include:

- Reduction of mud pH
- Discoloration of mud (to a dark color)
- Rotten egg odor
- Formation of black scale on steel drill pipe

Continuous monitoring and recording of hydrogen sulfide and carbon dioxide will be performed at the locations to be specified by the Contractor. Safety monitoring systems with warning alarms for high emissions of potentially hazardous gases, including H₂S, incorporated at the well sites (e.g. the power plant and reinjection sites), as well as providing direct safety measures in the event of a blowout, will highlight

potential H₂S emissions issues which could arise during well commissioning and operation. All personnel and local residents will be made aware of the procedure should an alarm be activated. Specific monitoring procedures for H₂S are provided in the Operational Health and Safety Manual prepared by DGDC.

If hydrogen sulfide gas is detected at levels that will produce unacceptable odors at downwind residences, DGDC will inject abatement chemicals into the drilling rod to reduce hydrogen sulfide emissions to acceptable levels.

DGDC will develop an evacuation plan, and a wind sock will be mounted on site so that plant personnel can move up-wind from a leak.

5.7.2 Operation

5.7.2.1 Dust and Particles

Dust and particle emissions are not expected as a result of operation activities. However, if site activities take place that could disturb soils, the mitigation measures described above will be implemented. Any vehicle carrying materials on site that could potentially lead to dust and particle emissions will be covered as discussed above. Site personnel will be trained in identifying potential activities that could lead to dust and particle emissions in order to implement the appropriate preventive measures.

5.7.2.2 Odors and Process Emissions

The O&M Contractor will ensure the following monitoring is undertaken during operation:

- Ambient monitoring for H₂S can be easily undertaken at sensitive locations (e.g. nearby residential areas) using low-level ambient H₂S monitors such as Odalog, which can be deployed at multiple locations for up to two months at a time.
- Safety monitoring systems with warning alarms for high emissions of potentially hazardous gases, including H₂S, incorporated at the well sites (e.g. the power plant and reinjection sites), as well as providing direct safety measures in the event of a blowout, will highlight potential H₂S emissions issues which could arise during well commissioning and operation. All personnel and local residents will be made aware of the procedure should an alarm be activated. Specific monitoring procedures for H₂S are provided in the Operational Health and Safety Manual prepared by DGDC.
- For the Organic Rankine Cycle option, there will be infrared heat detectors and pentane vapor monitors installed at the power plant site around the working fluid condenser/equipment and cooling tower, for early detection of any leaks of pentane or heat sources.
- All heat and pentane sensors if an ORC plant is selected will be checked and calibrated on an annual basis or as per the manufacturer's specifications.

DGDC will develop an evacuation plan, and a wind sock will be mounted on site so that plant personnel can move up-wind from a leak.

5.8 Training

Before the start of the construction, all project personnel identified within Section 2 – Roles and Responsibilities must have received a copy of the Plan and understand their respective responsibilities.

All Project activities will consider the reduction and appropriate management of air emissions. To accomplish this, all Project personnel will be trained in the general awareness and procedures concerning emissions management. Personnel involved with the air emissions generation will receive additional

training including refresher and updates to the training. Training will be provided in the implementation of this procedure.

5.9 Documentation and Record Keeping

Evidence of air emissions management will be maintained through monitoring logs.

DGDC will monitor the performance of the EPC Contractor with regards to Air Quality and shall upon finding any non-compliance, provide an immediate written notice to the EPC Contractor requiring them to correct the issue within a defined time period. The DGDC shall monitor that the EPC Contractor does in fact address all such matters; if the DGDC finds the EPC Contractor fails to address the matters within the time period, the DGDC shall advise the Engineer to the EPC Contract, whom shall consider the issuance of a “stop work” notice.

DGDC will monitor the performance of the O&M Contractor through periodic audits.

5.10 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this Plan:

Table 5-4: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
Health and Safety	Air emissions monitoring reports must be below recommended levels	100%	Construction and Operation	Monitoring logs / Weekly
Health and Safety	100% of the employees assigned to handled air emissions must have the appropriate training	100%	Construction and Operation	Training documents / Quarterly

6. NOISE MANAGEMENT PLAN

6.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensure the compliance of the implementation of the Environmental and Social Management Plan (ESMP) policies and procedures.

This Noise Management Plan (Plan) is designed to control and minimize potential sources of noise during construction and operation of the Project. This Plan describes potential sources of noise during Project construction and operation, noise standards applicable to the Project, and proposed measures and best management procedures (BMP) to be implemented to protect environmental and social receptors from potential adverse impacts associated with the increase of airborne noise.

6.1.1 Objective

The objective of this Plan is to define framework and actions to implement the mitigation to control and minimize potential sources of noise. The following objectives are also part of this Management Plan:

- Comply with applicable local and international noise requirements;
- Identify the potential sources of noise impacts during Project construction and operation;
- Define construction and operation procedures for noise management;
- Align with international best practices;
- Define the procedures and mitigation measures to be applied to construction and operation activities that have the potential to produce noise;
- Define training and communication commitments; and
- Define the monitoring, reporting, and adaptive management procedures for the Plan.

6.1.2 Scope of Application

The procedures identified in this Plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

The Noise Management Plan includes measures related to the management of airborne noise resulting from Project activities. This plan shall be distributed to all contractors / subcontractors, and it shall be included in all contractual documentation and used as a basis for all specific Noise Management Plans to be prepared by all engaged parties. Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

6.2 Roles and Responsibilities

In order to properly implement the Noise Management Plan, DGDC requires the involvement of the people listed below.

Table 6-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> Be familiarized, review and approve the Noise Management Plan.
Director of Accounts	<ul style="list-style-type: none"> Ensure the availability of resources necessary for the implementation of the Noise Management Plan
Head of ESG	<ul style="list-style-type: none"> Assure the correct implementation of the Noise Management Plan
ESG Manager	<ul style="list-style-type: none"> Assure the correct implementation of the Noise Management Plan Update the Noise Management Plan Respond to noise complaints Review and approve the contractor project-specific noise management plan.
Environmental Coordinator or H&S Manager	<ul style="list-style-type: none"> Ensure the generation of evidence and reports for national compliance and compliance with the IFC PS as well as maintaining DGDC's KPIs. In addition, ensure the internal coordination to follow the Noise Management Plan
Contractor Company	<ul style="list-style-type: none"> Develop a project-specific noise management plan Develop and implement additional noise mitigation measures in the event of noise complaints or if a proposed mitigation measure does not result in sufficient noise control Ensure that workers have access to personal protective equipment (PPE) and are trained in appropriate use and jobs with potential for exposure to elevated noise levels
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> Understand and carry out the activities set out in the Noise Management Plan Use PPE as needed to protect against exposure to elevated noise levels during Project construction and operation

Typical roles and responsibilities are as follows:

- As project phases unfold, Contractors will be responsible for overseeing the implementation of the Noise Management Plan. Contractors must develop and deliver a list of all noise management procedures, specific to each function. In the event of a noise complaint or in the event that a noise control measure does not result in sufficient noise control, Contractors will work with DGDC to identify and implement additional noise control measures to address the noise complaint or ensure sufficient noise control.
- Prior to the start of work involving the generation of airborne noise, each Contractor must prepare its own management plans and inspection procedures. Said management plans will be reviewed and approved by the DGDC before the works begin, in order to ensure consistency between the noise management plans.
- Workplace supervisors will ensure that noise management measures and BMPs are implemented prior to commencing Project activities, oversee health and safety factors for Contractors in relation to noise management, and enforce established environmental incident prevention and safety practices.

6.3 Sources of Impacts

Noise will be generated during Project construction and operation. Construction will involve the use of heavy equipment to clear and grade project parcels, construct the well pads and plant foundations, drill the production well and injection well, perform well testing, install the aboveground production and injection pipelines, assemble and install power plant equipment and related facilities (e.g., control room), and trench and install the underground transmission intertie line. In general, Project construction will proceed in phases

in which one activity is finished before the next activity begins (e.g., clearing and grading will be completed before well pads are constructed); however, some phases could overlap slightly. The majority of the construction activities will occur during daylight hours; however, well drilling and testing will occur 24 hours a day.

During operation, the primary sources of airborne noise will include the power plant equipment, pipelines, and venting during startup and shutdowns. The air-cooled condensers, which will use large fans to force air over thin fans containing the binary system working fluid, will produce the highest equipment levels.

6.4 National and International Standards

There are no national noise standards in Dominica; therefore, international limits for ambient/airborne noise levels will be applied. Legal and numeric standards applicable to the Project include:

- Environmental, Health, and Safety (EHS) Guidelines: Construction and Decommissioning, International Finance Corporation (IFC);
- EHS Guidelines: Noise, IFC
- EHS Guidelines: Geothermal Power Generation, IFC;
- Best practices for occupational noise.

The following table presents the IFC guidelines for ambient noise.

Table 6-2: IFC Guidelines for Ambient Noise

Receptor	Maximum Ambient Noise Level, L_{eq} , 1 hour (dBA)	
	Daytime (07:00-22:00)	Nighttime (22:00-07:00)
Residential, Institutional, Educational	55	45
Industrial, Commercial	70	70

Source: IFC 2007.

L_{eq} , 1 hour = statistical noise descriptor that represents the equivalent continuous sound pressure level over a 1-hour period;

dBA = A-weighted decibel.

In addition to the guidelines for sound contribution from a source at a receptor, the IFC also indicates that noise associated with a project should not cause the ambient noise level to rise by more than 3 dBA at the nearest off-site receptor.

The United States National Institute for Occupational Safety and Health (NIOSH) recommends that noise be controlled to at or below 85 dBA for an 8-hour exposure (equivalent to a standard workday). For construction or operational tasks where workers may be exposed to noise levels above 85 dBA, PPE is recommended to mitigate the noise exposure.

6.5 Approach

The Project will comply with IFC standards, as well as implementation of management practices and mitigation measures identified in the ESIA. The general approach to noise management is described below:

- **Minimization:** Whenever possible, noise will be minimized at the source by maintaining construction and operational equipment in good working order, and maintaining built-in noise minimization equipment such as mufflers, where applicable. During the construction phase of the Project, the majority of activities will be completed during daytime hours. Engines shall not be started and on-site

activities shall not be undertaken outside of the daytime construction hours. Non noise generating works can be undertaken at staging areas where works are not adjacent to residential receivers. Only well drilling and testing will occur 24 hours a day, 7 days per week.

- **Noise Mitigation (Shielding):** DGDC will use a silencer or rock muffler during all well venting activities. Contractors will need to provide localized noise screening where works are to be conducted within 200 meters (the compliance distance) of any sensitive receivers.

During Project operation, DGDC will maintaining vegetative buffers and/or planting trees and other dense vegetation between the facility and noise receptors to increase soft ground cover and potential attenuation of noise levels.

- **Landowner Notification:** Provide receptors within 1,000 feet of the project parcels written notice prior to the start of construction that describes the approximate schedule for the construction activities and a contact name and phone number for the construction contractor and DGDC staff person responsible for handling construction-related noise complaints.
- **Noise Monitoring:** DGDC will establish baseline sound levels at the nearby receptors prior to commencing construction, and will monitor noise levels at the nearby receptors during construction and operation. Construction activities should be undertaken in accordance with BS 5228, Code of Practice for Noise Control on Construction and Demolition Sites. All equipment used on site would be required to demonstrate compliance with the noise levels recommended within BS 5228.
- **Noise Complaint Resolution:** DGDC will establish a procedure for receiving noise complaints during Project construction and operation, along with a procedure for complaint resolution. This procedure will identify parties' responsibility for investigating the complaint, establishing a response plan, and ensuring that the response plan resolves the noise complaint.
- **Personal Protective Equipment:** DGDC or its contractors will provide PPE for construction and operational staff and training on how to properly use PPE. PPE will be used during tasks where workers may be exposed to noise levels above 85 dBA to mitigate the noise exposure.

6.6 Management and Mitigation Measures

6.6.1 Construction Noise

Construction works should adopt Best Management Practice (BMP) and Best Available Technology Economically Achievable (BATEA) practices. BMP includes encouragement of a project objective to reduce noise emissions. BATEA practices involve incorporating the most advanced and affordable technology to minimize noise emissions.

To minimize impacts at residential receptors from construction noise, DGDC will require contractors to implement the following noise mitigation measures:

- Provide receptors within 1,000 feet of the project parcels written notice prior to the start of construction that describes the approximate schedule for the construction activities and a contact name and phone number for the construction contractor and DGDC staff person responsible for handling construction-related noise complaints.
- Appropriate use of all plant and equipment, with reasonable work practices applied, including no extended periods of 'revving', idling or 'warming up' in proximity to existing residential receivers. Any excessively loud activities should be scheduled during periods of the day when general ambient noise levels are greatest. This would reduce the potential for cumulative noise impacts (relating to worst-case elevated operations) and extended periods of off-site annoyance.

- Minimizing reversing alarm noise emissions from mobile plant and transport truck operations should be considered, provided occupational health and safety requirements are satisfied. Where practicable, site entry and exit points should be managed to limit the need for reversing.
- Construction plant source noise levels should be confirmed prior to the commencement of works to verify construction noise impacts and noise management measures.
- Local residents and landowners are to be notified a minimum of 2 weeks prior to the commencement of construction works. The notification would detail proposed construction works, permitted hours of work and potential noise impacts. This should be done in conjunction with the community liaison officer of DGDC.
- Use a silencer or rock muffler during all well venting activities, including initial cleanout, as feasible.
- Implement the noise management plan that details noise monitoring requirements and noise complaint resolution recommendations.
- Provide PPE for workers completing tasks where noise levels exceed 85 dBA to mitigate the noise exposure.
- Locate haul routes as far as possible from residential receivers.
- Where possible, static construction plant such as generators should be located adjacent to on-site structures to impede noise propagation.

6.6.2 Operational Noise

To minimize facility sound levels and ensure that noise contributions at nearby receptors and increases in ambient noise comply with IFC guidelines, DGDC will ensure the O&M Contractor implement the following mitigation measures:

- Commissioning testing should be conducted during daytime periods only.
- During commissioning testing, temporary localized screening should be erected. Potential noise impact reduction of up to 6 dB(A) is achievable where acoustic screens are located within 5 m of the construction works, be at least 300 mm above the height of the noise source and provide a solid façade impeding line of sight to nearest receivers – any gaps negate noise reduction performance.
- Local residents and landowners should be notified prior to any commissioning testing.
- Maintaining vegetative buffers and/or planting trees and other dense vegetation between the facility and noise receptors to increase soft ground cover and potential attenuation of noise levels.
- Implement the noise management plan that details noise monitoring requirements and noise complaint resolution recommendations.
- Power plant workers will make direct observation of machine maintenance to ensure that any noise-creating faults are treated.
- Provide PPE for workers completing tasks where noise levels exceed 85 dBA to mitigate the noise exposure.

6.7 Noise Monitoring

The EPC Contractor will undertake noise monitoring to evaluate the actual construction noise levels at representative sensitive receiver locations, for example, adjacent to the power plant site. This monitoring should be carried out at the start of the construction of the Project and on a quarterly basis.

Direct observation of machine maintenance should also be made to ensure that any noise-creating faults are repaired. Specific noise monitoring procedures are provided in the Operational Health and Safety Manual prepared by DGDC.

DGDC will monitor the performance of the EPC Contractor. The DGDC shall review and approve the EPC Contractor’s Construction Noise Management Plan (CNMP).

The DGDC shall continuously audit the EPC Contractors adherence to the CNMP and shall upon finding any non-compliance, provide an immediate written notice to the EPC Contractor requiring them to correct the issue within a defined time period. The DGDC shall monitor that the EPC Contractor does in fact address all such matters; if the DGDC finds the EPC Contractor fails to address the matters within the time period, the DGDC shall advise the Engineer to the EPC Contract, whom shall consider the issuance of a “stop work” notice.

During operation, the O&M Contractor will measure noise levels on a quarterly basis at the power plant site and the nearest settlements for a duration of at least 48 hours. Results from this monitoring are to be used to assess compliance with any Dominica and the IFC EHS Guidelines (see above) and to be reported to the relevant authorities. Specific noise monitoring procedures are provided in the Operational Health and Safety Manual prepared by DGDC.

Noise monitoring data should also be made available for public access.

6.8 Training and Complaint Resolution

Before the start of the construction, all project personnel identified within Section 6.2 – Roles and Responsibilities must have received a copy of the Plan and understand their respective responsibilities. A summary of required construction noise management practices shall be provided to all staff and contractors and be included during site inductions. The summary should include, as a minimum, the permitted hours of construction work, work site locations and site ingress/egress.

Prior to the start of construction, DGDC will establish a procedure for receiving noise complaints during Project construction and operation, along with a procedure for complaint resolution. This procedure will identify parties’ responsibility for investigating the complaint, establishing a response plan, and ensuring that the response plan resolves the noise complaint.

All Project construction and operational staff will be trained regarding proper use of PPE, and will be informed of tasks where noise levels exceed 85 dBA to ensure that PPE is used during completion of these tasks.

6.9 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this Plan:

Table 6-3: Key Performance Indicators

Receptor	Impact	Mitigation Measures	Responsibility	Timing	Monitoring and KPI Frequency
Human Use and Residences	Potential increase in daytime airborne noise during general	Provide receptors within 1,000 feet of the project parcels written notice prior to the start of construction that describes the approximate schedule	Head of ESG/ESG Manager/Environmental Coordinator of H&S Manager/ ESG Manager	Construction	Implement noise monitoring described in Section 7 and complaint

Receptor	Impact	Mitigation Measures	Responsibility	Timing	Monitoring and KPI Frequency
	Project construction	<p>for the construction activities and a contact name and phone number for the construction contractor and DGDC staff person responsible for handling construction-related noise complaints.</p> <p>Project construction staff will receive appropriate required PPE and training in their use. Hearing protection will be required for any tasks with the potential for exposure to noise levels above 85 dBA or as outlined in the EPC contractor's worker health and safety plan.</p>	Construction Contractor		<p>resolution procedures;</p> <p>Daily site inspection for appropriate PPE use.</p>
Human Use and Residences	Potential increase in daytime and nighttime airborne noise during well drilling/testing	<p>Install an earthen berm between drilling locations and residential receptor locations within 1,000 feet of the drill rig; Provide receptors within 1,000 feet of drilling sites at least two week's advance written notice of the start of well drilling, well venting, and well testing activities;</p> <p>Use a silencer or rock muffler during all well venting activities, including initial cleanout, as feasible.</p> <p>Project construction staff will receive appropriate required PPE and training in their use. Hearing protection will be required for any tasks with the potential for exposure to noise levels above 85 dBA or as outlined in the EPC contractor's worker health and safety plan.</p>	<p>Head of ESG/ESG Manager/Environmental Coordinator of H&S Manager/ ESG Manager</p> <p>Drilling Contractor</p>	Construction	<p>Implement noise-monitoring requirements described in Section 7. If nighttime noise attributable to well drilling exceed 45 decibels (L_{Aeq}), then additional noise mitigation measures are needed;</p> <p>Implement complaint resolution procedures;</p> <p>Daily site inspection for appropriate PPE use.</p>

7. DISASTER RISK AND EMERGENCY MANAGEMENT PLAN

Please see the Disaster Risk and Emergency Management (DREM) Plan prepared by the Dominica Geothermal Development Company (DGDC), dated August 2019. The Plan can be downloaded at: <https://www.geodominica.dm/download/disaster-risk-and-emergency-management-drem-plan/>

8. WELL BLOWOUT PREVENTION PLAN

8.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensure the compliance of the implementation of the Environmental and Social Management Plan (ESMP) policies and procedures.

To promote the Project's alignment to best international practices, DGDC acknowledges that well control measures are an essential part to maintaining environmental and social health and safety of any geothermal project. Any uncontrolled flow of steam, brine or other well fluids constitutes a well blowout. Well control is the process of maintaining pressure inside the drilled wellbore in a manner that prevents gas or fluids from underground reservoirs flowing into the wellbore and escaping to the environment in an uncontrolled manner. This Well Blowout Prevention Plan details the steps to follow for the appropriate management of the wells in order to prevent potential impacts from a well blowout in the Projects area of influence (AOI).

8.1.1 Objective

The objective of this plan is to comply with international best practice when it comes to well stability and control by identify project risks and providing appropriate mitigation. In general, the objectives of this plan include:

- Protect the health and safety of drilling, construction, and operating personnel
- Protect surface and groundwater quality for local users and the environment
- Define measures and procedures for blowout prevention functions including roles and responsibilities and training requirements;
- Comply with applicable regulatory requirements and recommended international guidelines and align with international best practices; and
- Define and implement monitoring and reporting procedures

8.1.2 Scope of Application

This procedure will apply during the development of DGDC's activities and during the Project's life cycle (construction, operations and decommissioning). It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

8.2 Roles and Responsibilities

In order to properly implement the Well Blowout Prevention Plan, DGDC requires the involvement of the people listed below.

Table 8-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	■ Be familiarized, review and approve the Well Blowout Prevention Plan.
Director of Accounts	■ Ensure the availability of resources necessary for the implementation of the Well Blowout Prevention Plan.
Head of ESG	■ Ensure the correct implementation of the Well Blowout Prevention Plan.

Role	Responsibilities
ESG Manager	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Well Blowout Prevention Plan ■ Update the Well Blowout Prevention Plan. ■ Review and approve the contractor project-specific well blowout prevention plans.
Environmental Coordinator or H&S Manager	<ul style="list-style-type: none"> ■ Ensure the generation of evidence and reports for compliance with the IFC PS as well as maintaining DGDC's KPIs. In addition, ensure the internal coordination to follow the Well Blowout Prevention Plan.
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Well Blowout Prevention Plan.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Well Blowout Prevention Plan.

Typical roles and responsibilities are as follows:

8.2.1 Construction

The Drilling Contractor is responsible for the implementation of the company policies and procedures on well control and will:

- Ensure that all personnel are fully aware of Company policies and procedures, and their own roles and responsibilities.
- Ensure tests and drills are carried out as required and their results are recorded and reported DGDC

It is the responsibility of the Contractor Drilling Supervisor to:

- Acquaint himself with the drill site, the drill rig and drill pad;
- Be knowledgeable of H₂S procedures and verify that all personnel on site are suitably equipped and trained.
- Be acquainted with all project contingency plans;
- Keep DGDC fully informed on any well control situations, and continuously discuss upcoming operations with regards to well control and concurrent operations philosophies.
- Ensure that all well operations are conducted with full primary well control, and that necessary kill mud and mud weight building material are present at all times.
- Ensure that early signs of over pressure are detected and recognized.
- Maintain a system of well control data sheets to be ready for immediate use if required.
- Review in detail the drilling and test programs and advise DGDC of any aspects that might cause well control problems.
- Report the results of tests and drills carried out for well control purposes.

The Rig Drilling Engineer will:

- In conjunction with the engineer in charge of drilling muds, monitor mud logging for indications of abnormal pressure zones or lost circulation zones.
- Calculate the mud weights required to control the well, and supervise operations regarding kill mud preparation.
- Monitor and record details of events.

- Supervise formation strength tests.

Engineer in charge of Data Logger:

The Engineer in charge of the Data Logger has the prime responsibility to ensure the following monitoring systems are both fully operational and well maintained:

- Gas detection (including hydrogen sulfide - H₂S and carbon dioxide – CO₂).
- Drilling fluid data: Density, temperature, flow rates (both in and out of the well), resistivity, and surface volumes.
- Drilling parameters: Hook load, weight-on-bit, rotary torque, pump-rate, standpipe (& casing) pressure, and penetration rates.
- Monitor the resistivity and gamma ray readings that is continuously gathered downhole.

In addition, notify the Driller and Drilling Supervisor of any indications from the data being gathered of potential over pressures.

Engineer in charge of Drilling Muds:

The engineering in charge of the drilling muds is responsible for monitoring mud parameters. They will:

- Inform the Rig Driller and the Drilling Supervisor of changes in mud parameters that may indicate potential over pressures.
- Keep the Driller informed of any mud transfers, treatment, or any other act that will change the mud parameters or volume of the active mud system.
- Plan the maintenance of adequate chemical stocks required for well control purposes

8.2.2 Operation

The capacity, integrity, and security of the geothermal wellhead equipment are the responsibility of DGDC's Plant Manager.

8.3 Blowout Preventers

The main function of the blowout prevention equipment is to safely control the flow of fluids at the surface of a well in case of a blowout. The requirements of the blowout prevention stack are to:

- Close the top of the wellbore to prevent the release of fluids or to allow for the safe diversion of these fluids away from the rig and personnel,
- Allow safe, controlled release of shut in, pressured fluids through choke lines and manifolds,
- Allow pumping of fluids (mud or water) into the wellbore through kill lines, and
- Allow vertical movement of the drill pipe without realizing fluids.

8.4 Prevention Activities

8.4.1 Construction

8.4.1.1 Cementing of Casing

All casing strings will be cemented with a quantity of cement sufficient to fill the annular space back to the surface. The cement utilized will be a Class of cement suitable for the environmental factors of the Site as

determined by the ECP Contractor. Cementing the casing is required in order to provide strength to the casing and prevent the movement of fluids into possible fresh water zones.

8.4.1.2 Equipment Testing

Equipment that may be exposed to well pressure will be pressure tested to a low pressure and then to a high pressure. Pressure testing will be conducted on:

- All blowout preventers and related equipment (when installed, prior to drilling out casing shoes, and following repairs or reassembly of the preventers that require disconnecting a pressure seal in the assembly)
- Casing,
- Choke and kill line valves, choke manifold valves, upper and lower kelly cocks, drill pipe safety valves, and inside blowout prevention equipment

All operational components of the blowout prevention equipment will also be function tested at least once a week to verify the components' intended operations. All flange bolts will be inspected at least weekly and retightened as necessary during drilling operations. The auxiliary control systems will be maintained in working order and inspected daily to check the mechanical condition and effectiveness.

In the event of casing failure during testing, the casing must be repaired or recemented until a satisfactory test is obtained. Results of the pressure tests will be documented and submitted to DGDC for safekeeping.

8.4.1.3 Blowout Prevention Equipment and Procedures

Blowout preventers and related well control equipment will be installed, tested immediately after installation using water, and maintained ready for use until drilling operations are completed. The necessary components, such as packing elements and ram rubbers, will be of high-temperature resistant material. All kill lines, blowdown lines, manifolds, and fittings will be steel and have a temperature derated minimum working pressure rating equivalent to the maximum anticipated wellhead surface pressure.

Blowout prevention equipment will be automated with hydraulic actuating systems and accumulators of sufficient capacity to close all of the hydraulically operated equipment with the required minimum pressure remaining on the accumulator (working pressure of 5,000 psi). The equipment also has three manual locking devices with hand wheels extending outside of the rig's substructure.

The blowout prevention equipment schematic diagram will indicate the minimum size and pressure rating of all components of the wellhead and blowout preventer assembly. All blowout preventers, choke lines, and choke manifolds will be installed above ground level, as will casing heads. The equipment will have a ram type blowout preventers with one set of pipe rams and one set of blind rams.

The accumulator will have sufficient capacity to operate the blowout prevention equipment. Blowout prevention equipment controls will be located in the dog house.

In addition, a full opening drill string safety valve in the open position will be maintained on the rig floor at all times while drilling operations are being conducted. A kelly cock will be installed between the kelly and the swivel.

Using the returning drilling fluid, the automated mud logger and its supporting sensor system continuously survey the changing rock features, formation fluids, and temperature variations and is the first to evaluate the formation of gas and liquid entries that signals the penetration of high temperature/pressure conditions.

8.4.1.4 Design Standards

Well designs, barriers and cementing program were developed with the involvement of a registered Professional Engineer. The following design and testing standards were used for the plant systems:

Table 8-2: Design Standards

Component	Design Standards
Basis of structural Design	Euro norm (EN) 1990
Actions on structures	EN 1991
Design of concrete structures	EN 1992
Design of steel structures	EN 1993, EN 10025 or EN 10210 (hollow sections)
Design of composite steel and concrete structures	EN 1994
Design of timber structures	EN 1995
Design of masonry structures	EN 1996
Geotechnical design	EN 1997
Design of structures for earthquake resistance	EN 1998
Steel for the reinforcement of concrete – Ribbed bars and welded fabric	EN 10080
Concrete - Specification, performance, production and conformity	EN 206
Foundations for Dynamic Equipment	American Concrete Institute (ACI) 351.3R-04
Connections	Deutsches Institute fur Normung (DIN) 931/EN 24014

8.4.1.5 Drilling Fluid

Sufficient drilling fluid materials to ensure well control will be maintained on site and readily accessible for use at all times in two mud tanks. Mud testing and treatment consistent with good operating practice will be performed daily or more frequently as conditions warrant. Mud testing equipment must be maintained on the drilling rig at all times. In addition, there will be mud pit with a functioning alarm as well as high/low level indicators, degassers, and a solids control system.

The temperature of the drilling fluid going into and coming out of the hole will be monitored, read, and recorded on the driller's or mud log for a minimum of every 30 feet of hole drilled below the conductor casing; and a hydrogen sulfide indicator and alarm will be installed in areas suspected or known to contain hydrogen sulfide gas that may reach levels considered dangerous to the health and safety of personnel in the area.

8.4.1.6 Well Control

Before pulling drill pipe, the drilling fluid will be properly conditioned or displaced. The hole will be kept reasonably full at all times; and, in no event will the annular mud level be deeper than 100 feet from the rotary table when coming out of the hole with drill pipe. A mud logger and cooler will be utilized when necessary to maintain mud characteristics for proper well control and hole conditioning.

8.4.1.7 Wellhead Equipment and Testing

In order to complete the wells, all wellhead connections will be fluid pressure tested to the required working pressure rating (see Design Standards above). A certified welder using materials in conformance with the specifications above will perform welding of wellhead connections.

Completed wells will be equipped with a casing head with side outlets, a master valve, production valve, and an expansion spool. All equipment will have a temperature derated working pressure equal to or greater than the surface shut-in pressure of the well at reservoir temperature. Packing, sealing mediums and lubricants will consist of materials or substances that function effectively at, and are resistant to, high temperatures. Wellhead equipment, valves, flanges, and fittings will meet minimum specifications in the Design Standards table above.

8.4.1.8 Supervision

From the time drilling operations are initiated and until the well is completed or decommissioned, a member of the drilling crew or the tool pusher will monitor the rig floor at all times for surveillance purposes, unless the well is secured with blowout preventers or cement plugs.

The operator will use all necessary precautions to keep all wells under control and use trained and competent personnel and properly maintained equipment and materials at all times.

8.4.2 Operation

During operations, wellheads and blowout prevention equipment will be properly maintained and inspected.

There are subsurface risks to casing due to corrosion and scaling. According to current design details, operation parameters in the system will be maintained so that there is no scaling (high temperatures). A well monitoring plan will be prepared once final site conditions are known (see monitoring section below).

Blowout prevention requirements during remedial work, redrills, recompletions and abandonments, in all geothermal wells, will be evaluated and provided for by the same process of consideration required in during new geothermal well drilling.

8.5 Emergency Response

In the event of a well blowout, response measures will require professional judgement; no operation will be undertaken if it involves risk to personnel. A process needs to be developed to respond to these emergencies by the EPC Contractor during Construction and by DGDC during Operation, which needs to include:

1. Measures for protecting the personnel at the site in the event of a well control emergency
2. Notification protocols at the onset of a well emergency
3. Measures to prevent further damage or injury while adequate equipment and personnel are being mobilized

4. Defining the critical information that is required in order to determine the appropriate response level and strategies
5. Organizing personnel and providing guidelines for their roles during the emergency response and the subsequent management
6. Pre-selecting sources and developing mobilization plans for personnel, equipment, materials and services typically required for implementation of well control procedures
7. Notification of the appropriate regulatory agencies

In the event primary well control is lost, a series of escalating responses will be planned to regain primary well control by establishing borehole hydrostatic pressure above formation pore pressures:

It is very important to shut-in the well as soon as possible when uncontrolled flow is suspected. The steps will depend on the phase of the drilling activities (for example, while drilling, while tripping, or testing). Standard practices entail:

- The first response is to close the designated blowout preventer
- Ensure the choke is closed
- Open the choke line hydraulic opening valve
- Verify that the well is shut-in and the flow has stopped
- A detailed blowout response procedure and plan will be developed by the drilling contractor for submittal to DGDC prior to initiation of the drilling activities.

8.6 Documentation and Monitoring

8.6.1 Construction

8.6.1.1 Testing

The results of all blowout prevention equipment pressure tests and function tests must be recorded with all available information including the type of test, testing sequence, low and high pressures, duration of each test, and results of each test.

Casing test results must be recorded in the driller's log and maintained after completion. The casing and lap test reports must give a detailed description of the test including mud and cement volumes, lapse of time between running and cementing casing and testing, method of testing, and test results.

The drilling contractor to DGDC will submit all testing results.

8.6.1.2 Monitoring

The driller will monitor the drilling penetration rate and the drilling fluid circulation during drilling activities. The logger will monitor temperature variations, secondary mineralization and formation fluid entries. The temperature of the drilling fluid going into and coming out of the hole will be monitored, read, and recorded on the driller's or mud log. This information will be used to predict irregularities and risks and inform the drilling engineering and drilling supervisor immediately. All drilling and mud logs must also be maintained until completion of the Project.

8.6.2 Operation

During operation, wells need to be monitored for any warning signs of undesirable changes such as decreasing generating capacity due to lower pressure or flow, insufficient injection capacity, or possible operational problems such as scaling or corrosion in the wells or in the surface equipment.

Monitoring programs have to be specifically designed for each geothermal reservoir, because of their individual characteristics and the distinct differences inherent in the metering methodology adopted. Monitoring programs may also have to be revised as time progresses, and more experience is gained, e.g. monitoring frequency of different parameters. A monitoring program will be developed once more information is known about the specific characteristics at the site. Below is a list of directly observable basic aspects included in conventional geothermal monitoring programs:

- Mass discharge histories of production wells (pumping for low-temperature wells).
- Temperature or enthalpy (if two-phase) of fluid produced.
- Water level or wellhead pressure (reflecting reservoir pressure) of production wells.
- Chemical content of water (and steam) produced.
- Injection rate histories of injection wells.
- Temperature of injected water.
- Wellhead pressure (water level) for injection wells.
- Well status through diameter monitoring (caliper logs), injectivity tests and other methods

8.7 Training

8.7.1 Construction

Prior to drilling activities, all tool pushers and drilling superintendents are required to have completed an API, IADC, or similar governing body sanction well control certification program. The certification must be renewed every two years.

While on site, a blowout prevention practice drill must be conducted weekly for each drilling crew and be recorded on the driller's log.

8.7.2 Operation

Frequent pit drills and mock well control drills will be planned and conducted for all plant personnel. Records of all training and drills will be maintained on site for as long as the personnel are employed.

8.8 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 8-3: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool/Frequency
Health and Safety	Employees must be in compliance with the training program (weekly)	100%	Construction and	Training Records / Weekly

Health and Safety	Employees must be in compliance with the training program (every six months)	100%	Operation	Training Records / Every six months
Health and Safety	Employees must be in compliance with the drills program and been instructed on incorrect actions and/or deficiencies.	100%	Construction and Operation	Training Records / Yearly
Health and Safety	Percentage of workers who have training on safety and emergency response.	100%	Construction and Operation	Training Records / Yearly
Health and Safety	Number of accidents and incidents	Zero incidents	Construction and Operation	Incident Reports / Monthly

9. EMERGENCY RESPONSE PLAN

An Emergency Reponses Plan details actions to be taken for an effective response in the event of the emergencies that could potentially be experienced by the Project, including physical accidents to personnel fires, and sabotage. The Plan also defines the roles and responsibilities during an emergency response. An Operational Health and Safety Plan which includes Emergency Response Procedures under the potential emergency situations that could be experienced by the Project was prepared by DGDC. The Plan can be downloaded at: <https://www.geodominica.dm/download/disaster-risk-and-emergency-management-drem-plan/>

10. SECURITY MANAGEMENT PLAN

10.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensure the compliance and implementation of the Environmental and Social Management Plans (ESMP) policies and procedures.

The Security Management Plan will assure an effective protection of people, assets, and operations of the Project, in accordance with the World Bank Performance Standards, Human Rights principles, and minimizing any possible impact on local communities.

10.1.1 Objective

The objective of this plan is to establish and define the guidelines that guarantee the protection and Security of the assets and personnel involved in the execution of DGDC's projects and activities.

10.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during projects' life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

10.2 Roles and Responsibilities

In order to properly implement the Labor Conditions and Workers Selection Plan, DGDC requires the involvement of the people listed below.

Table 10-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none">■ Review and approve the Security Management Plan.
Director of Accounts	<ul style="list-style-type: none">■ Ensure the availability of resources necessary for the implementation of the Security Management Plan.
ESG Manager	<ul style="list-style-type: none">■ Ensure the correct implementation of the Security Management Plan.■ Review and approve the contractor project-specific Security Management Plan.
H&S Manager	<ul style="list-style-type: none">■ Ensure the correct implementation of the Security Management Plan.
EHS Representatives ⁴	<ul style="list-style-type: none">■ Help with the implementation of the Security Management Plan.
Head of Security	<ul style="list-style-type: none">■ Manage the security personnel, implement, update and monitor the Security Management Plan.

⁴ The EHS Representative will be the main authority on the Project site in charge of Environmental Health and Safety (EHS).

Role	Responsibilities
Security Personnel (Guards, Drivers, etc.)	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Security Management Plan. ■ Develop their work in compliance with all applicable regulations regarding respect for Human Rights (World Bank PS 4). ■ Know how to proceed with complaints and / or claims of interest groups and local communities.
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Security Management Plan aligned with this Security Management Plan.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Security Management Plan.

10.3 Activities

At the beginning of the Project, DGDC must identify potential risks or impacts related to physical security, by using the Risk and Impact Identification process, and determine the level of risk of each situation.

The following are the most common situations that DGDC may face during a Project development:

- Material/equipment robbery;
- Presence of unauthorized personnel in the Project;
- Entry or intrusion of personnel within restricted areas;
- Conflicts between workers; and
- Conflicts between Project's workers and local communities.

To prevent this type of risks and impacts from occurring, there are some measures that can be carried out in the DGDC Project:

- Security services;
- Access Control Service for workers, machinery, suppliers, and external visitors;
- Surveillance rounds;
- Communication system with the security service and the police.

These activities may change depending on the results obtained in the risk analysis. When required, these criteria will be included as contractual measures. Risk and Impact Identification and established prevention / mitigation measures will be reviewed periodically or when there are relevant changes, in order to ensure sufficient protection throughout all phases of the Project's life cycle.

For cases in which this type of situation cannot be prevented, there will be specific (and confidential) procedures for action by workers with Security responsibilities, which favor the control of said situations and minimize their possible conditions.

There will be total coordination between the workers responsible for DGDC's Security and the Local Authorities. If necessary and depending on the circumstances, DGDC may require assistance from Local Authorities, and vice versa. Any incident related to Security must be reported and investigated to analyze its possible causes and avoid its recurrence in the future.

10.3.1 Site Security

In order to provide security, DGDC will fence the entire parcel and construct a security guard facility at the entrance gate. Additional security generally consists of cameras and perimeter monitoring by security. DGDC plans to maintain the existing trees, shrubs, and dense vegetation along the site boundaries.

10.3.2 Recruitment for Security Personnel

To assure that the Security Personnel working for DGDC are aligned with best international practices, the hiring of Security Personnel and their performance, will need to meet the following criteria:

- Security Personnel will have full understanding of DGDC's Safety, Health, Environment and Social Standards, World Bank PS 4, DGDC's Code of Conduct, the Basic Principles on the Use of Force and Firearms by Law Enforcement Officials (United Nations) and applicable local legislation in this matter.
- Security Personnel will require to present a completed Use of Force and Human Rights Training certification before they begin to work at the Project.
- Security Personnel will show professionalism in managing expectations and concerns in conflicts in which local communities may be affected.
- DGDC will not hire as Security Personnel any individual who has been involved in cases of abuse of Human Rights.
- Security Personnel will comply with the confidentiality agreements for sensitive information to which they will have access due to their employment position.
- DGDC will provide the necessary material resources to ensure that prevention and defense work strengthens the necessary levels of physical security.
- The performance of the Security Personnel will be monitored, corrective actions will be identified and lessons learned will be implemented.
- An investigation (documented and registered) will be carried out by DGDC of any abusive situation or in which the previously cited principles have been breached. Such cases will entail the necessary disciplinary measures.

Security personnel must have knowledge of the Internal Grievance Mechanism and their labor rights/conditions at all times. DGDC labor conditions are aligned International Finance Corporation (IFC) Performance Standard (PS) 2.

10.3.2.1 Human Rights and Use of Force Training

All security personnel working on the Project will be required to provide a completed human rights and use of force training certification before starting to work at the Project. The Project aims to maintain a work environment that values the respect for human rights and the treatment with fairness and dignity of all people involved in the Project, as well as the external stakeholders. The training will include subjects such as appropriate conduct in different security scenarios, lawful use of force and use of less lethal weapons, and if applicable, the use of firearms. The Project does not expect to have armed security guards, however, this training will still be compulsory for all security personnel.

Instructions will emphasize that "security personnel are permitted to use force only as a matter of last resort and only for preventive and defensive purposes in proportion to the nature and extent of the threat, and in a manner that respects human rights" (IFC, Guidance Note 4). For example, security guards will refrain from verbal or physical harassment of any kind. Lethal force will be used only where other means are unsuccessful, and only to protect human life.

Training programs can be provided by the Project, the security provider, and/or qualified third parties (or a combination of these). When training is designed and delivered by contractors, the Project will periodically review the training agenda, materials, attendance log, and other aspects of the training, and the Head of Security will also attend a training session. The human rights and use of force training certification will be required before starting to work in the Project and a re-fresher training will be required on a yearly basis.

The Human Resources Manager in collaboration with the Head of Security will keep records of all the security guards on site and the necessary documentation proving the training completion (training certificate, specific training curriculum and date of completion).

10.3.3 Training and Information

In addition, employees with Security responsibilities (Guardians, Drivers, etc.) will receive specific training in order to ensure that the response to any dangerous situation is adequate.

These trainings will consider social aspects and respect for Human Rights. Emphasis will be placed on the identification of stakeholders and local communities, their expectations and possible concerns and the associated potential risks.

In addition, Employees with responsibilities in the field of physical security will understand the External Grievance Mechanism Plan to act on it in cases where they interact as a point of contact between the local communities' members and the Project.

10.3.4 Security Guard Functions

The main functions of DGDC's Security Personnel is to ensure and safeguard the Project facilities, as well as material goods of any kind, along with:

- Reduce the possibility of equipment subtraction, deterioration or improper use.
- Control at all times the entry and exit of staff and guards to the site.
- Manage the existing protection systems (fire detection, surveillance and security systems, alarms, etc.);
- Collaborate in evacuation, alarm, firefighting, first aid, transportation of wounded and intervention, etc.
- Immediate communication with Project supervisors and local authorities in case of an incident (the security guard must always have the phone numbers or contact information to communicate the emergency in a timely manner);
- Control the entry and exit of vehicles in access control; and
- Control of poorly parked vehicles.

10.3.5 Site Access Control

For access to the facilities or sites, workers, contractors and visitors must wear an identification badge in a visible place during their stay.

The identification badge must have at least the following information:

- Name of the company;
- Full name of the employee or in the case of visit must be indicated on the badge;
- Number or validity of the badge; and
- Photograph.

The ESG Manager is responsible for coordinating with the Security Personnel the access of contractors, visitors and workers to the Sites. Visitors will also be provided the appropriate PPE.

During the days when there are no assigned tasks or maintenance routines, personnel will not be allowed access to the sites. Access to any person who intends to sell or promote any item or service within the DGDC Sites or facilities is prohibited.

10.3.6 Additional Measures

For security measures regarding unplanned events and emergencies at the Project, see DGDC's Emergency Management Plan. Furthermore, below are some security related additional measures applicable to DGDC's employees, contractors, subcontractors, service providers and visitors to ensure the physical safety of the Project, these measures will be communicated and monitored by the ESG Manager.

- Smoking is prohibited at all the DGDC Installations.
- The entry of weapons is not allowed.
- The introduction, possession and/ or consumption of alcoholic beverages, drugs or narcotic or psychotropic substances on the Project's sites, as well as access to people to the site under their influence is strictly prohibited.
- When noticing any unsafe conditions, the person of the highest rank on the site must inform the EHS Representative.
- Workers or any other people from the Project will not be allowed to carry out any activity if they are not authorized and trained.
- The areas must be kept clean and free of objects that impede the work.
- The EHS Representative will be informed of any people or vehicles outside or outside their work area.
- All Project staff will be asked to stay alert to unsafe conditions, correct them and notify them immediately.

10.4 Documentation and Monitoring

The Head of Security will keep evidence and will be maintained through the logbooks and minutes of the meetings, and other applicable documents.

10.5 Key Performance Indicators

The Security Management Plan is to be reviewed on a six-month basis for the initial two years and then annually or as necessary in consultation with the Head of Security. The Project will ensure that contractors update their procedures at least once every six months during the first two years and then annually or as needed.

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 10-2: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
Security Incidents (internal and external)	Number of security incidents per quarter (involving workers)	Zero security incidents. If security incidents occur, 100% of the incidents should be	All phases of the Project	Head of Security's Records and Reports, in coordination with

		reported (including how it was solved, lessons learnt and corrective actions).		Contractors / per quarter
	Number of security incidents per quarter (involving community members of other external stakeholders)	Zero security incidents If security incidents occur, 100% of the incidents should be reported (including how it was solved, lessons learnt and corrective actions).	All phases of the Project	External and Internal Grievance Mechanism / per quarter
	Number of grievances from the community related to security at the Project	100% grievances regarding security concerns addressed and solved in a timely manner	All phases of the Project	
Security Trainings	Security personnel trained at the Project (human rights and use of force trainings)	100% of trained security personnel before starting to work at the Project and re-fresher training on a yearly basis	All phases of the Project	DGDC Human Resources Training Records / Yearly
Inspections	Number of inspections per quarter	At least one internal security inspection will be carried out each quarter	All phases of the Project	Head of Security's Records and Reports, in coordination with Contractors / Quarterly

11. OPERATIONAL HEALTH AND SAFETY MANAGEMENT PLAN

A thorough Operational Health and Safety Plan which includes procedures for potential emergency situations that could be experienced by the Project was prepared by DGDC. The Plan can be downloaded at: <https://www.geodominica.dm/download/occupational-health-safety-manual/>

12. LABOR CONDITIONS AND WORKERS SELECTION PLAN

12.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the Environmental and Social Management Plans (ESMP) policies and procedures, and the World Bank PS 4 standard.

DGDC considers that its employees represent the true competitive advantage and the main asset of the organization. As such, DGDC believes the culture and the way its employees experience the company is essential and will seek through different actions to promote a culture focused on excellence, by relying on its employees, their permanent development over time and access to professional opportunities and personal growth.

The Labor Conditions and Workers Selection Plan aims to create the framework of action to promote mutual benefits and ensure workers are involved with the vision, mission, objectives, principles and organizational values.

12.1.1 Objective

The overall objectives of the Labor Conditions and Workers Selection Plan are to:

- Base the recruitment, selection and hiring of personnel on merit and competitiveness;
- Establish, maintain and improve worker-manager relationship;
- Promote fair treatment, non-discrimination and equal opportunity of workers, and compliance with healthy and safe (H&S) working conditions; and
- Protect workers' wellbeing.

12.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle (drilling, plant construction, commissioning and operations). It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

Contractors will use this procedure and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

12.2 Roles and Responsibilities

In order to properly implement the Labor Conditions and Workers Selection Plan, DGDC requires the involvement of the people listed below.

Table 12-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	■ Be familiarized, review and approve the Labor Conditions and Workers Selection Plan.
Director of Accounts	■ Ensure the availability of resources necessary for the implementation of the Labor Conditions and Workers Selection Plan.
Head of ESG	■ Be familiarized with the Labor Conditions and Workers Selection Plan.

ESG Manager	<ul style="list-style-type: none"> ■ Update the Labor Conditions and Workers Selection Plan. ■ Review and approve the contractor project-specific Labor Conditions and Workers Selection Plan.
Calibration Committee	<ul style="list-style-type: none"> ■ Review the evaluation of its collaborators, as established in this plan.
Human Resources Manager	<ul style="list-style-type: none"> ■ Supervise the implementation of the Labor Conditions and Workers Selection Plan among internal stakeholders upon hiring and reinforce it as necessary. ■ Coordinate, together with the Community Liaison Officer, the implementation of the temporary jobs program, according to the present plan. ■ Supervise the Performance Management Process, according to what is stated in this plan.
Community Liaison Officer (CLO)	<ul style="list-style-type: none"> ■ Coordinate, together with the Human Resources Manager, the implementation of the temporary jobs program, according to the present plan.
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific plan aligned with the Labor Conditions and Workers Selection Plan in accordance with the World Bank Performance Standards, particularly PS 2.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Workers Health and Safety Management Pan.

12.3 Activities

DGDC acknowledges the importance of basic rights of workers and the value of a solid worker-manager relationship, which will be achieved through a fair treat to direct and indirect workers and the provision of health and safety (H&S) working conditions.

In order to do so, DGDC has developed the Labor Conditions and Workers Selection Plan, which is composed of the steps presented herein.

DGDC will undertake vocational training to assist local people in obtaining jobs with the Project.

12.3.1 Working Conditions and Management of Worker Relationship

A constructive worker-management relationship, and by treating workers fairly and providing them with safe and healthy working conditions, DGDC may create tangible benefits, such as enhancement of the efficiency and productivity of its operations.

12.3.2 Human Resources Policy

DGDC, through the Human Resources Manager, will develop, communicate, explain and make accessible to all the Project's workers an integrated Human Resources Policy upon taking employment.

The Human Resources Policy will provide workers with information regarding their rights under the applicable labor law, including their rights related to wages and benefits. It may also include DGDC' vision, mission, objectives, principles and organizational values.

12.3.3 Working Conditions and Terms of Employment

DGDC, the EPC Contractor and all Subcontractors will ensure a transparent hiring process is conducted to help the community to understand strategic staffing decisions for the Project.

DGDC will prepare a vocational training and job opportunity program. This training program will aim at:

- Making aware hard-to-reach groups of job opportunities
- Facilitating the growth and development of new entrepreneurs, both individuals and groups originating from affected communities

- Providing opportunities for women and women's groups to participate in the work force to the extent safe and practical, and assist them in having good quality work standards so they can train others and are able to work with other companies in the future

The yearly communication plan maintained by the Community Liaison Officer will be used to that effect.

As part of the recruitment process, the Human Resources Manager will evaluate the candidates' skills in relation to the minimum requirements of the position to be filled. The workforce will be composed of staff with the experience, education, training and the appropriate skills required for their job functions.

To this end, the Human Resources Manager will establish job descriptions based on the essential functions of the position, as well as knowledge, skills and abilities necessary to perform the required functions.

Prior to a hiring being done, the Human Resources Manager will let the new employee know what their role will be, their contribution to the organization and how this translates into the delivery of better services. Moreover, the Human Resources Manager will make sure the new employee is aware of the exact duration of their contract, this will prevent public false accusations against the company or rumors that could affect DGDC' reputation due to the termination of employment.

The Human Resources Manager will document and communicate to all new employees their working conditions and terms of employment, including wage, benefits, holidays, right to unionize in compliance with applicable local laws.

It is for the aforementioned, that DGDC has established an onboarding process that considers, among others, the following elements:

- Rights and duties of the collaborators and all those regulations that govern their behavior;
- Actions that promote a work environment based on mutual respect between men and women;
- Actions aimed to prevent, tackle and eradicate any type of discrimination;
- Specific induction actions when a person joins the company, to align them with the values and responsibilities in the management of their role within the organization;
- Specific actions that allow an adequate reincorporation of those people who are integrated after a prolonged medical leave, parental post-natal leave or some other situation that for a long time has distanced them from the Project;
- Specific actions in the induction of the position when a person changes functions within the organization, assuming new responsibilities and, especially, when it comes to positions of leadership and with responsibility in the direction of the persons, in such a way, to align them with the values and responsibilities in the management of people who are responsible for it.

12.3.4 Worker's Organizations

If national law recognizes workers' rights to reunite, form and join workers' organizations and to bargain collectively, DGDC will comply with national law. Where national law substantially restricts workers' organizations, DGDC will enable alternative means for workers to express themselves and protect their rights regarding working conditions and terms of employment.

In either case described in the prior paragraph, and where national law is silent, DGDC will not discourage workers from forming or joining workers' organizations or from bargaining collectively, and will not discriminate or retaliate against workers who participate, or seek to participate, in such organizations.

12.3.5 Non-Discrimination and Equal Opportunity

DGDC will not make employment decisions on the basis of personal characteristics unrelated to inherent job requirements, it will base the employment relationship on the principle of equal opportunity and fair treatment, and will not discriminate with respect to aspects of the employment relationship, including:

- Recruitment and hiring;
- Compensation (including wages and benefits);
- Working conditions and terms of employment;
- Access to training;
- Promotion;
- Termination of employment or retirement; and
- Discipline.

The Human Resources Manager will ensure that the principle of equality is applied to the company's daily development of activities, by eradicating the existence of preferences or differences that may exist due to gender, religion, country of origin, sexual orientation, ethnicity, pregnancy, age, disability, among others. DGDC will comply with national law with regards to encouraging nondiscrimination in employment. If national laws are silent on nondiscrimination in employment, DGDC will meet the conditions stated in the International Finance Corporation's (IFC) Performance Standard (PS) 2 (e.g., freedom of association, abolition of forced labor, equal remuneration).

12.3.6 Gender Equality

DGDC is committed to promoting gender equality and diversity through its actions. It aims to identify opportunities and strategies to improve the workplace, so both women and men can perform their jobs well, and develop action plans to institute new or strengthen existing policies and practices to recruit, retain, and promote more women.

To this regard, DGDC has assumed the following compromises:

- The rates of violence against women will be part of the social studies of the region where the Project is located, so that mitigation actions can emerge if necessary;
- Possible negative impacts that DGDC' actions may generate will be identified, not only in relation to human life, but also in relation to gender;
- Prioritize the cultural factors of each area, to evaluate important issues:
 - Active female voice;
 - Women's loneliness in the case of male migration to work;
 - The types of help and assistance required these women to become an active voice in employee engagement.
- A safe environment for women in the communities will be created or them to express themselves without fear of reprisal;
- All community meetings will be held at the best time for the female population of the region, always respecting their established schedules of domestic activities and attention to children and older focus groups, if necessary;
- A welcoming environment will be created for motherhood needs (e.g. take her child to a meeting);

- No woman, child, or elderly person will be put at risk or suffer any kind of reprisal;
- All of DGDC' partnerships on the construction site will have contractual clauses to the detriment of:
 - Zero tolerance for moral and sexual harassment (Gender-based Violence Policy);
 - Minimum percentage of training and local female workforce in construction and project development;
 - Specific personal protection equipment for women's work;
 - Flexible working hours if women are breastfeeding.
- The Grievance Mechanisms will be able to immediately act and resolve instances and complaints of gender-related discrimination (including harassment, bullying, sexual abuse, etc.). DGDC will monitor and oversee the handling of complaints of gender-related discrimination.

The Human Resources Manager will personally follow up on all workplace harassment complaints, as well as other gender related issues received through DGDC's Internal or External Grievance Mechanisms.

12.3.7 Retrenchment

If the Project anticipates the elimination of a significant number of jobs or a layoff of a significant number of workers that cannot be avoided, the Human Resources Manager will develop and implement a plan to mitigate the adverse issues, such as:

- The schedule of cutbacks;
- Retrenchment methods and procedures;
- Selection criteria (i.e., the selection criteria for those to be laid off will be objective, fair and transparent);
- Severance payments;
- Offers of alternative employment;
- Assistance in retraining efforts and job placement.

Additionally, in many countries, national law requires advance notice to affected workers, communities and/or governments. DGDC will comply with national law. Where national law is silent on this matter, DGDC will still notify workers and communities in advance, so they are aware if the process that will unfold.

Consultation with governmental institutions may be required by law, and, in addition, DGDC will approach local governments where the scale of layoffs can have a significant effect on communities, and where government assistance may be available to help address the impacts.

DGDC will also consult with employees and their organizations in developing the retrenchment plan for the Project. Consultations are essential for the development of plans to reflect workers' concerns, as well as their ideas about ways to avoid or minimize layoffs, criteria for selection and compensation payments.

The Internal and External Grievance Mechanisms adopted by DGDC will both serve as communication channels to deal with claims that any provisions in the retrenchment plan were not followed.

Nonetheless, it is important to note that the Project does not expect significant retrenchments as the expected number of workers, even during peak construction periods will not exceed 50 workers. During operations, approximately 3 employees will work on site.

12.3.8 Grievance Mechanism

DGDC will implement an Internal Grievance Mechanism for employees and all other internal stakeholders to raise workplace related concerns (see Internal Grievance Mechanism Plan). The Human Resources Manager will inform workers of the grievance mechanism at the time of hire, as well as through refresher trainings.

12.4 Workforce

DGDC acknowledges that the workforce is a valuable asset and a key ingredient in the sustainability of a company. Hence, it is committed to protect and prioritize its Project's workers integrity and wellbeing.

12.4.1 Child Labor

DGDC will not employ children in any capacity. DGDC will follow national applicable laws and PS.2/ILO.

12.4.2 Forced Labor

DGDC will not recur to forced labor, which consists of any work or service not voluntarily performed that is requested from an individual under threat of force or penalty. This covers any kind of involuntary or compulsory labor, such as indentured labor, bonded labor or similar labor-contracting arrangements.

DGDC will not hold on any personal documentation of workers at any point of the Project development under any circumstances.

12.5 Occupational Health and Safety

DGDC has designed an Occupational Health and Safety Management Plan. The aim of this plan is to ensure workers perform their activities in a safe and healthy work environment, taking into account inherent risks in its particular sector and specific hazards in the Project's work areas, including physical, chemical, biological, and geothermal risks.

DGDC will take steps to prevent accidents, injury, and disease arising from, associated with, or occurring in the course of work by minimizing, so far as reasonably practicable, the causes of those hazards.

12.6 Temporary Jobs

The temporary jobs that the Project could generate for the community members during its construction and operations play a very important role for the company, as they will allow the establishment of a good relationship with local communities.

The purpose of the generation of temporary jobs, using local, not specialized people, to carry out Project's activities, is to provide a temporary source of income for the people living near the Project. The supply of jobs in the Project's Area of Influence, although short term, could affect positively in the quality of life of the neighboring people.

This process is expected to happen mainly during the construction phase of the Project and will be coordinated by the Human Resources Manager, alongside the CLO.

12.6.1 Hiring Requirements

The potential beneficiaries of the program will be, on an equal footing, men and women over 18 years old, in compliance with current labor legislation.

They must be mainly inhabitants of the communities in the Project Area of Influence who are not public servers and have the necessary skills to carry out the activities.

The Contractor shall where practical maximize the use of local Dominica labor, suppliers and services during the execution of the project. Local Dominican labor shall include non-skilled, semi-skilled and skilled labor as well as Dominica based service providers. Service providers shall include labor hire companies, local civil contracting companies, catering and transport services and the like. Furthermore, Bidders shall provide a methodology statement on how local labor, suppliers and services will be sourced and engaged as well as the proposed conditions of engagement.

The EPC Contractor will develop a visitor's center at the power plant and hand it over to the community in order to allow them to create visitor business.

DGDC and its contractors will define clear hiring criteria, according to their internal procedures and in compliance with legal requirements, including the DGDC's Human Resources Policy.

DGDC will put an emphasis to attract diverse candidates, addressing bias in selection and will include gender recruitment targets to measure progress towards gender equity goals. These processes are described below.

12.6.1.1 Attracting Diverse Candidates

In order to attract diverse candidates DGDC and its contractors will:

- Check job descriptions for biased terms or gendered language: Gender-inclusive terms are more likely to signal gender inclusivity and opportunities for both men and women. For example, use gender-neutral language, such as "foreperson" instead of "foreman";
- Revise job descriptions if necessary, to encourage gender diversity:
 - DGDC will describe the job requirements, not the person who will fill the job. For instance, for physically demanding jobs, the specific tasks will be described, rather than describing a "physically fit" candidate.
 - Clearly state required or desirable skills; state any formal training/qualifications required (but only require them when they are necessary for the job);
 - Specifically state that the job is open to all type of candidates;
 - Highlight opportunities for career progression;
 - Clarify whether a job requires standard on-site working hours, shift-work, and/or the potential for flexible work arrangements.
- Review job announcements and recruiting material (such as print, radio advertisement, etc.) for gender-biased language:
 - Do they present a gender-diverse and inclusive image?
 - Are men and women featured?
 - Are both men and women featured in operations roles?
 - Do voice-overs in radio, social media or television feature both men and women?
- Revise job advertisements and materials to present a more gender-inclusive and diverse image:
 - Include men and women in a variety of roles;

- Use men's and women's voices;
 - Highlight career development potential for both men and women.
- Review job applications for questions that may prompt gender bias:
 - Applications will only ask for relevant information—and not request details such as marital status or age;
 - Applications will include opportunities for candidates to highlight previous formal and informal work experiences that support their ability to do the job.

Review job selection criteria that may create bias. For instance, a question asking for years of experience might not directly impact skills or qualifications; however, it could put at a disadvantage male or female applicants who have taken time out of work for family reasons.

12.6.1.2 *Address Bias in Selection*

In order to address possible bias in the selection process, DGDC and its contractors will:

- Ensure gender diversity in recruitment/selection teams: Selection teams will include at least one male and one female of equal seniority;
- Conduct bias training with HR and selection teams: This will help to identify and combat hidden biases, such as what work is appropriate for women, or how periods of absence from the workforce are judged;
- Ensure all members of selection teams are aware of relevant legislation related to non-discrimination;
- Test HR staff and selection teams for implicit bias: such as associations between women and men and different types of work;
- Develop a standardized, transparent recruitment process: This will ensure that all applicants have equal opportunity. Providing detailed criteria for all advertised positions will reduce reliance on subjective questions of “proper fit”;
- Set minimum targets for the number of shortlisted female candidates: If DGDC uses a recruitment firm, DGDC will make sure the firm knows about the targets and is held accountable for meeting them;
- Develop a policy on appropriate interview questions: DGDC will avoid questions regarding marital status, children, intent to have children, or sexual orientation.

12.6.1.3 *Recruitment Targets*

Setting targets will help DGDC to measure progress towards gender equity goals. They increase coordination and strengthen commitment to meeting these equity goals. While targets (and quotas) cannot address the underlying reasons for under-representation of women in particular parts of the workforce, they have been shown to be among the most effective means of addressing gaps in gender diversity.

Targets will be specific and challenging. In addition to quantitative metrics, they will include qualitative indicators of the ways in which people work together—for instance, targets that signal a more respectful workplace, more inclusive meeting practices, and more flexibility in work arrangements. Metrics also might include indicators like decreased absenteeism and turnover, and higher employee satisfaction. A table is presented below with DGDC's targets in order to achieve gender equity in employment and have a gender-inclusive work environment.

Table 12-2: Targets

Type of Target	DGDC TARGET
GENDER EQUITY IN EMPLOYMENT	<ul style="list-style-type: none"> ■ 15% target of women working on the project
REVIEW HR POLICIES AND PHYSICAL INFRASTRUCTURE	<ul style="list-style-type: none"> ■ Review all job descriptions and recruitment material related to positions in all departments for gender-discriminatory or discouraging language; ■ Review HR policies regarding ergonomics, personal protective equipment (PPE), workplace safety, and equipment to ensure that these consider differences in safety needs between, men and women; ■ Ensure that all departments on site comply with HR policies on ergonomics, PPE, workplace safety and equipment; ■ Ensure all toilet and shower facilities to be compliant.
GENDER-INCLUSIVE WORK ENVIRONMENT	<ul style="list-style-type: none"> ■ Improve parity in perceptions on career development opportunities between male and female employees.

Source: ERM based on IFC, Unlocking Opportunities for Women and Business, A Toolkit of Actions and Strategies, 2020.

12.6.2 Communication Mechanisms

Different communication mechanisms will be developed as described in the Stakeholder Engagement Plan, in order to encourage the participation of communities located within the Project Areas of Influence.

Communication activities and the publication of vacancies will contain at least the following information:

- The requirements to be a candidate for the program: Applicants will have the obligation to state their personal data, including name and address, which must be corroborated by the Company's Human Resources Area;
- The jobs offered will specify temporary and/or permanent conditions;
- They will be informed if any type of minimum training related to the position offered is required.

Once the temporary employment vacancies are announced, together with their requirements, those who are in compliance may apply and, on the dates indicated, the beneficiaries of the program will be published.

12.6.3 Workers Engaged by Third Parties

DGDC developed the Contractors Management and Supervision Plan to define the minimum requirements that contractors and subcontractors working on behalf of DGDC must meet, in order to ensure that the environmental, social, and occupational health and safety risks associated with the contracted services, products and equipment are reduced and avoided. DGDC will take into account the risks inherent to their particular sector and specific classes of hazards in work areas, including physical, chemical, biological and geothermal hazards.

12.7 Performance Management Process

DGDC has adopted a performance management process, so that each employee receives timely feedback regarding their performance, either positive to continue in their path of growth or professional development, or corrective, in order to implement corrective actions if necessary.

The process considers, among others, the following elements:

- Evaluation of cultural components, referred to the level of compliance of the competencies of each collaborator in the organization;
- Evaluation of work objectives, which involve three types:
 - Platform Success: DGDC' objectives as a whole;
 - Functional Component: Group or area objectives
 - Individual Component: Specific objectives and goals for each collaborator.

To obtain final performance grade of each collaborator, the responsible evaluator must submit his/her judgment to a calibration committee, formed by DGDC's management team, in which the partial result of the evaluation of its collaborators in charge will be reviewed, as to be able to count on an integral appreciation of the performance of each collaborator.

Likewise, in the calibration committee, the responsible supervisor/evaluator may have solid and consistent arguments that justify the evaluation that will be delivered. Therefore, the evaluator can also have arguments agreed by the entire committee to deliver to the employee when giving feedback.

The performance evaluation process has a duration of one year, understood as the beginning of the evaluation period, the month of January of each calendar year.

12.8 Documentation and Monitoring

The Human Resources Manager will be responsible for the implementation of what is stated in this plane and will keep evidence of it (e.g. documentation on DGDC's policies, recruitment documents and processes, working conditions, internal grievance mechanism, workers who come from local communities, number of women hired by the Project).

DGDC will monitor the number of people being employed by the Project in:

1. The three key villages (Laudat, Trafalgar and Wotten Waven)
2. The wider Roseau Valley, against predicted numbers of employees.

DGDC will undertake surveys to determine the number of new businesses generated by the development and the level of indirect employment.

During the first four years of operation, on a quarterly basis, DGDC will record the number of inhabitants of the three villages affected by the power plant to have received training, and nature of training received, disaggregated by age, sex and village/block.

12.9 Key Performance Indicators

The Labor Conditions and Workers Selection Management Plan is to be reviewed on a six-month basis for the initial two years and then annually or as necessary in consultation with the Human Resources Manager. The Project will ensure that contractors update their procedures at least once every six months during the first two years and then annually or as needed.

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 12-3: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool Frequency
Working Conditions	Human Resources Policy distributed in all the onboarding inductions	100% of Inductions shall distribute the Human Resources Policy (as well as the Code of Conduct, and other relevant policies, e.g. Sexual Harassment Policy)	Construction and operations	Human Resources Records and Internal Grievance Mechanism / Quarterly
	Sign Terms of Employment	Terms of employment explained and signed by 100% of the Project's workforce	Construction and operations	
	Non-discrimination and gender-based violence	Zero tolerance of discrimination of any type. 100% reported, evaluated and solved grievances regarding discrimination complaints and gender-based violence in a timely manner	Construction and operations	
	Gender equality: percentage of women working in the Project	15% target	Construction and operations	
	Retrenchments	100% of informed workers regarding the schedule of cutbacks; the retrenchment procedures; transparent and fair selection criteria for those to be laid off; severance payments; and if applicable offers of alternative employment; and assistance in retraining efforts and job placement.	Construction and operations	
Workforce	Child Labor and Forced Labor	Zero child or forced labor.	Construction and operations	Human Resources Manager / Quarterly
Hiring	Recruitment Targets	100% recruitment targets met to attract diverse candidates and avoid biases during selection	Construction and operations	Human Resources Manager / Quarterly

13. INTERNAL GRIEVANCE MECHANISM

13.1 Introduction

DGDC is committed to ensuring compliance in the implementation of the ESMP policies and procedures.

The Project is committed to maintaining lasting, transparent, culturally appropriate and efficient relationships with its internal and external stakeholders, through communication and engagement measures that allow receiving, analyzing and solving any concern, doubt, question regarding the environmental and social performance of the Project in all of its activities.

Based on the foregoing, the Project has developed an Internal Grievance Mechanism with the objective of identifying and managing the potential internal nonconformities and/or complaints in a timely and effective manner.

13.1.1 Objective

Establish an Internal Grievance Mechanism so that the Project can handle internal complaints, presented by its employees and internal stakeholders (e.g. direct workers and their organizations, workers hired by third parties, contractors, subcontractors, supply chain workers), during the development of its projects by giving them an adequate response, generating satisfactory agreements and implementing compensatory and corrective actions, when necessary.

By establishing an effective Internal Grievance Mechanism, DGDC will be able to manage potential conflicts of interest by segregating the roles and responsibilities of individuals involved in the concern, suggestion or grievance management process and avoiding placing individuals in a position where conflicts could be perceived to arise.

The plan does not replace the public mechanisms of resolution of conflicts in Dominica's legal system but covers the legal process in the Grievance Mechanism to minimize the management of grievances and escalation to the judicial system.

13.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

13.1.3 Definitions

The main terms used in this document are defined below:

Table 13-1: Terms and Definitions

Term	Definition
Claim	Concern, suggestion, complaint, or grievance raised by an individual or group of individuals that need to be addressed.
Claimant	Person or group of people communicating a claim to DGDC.

Term	Definition
Concern	Requests for information or general negative perceptions unrelated to a specific Project impact or incident. If not addressed to the satisfaction of the claimant, concerns may become claims.
Conflict of interest	A conflict of interest exists where there is a divergence between the interests of an employee or contractor and his or her responsibilities or capabilities under this directive, such that an independent observer might reasonably question whether the actions of that person are influenced by his or her own interests.
Contractor	An individual or a company that has entered into a contract to provide goods or services to DGDC. The term covers parties directly contracted by DGDC and those contracted by a Contractor company, also referred to as subcontractors.
Grievance	A problem raised by an individual or group of individuals that needs to be addressed. Claims can result from either real or perceived impacts of DGDC's operations. The terms "claim" and "grievance" can be used interchangeably.
Suggestion	Proposal, insinuation, or indication that is submitted with the aim of proposing an action to improve DGDC's internal processes.
Retaliation	Any adverse action taken against a Claimant, employee, or contractor whose purpose is to frustrate the operation of this directive.
Worker Representatives	People designated from DGDC or a contractor to represent Project workers. It can be a worker, supervisor, or union representative.
Workers Grievance Mechanism	A procedure through which a grievance can be raised by a worker, assessed, investigated and responded to. It is also a framework through which workers can gain access to remedy for any adverse impacts or damage they have suffered as a result of business activities.

13.2 Roles and Responsibilities

In order to properly implement the Internal Grievance Mechanism, DGDC requires the involvement of the people listed below.

Table 13-2: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> Review and approve the Internal Grievance Mechanism.
Director of Accounts	<ul style="list-style-type: none"> Ensure the availability of resources necessary for the implementation of the Internal Grievance Mechanism.
HR Manager	<ul style="list-style-type: none"> Ensure the correct implementation of the Internal Grievance Mechanism. Communicate the Internal Grievance Mechanism among DGDC's internal stakeholders (i.e. employees, contractors and sub-contractors)
Head of ESG	<ul style="list-style-type: none"> Ensure the correct implementation of the Internal Grievance Mechanism.
Representative of DGDC's Legal Area	<ul style="list-style-type: none"> Evaluate and determine the origin of the complaints received and define the measures to be taken in response, as suitable according to what is stated in this plan.
Project Manager	<ul style="list-style-type: none"> Communicate the Internal Grievance Mechanism among DGDC's internal stakeholders (i.e. employees, contractors and sub-contractors) at a project level.

Role	Responsibilities
ESG Manager	<ul style="list-style-type: none"> ■ Help with the implementation of the Internal Grievance Mechanism. ■ Review and approve the contractor project-specific Internal Grievance Mechanism Plan. ■ Update the Internal Grievance Mechanism.
Grievance Mechanism Team	<ul style="list-style-type: none"> ■ Manage the registration and follow up on to the feedback received. ■ Share the received feedback with the Project Manager, based on what is stated in this document. ■ Sign all responses before being communicated to the employee and/or interested parties. ■ Share the feedback of subcontractors, with the appropriate contractor when applicable
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Read and be familiarized with the Internal Grievance Mechanism. ■ In case of not having a proper mechanism of their own, inform their employees working in DGDC's operations about the existence of this mechanism and monitor its implementation

13.3 Activities

The Internal Grievance Mechanism Plan establishes the guidelines for internal stakeholders to submit complaints, grievances and concerns arising from any project's activities and operations, ensuring the accessibility and effectiveness of the process.

13.3.1 Principles

DGDC recognizes that this plan has to guarantee the same level of integrity and respect for all the people involved, as well as for any type of claim. To this regard, the Project's Internal Grievance Mechanism will be:

- **Understandable and reliable** (e.g. the affected stakeholders must understand the management plan, the confidentiality of the person filing the complaint must be protected, the expected deadline for receiving a response must be shared);
- **Culturally appropriated and accessible** (e.g. complaints can be filed in the local language, the technology required to file a complaint must be of common use, illiterate people can file complaints verbally);
- **Free of charge** (e.g., raising a complaint will not have any cost);
- **Anonymity** (e.g., the claimant will have the option to remain anonymous);
- **Proportional** (e.g., to provide the appropriate level of management to address the grievance promptly);
- **Rights-Compatible** (e.g. outcomes and remedies will be in line with internationally-recognized human rights legislation and national law. No aspect of the mechanism will prevent workers from enforcing their legal rights. Workers will be protected against retaliation for having raised complaints);
- **Inclusive and non-discriminatory** (e.g. all grievances, from all workers regardless of age, ethnicity, mental or physical disability, race, religion, gender, sexual orientation or gender identity, will be accepted, reviewed and solved as needed);
- **Transparent** (e.g. every complaint will be treated seriously, and dealt with consistently and in an impartial, confidential and transparent manner. The process is transparent and provides timely feedback to the claimant).

The present plan establishes the guidelines of the Internal Grievance Mechanism and describes how each Project along with its Grievance Mechanism Team⁵ will proceed in order to adequately and satisfactorily address the possible complaints expressed by its internal stakeholders. Complaints related to affected communities and external stakeholders are covered by the External Grievance Mechanism Plan.

The Internal Grievance Mechanism aims to prevent social contingencies and conflicts with the people directly involved in the development of the Project, since it will provide, at all times, effective attention, and it has the obligation to respond to the requests of all claimants.

DGDC has established a process for the reception, registration, review, analysis, resolution and evaluation of complaints, claims and concerns to be implemented in all of its projects. The process will be documented through a physical record file and will end with the closure and written agreement on the resolution of both parties (i.e. the claimant and the Project).

13.3.2 Publication of the Mechanism

Based on the Stakeholder Engagement Plan the Project will inform internal stakeholders about the Grievance Mechanism and the communication channels to submit complaints, claims or suggestions regarding any activities related to the Project, as well as how and where to submit them. This information will be shared through:

- Direct dialogue;
- Printed material such as brochures and posters;
- Informative presentations of the Project;
- Trainings; and
- Didactic educational tools (e.g. games, videos, books, etc.).

13.3.3 Internal Grievance Mechanism Procedure

In order to ensure the proper implementation of the Internal Grievance Mechanism, and the resolution of the feedback received, this mechanism is divided into four main steps. These steps are presented in the figure below.

⁵ The Grievance Mechanism Team is led by the Head of HR and the Head of ESG.



Source: ERM, 2020.

Figure 13-1: Internal Grievance Mechanism Procedure

These steps are designed based on the recommendations of the International Finance Corporation (IFC), through which a communication channel and responsible for monitoring in each of them is designated.

13.3.3.1 *Reception and Registration*

Once the Grievance Mechanism has been presented to the internal stakeholders, any manager of the Project, Company and/or contractors will be able to personally receive any feedback, which must then be delivered to the Grievance Mechanism Team.

In addition of the feedback collected by the managers, the feedback will be submitted through the following reception channels:

- Website – To be determined prior to the start of construction and operation activities;
- Telephone – To be determined prior to the start of construction and operation activities;
- A Grievances Mailbox placed within the Project’s facilities. The mailbox’s precise location will be shared with workers during their hiring process.

Any complaint or suggestion that is entered by the aforementioned means must follow the Internal GM form, attached to the present plan as **Appendix 13-A**, which shall contain the following information:

- Place and date of the complaint or suggestion;
- Reason for the feedback, with details of the events;
- Claimant’s contact information (In case the grievance is not anonymous);
- Claimant’s proposed solution to the issue.

The process will begin with the receipt of a complaint or suggestion by the Grievance Mechanism Team and notify the claimant that the claim has been received, will be reviewed and taken for analysis. Once the suggestions and/or complaints have been received, the Grievance Mechanism Team will complete the Communication Report (**Appendix 13-B**) and the information collected regarding the complaint and/or suggestion will be captured in the Internal GM Database to register the complaints and/or suggestions.

If the claim is readily resolvable (e.g., a request that can be immediately granted or an easy solution can be applied without an investigation process), the person receiving the claim (i.e., immediate manager, human resources or worker representative) takes action to address the issue directly and records the details

in the Internal GM Database. If the claim subject is considered sensitive by the claimant (e.g., in cases regarding abuse, sexual harassment, or other forms of gender-based violence), a special point of contact with adequate training will be provided. The claimant will have the option to talk to a point person of their same gender, if requested.

Claims will not be applicable in cases when:

1. It is not directly related to DGDC, its contractors, or subcontractors;
2. It is out of DGDC's influence;
3. Its nature exceeds the scope of the present Internal Grievance Mechanism;
4. The claimant has no standing to file; and/or
5. There are other formal mechanisms/institutions or community procedures more appropriate to address the issue.

When the claim is classified as **non-applicable** following the above criteria, DGDC will clearly communicate the reasons why it cannot be considered to the claimant, and when possible, DGDC will provide information to help them redirect their claim to the right institution or party.

The Internal Grievance Database is updated weekly to reflect the current state of the claim until the claim has been resolved according to the claimant. Reception of the claim will be acknowledged within three (3) days after the claim is received. If an investigation is needed, this will take up to 15 days (low risk claims), up to 10 days (medium risk claims) and 5 days (high risk claims).

The Project will provide a means by which all workers will be able to raise **anonymous complaints**. This gives the most vulnerable workers confidence that they will not be retaliated against for raising concerns, and can be fundamental to shifting power dynamics in the workplace. Therefore, in case of an anonymous case, the resolution will be published on a visible and accessible notice board on site and communicated in regular staff meetings.

13.3.3.2 *Review, Analysis and Investigation*

Once the complaints have been filed, the review, analysis and investigation process will unfold as follows:

1. The Grievance Mechanism Team will collect on a weekly basis the complaints presented, whether submitted physically or via website, and will review the nature of the complaint, as well as the company's departments potentially involved;
2. The Grievance Mechanism Team will make an initial assessment of severity in coordination with the H&S Manager, if necessary. The grievances will be classified in four categories:
 - a. **Non-Admissible** (e.g. claims that are not directly related to the Project, its contractors or subcontractors, out of DGDC's influence);
 - b. **Low Risk** (e.g. claims that do not require resolution per se, but instead only require information or a certain clarification to be provided to the claimant. If there are recurring complaints that have been previously received and addressed by the Project, DGDC will reconsider elevating the importance of the complaint, as this might be a sign that the response to the grievance has been insufficient or inadequate);
 - c. **Medium Risk** (e.g. claims that require resolution and are related to minor risks associated with health, the environment, construction, transportation, and contractor and subcontractor personnel. Although important, they do not pose an immediate risk); and

- d. **High Risk** (e.g. claims related to the security and safety of Project personnel and community stakeholders, as well of those that, according to criteria of the Human Resources team, require immediate response as the claim poses an immediate major health and safety risk or a risk to an individual, to a large or small group or several groups of stakeholders. This includes claims regarding illegal and abusive activities).
3. The HR Manager will prepare the Communication Report, that includes the information listed below:
 - a. Internal tracking folio number provided to the claimant;
 - b. Type of feedback,
 - c. Area potentially involved;
 - d. Claimant's information (In case the grievance is not anonymous);
 - e. Date the complaint or suggestion was originated;
 - f. Grievance Risk Category (Low, Medium or High);
 - g. Brief description of the complaint or suggestion;
 - h. Area responsible for monitoring and solution;
 - i. Recommended solution;
 - j. Term of resolution.
 4. Once the complaint, claim or concern has been reviewed, the investigation must be carried out in the first instance by a member of the Grievance Mechanism Team. In case the feedback transcends and involves more areas of the Project, the suggestions and/or complaints will also be channeled to the Project Manager and the HR Manager, as appropriate, to coordinate resolution with the departments involved, depending on the scope of each, and to determine the actions to follow.

Regardless of the categorization of the claim, the claimant must always be informed that her or his grievance has been received and is being investigated. The answer must be given in written and/or verbal form, in a clear and precise language, preferably respecting the claimant's language. In cases where the complaint is anonymous, the response will be published in the same way in which the complaint was submitted (through the website or in the module). The deadline for the resolution of a complaint or claim is according to the categories shown in the following table.
 5. The evaluation of each complaint claim or concern must be in accordance with the following categories.

Table 13-3: Timeframe per Claim Category

Claim Category	Responsibilities	Response Time
Non-Admissible	Grievance Mechanism Team notifies the claimant	These suggestions and/or complaints will be communicated within fifteen (15) business days once the categorization is done.
Low Risk	The Manager of the area responsible for the resolution receives and follow up the complaint.	These suggestions and/or complaints will be addressed and answered in an average of ten (10) business days. If the complaint could not be resolved within this timeframe for reasons beyond the Project, the claimant will be notified and the time of response will be determined, considering a maximum period of three (3) months.

Claim Category	Responsibilities	Response Time
Medium Risk	The Manager of the area responsible for the resolution receives and attends the complaint.	<p>The response will be carried out within an average of five (5) days after categorizing the complaint or concern, indicating that the resolution period will be of fifteen (15) business days from the complaint's registration.</p> <p>If the complaint could not be resolved within this timeframe for reasons beyond the Project, the applicant will be notified and the time of response will be determined, considering a maximum period of three (3) months.</p>
High Risk	<p>The Manager of the area responsible for the resolution receives and responds to the complaint immediately and communicates it to the Project Manager via email/phone call.</p> <p>Once registered and communicated internally, the ESG Manager will proceed to provide support for the follow-up and resolution of the complaint, collectively with the Manager of the responsible area and the Project Manager.</p>	<p>The response time must be immediate (within 24 hours of its submission)</p> <p>In the event that, for reasons beyond the Project, the complaint could not be resolved within this timeframe, the claimant will be notified, and the time of response will be determined on a case-by-case basis. However, the resolution period will not be longer than five (5) days.</p>

Source: ERM, 2020.

In high-risk situations, where there is a possibility of serious danger (e.g., death, sexual harassment), DGDC will consider involving other member teams to weigh in on the resolution strategy. In these type of cases, an alternative timeline will be established for addressing and involving third parties as needed, such as police and hospitals. The Project will always protect the confidentiality of the claimant. The special procedure for High Risk Claims is described below.

1. The claim enters an expedited process for investigation and resolution by HR and if applicable other senior management, such as the H&S Manager, when appropriate.
2. DGDC initiates the investigation immediately and coordinates with local authorities to appropriately address the matter for claims related to allegations of illegal or abusive acts.
3. HR meets the claimant to gather additional information as necessary. Subsequently, he or she investigates the claim (e.g., meets with members of the security team involved in the claim), develops, and implements corrective actions in collaboration with other project staff, as necessary.
4. If both the HR staff and other staff involved in the resolution of the claim are all the same gender, and the claimant prefers to speak to a person of his or her same gender, DGDC will facilitate this request. This option will be disseminated when disclosing the procedure. If additional investigations are needed, these are promptly undertaken.

If the person responsible of the claim is not able to obtain a resolution within 5 days of the reception of the claim, he or she submits the claim to Human Resources, who notifies and seeks advice from the H&S Manager.

If the H&S Manager and Human Resources do not reach an agreement on a resolution within the following 5 days, Human Resources arranges meetings and discussions with relevant higher hierarchy personnel and the claimant, as well as other relevant departments, to agree on a final solution.

Before the final resolution is issued, the agreed resolution will be reviewed by the claimant, or his or her worker representative, and will confirm his or her agreement with the solution proposed.

13.3.3.3 *Resolution*

Once the complaints have been categorized and reviewed, the resolution and closure process will unfold as follows:

1. The first step for the resolution is the determination of the timeframe (considering the periods defined in the Table above) and its inclusion in the registration file previously elaborated.
2. The complaint or claim will be discussed by the managers of the areas involved. However, if a Manager is directly involved in the grievance, that person cannot play a role in the Internal Grievance Mechanism process in order to prevent conflicts of interest. In the case of complaints related to allegations of illegal or abusive acts, the Project will immediately initiate the investigation to adequately address the matter. Based on the investigation, the complaint may or may not proceed.
3. Depending on the risk category, the approach will be defined. The management of the responsible areas, together with a representative of the Legal Area will evaluate and determine the origin of the complaint and define the measures to be taken in response. The ESG Manager must sign all responses before they are communicated to the employee and/or interested parties.
4. If the complaint is not admissible, the claimant will be notified.
5. The Grievance Mechanism Team and the Project Manager will have performed an analysis of all the viable resolutions, seeking to, at all times, provide solutions that respond to the claimant, from a position of dialogue and respect. A complaint will be dismissed only when all the instances of solution have been exhausted, explaining in writing to the claimant, in a clear and indubitable manner, the reasons for the refusal on the resolution of the complaint.
6. All documentation issued during the process by the company to interested parties must be sent by email or written notification. In any case, the answer must have the corresponding record (the folio of complaint or suggestion) and will be properly archived as part of the process.

13.3.3.4 *Right to Appeal*

A worker who is not satisfied with the procedure or resolution can contest DGDC's decision. The claimant will have a maximum period of fifteen (15) business days to express any disagreement with the response and appeal it. Once the deadline has elapsed and there are no new grounds for complaint, the process will be considered closed.

In the event that a claimant wishes to challenge/appeal DGDC's decision or propose a counter offer, the In-Country Director and the Project Director will decide whether DGDC can resolve the dispute or it is necessary to involve a third party (e.g. a mediator, technical expert, local authority, or ombudsman) to reach an agreement between the parties and resolve the dispute. The claimant will always have the right to seek other legal or administrative resources. The last resort will be the national judicial process.

When a resolution agreement is established, both parties, the Human Resources Manager, acting as the representative of DGDC and the claimant, will sign it in writing. Once the solution is implemented, both parties in recognition of compliance with the agreement will sign a compliance agreement again.

13.3.3.5 Evaluation and Follow Up

It will be the responsibility of the Grievance Mechanism Team to follow up on all responses to suggestions and/or complaints in written and/or verbal form, especially those of medium and high priority, so as to confirm that the response given to the interest group was adequate, given the circumstances and criteria applicable at the time of filing the complaint. The Internal GM Database will be used to follow up each claim until it is resolved and closed.

13.4 Confidentiality and Protection from Retaliation

The Project is committed to protecting the identity of claimants and anyone else involved in the claim, and to handling personal information in accordance with legal requirements. This duty extends to all employees and representatives of DGDC and its contractors who participate in the Internal Grievance Mechanism process.

Information about a claim is shared within the company on a need-to-know basis and only to the extent necessary to complete the steps in this directive. DGDC will not share personal information with third parties unless required by law or authorized by the claimant.

When a claim relates to a specific DGDC or contractor employee, that person cannot play a role in the Internal Grievance Mechanism process in order to prevent conflicts of interest.

DGDC does not tolerate retaliation against claimants, be they an employee or contractor. When concerns about retaliation are raised, Human Resources is responsible for leading an investigation into the alleged retaliation under DGDC’s Human Resources Policy and Code of Conduct.

13.5 Documentation and Monitoring

Once every two months, the Grievance Mechanism Team will send the Internal GM Database to the Project Manager with information on the feedback received through a consolidated report showing the status of each claim and its indicators.

This plan will be monitored continuously and is designed to facilitate the integration of lessons learned during its execution. The Project will be able to respond adequately to situations as soon as they develop.

The Internal Grievance Mechanism Plan will be reviewed annually however, if required, the mechanism could be updated as necessary. It will also ensure that contractors update their procedures at least once a year.

13.6 Key Performance Indicators

The table below present the key performance indicators that will evaluate the implementation of this plan:

Table 13-4: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Method/Tool / Frequency
GM attainment	DGDC will review the Internal Grievance Database, including complaints closed and those	100% of grievances resolved in a timely manner	Internal Grievance Mechanism Database

Impact	Indicator	Performance Goals/ KPIs	Method/Tool / Frequency
	unresolved. Number of grievances received per month versus number of grievances resolved.		and Human Resources Manager / Quarterly
GM time efficiency	DGDC will review the Internal Grievance Database, especially the number of days between the grievances submission until its resolution and closure to calculate the average length of time needed to resolve grievances.	Low risk grievances: Max. 10 days Medium risk grievances: Max. 5 days High-risk grievances: Max. 24 hours	Internal Grievance Mechanism Database and Human Resources Manager / Quarterly
GM Focus/ Risk Areas	DGDC will review the Internal Grievance Database and if necessary talk to managers of technical areas or departments, to breakdown the grievances topics (e.g. health, safety, etc.) and grievance source	Resolve 100% of grievances from all sources and about all topics. Disseminate information regarding the different solutions when there are recurrent complaints in order to decrease recurrent grievances.	Human Resources Manager in coordination with contractors / Quarterly
Method of grievance reporting	DGDC will review the Internal Grievance Database and engage with workers to check the use and success of the different grievance reporting methods (e.g., number of grievances received by phone, at the office, website, and boxes).	100% of reporting methods will be functional and accessible at all times.	Human Resources Manager through direct interviews with workers / Quarterly
GM dissemination	DGDC will monitor all GM informational documents, meetings, and events where the GM was disclosed and explained.	GM dissemination of information in at least 70% of events and regular meetings with staff, including contractors and subcontractors.	Human Resources Manager Records (trainings, meetings, orientation sessions, etc.) / Quarterly

14. COMMUNITY HEALTH AND SAFETY MANAGEMENT PLAN

14.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the implementation of the Environmental and Social Management Plans (ESMP) policies and procedures.

To promote its projects alignment to best international practices, DGDC acknowledges that health and safety measures are an essential part of the management of any project, in order to ensure the wellbeing of the stakeholders (e.g. communities) directly and indirectly involved in its activities. Additionally, DGDC recognizes that the development of its operations, as well as the equipment and infrastructure of a Project, can increase the chances of the neighboring communities of being exposed to potential risks and impacts.

DGDC has adopted risk prevention as one of its main concerns and, through the Community Health and Safety Management Plan, seeks to avoid or minimize the potential risks and impacts to health and community safety that may result from activities related to any of its projects during the construction and operations phase, specially focusing on vulnerable groups.

14.1.1 Objective

The objective of this plan is to establish the necessary mechanisms to prevent the occurrence of incidents and accidents related to the Project that could affect neighboring communities during the different phases of the Project. More specifically, this plan intends to present the appropriate measures to respond to:

- Changes in the health of affected communities, including exposure to disease or changes in the availability and quality of water sources;
- Changes in livelihoods and income generation opportunities that affect the affected communities' access to social infrastructure;
- Changes in the security of the affected communities related to emergencies, unplanned events, crime and conflict; and
- Ensure that the safeguarding of personnel and property is carried out in a legitimate manner that avoids or limits risks to the community's safety and security.

14.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

The geographical scope is described by the Project Area of Influence (AOI), which comprises two parts:

- The physical footprint of the project, comprising the area occupied by direct components and Associated Facilities (Area of Direct Influence, ADI). Direct components are centered on the Project's parcel, well pads, transmission line route, and transportation routes to and from the site.
- The ADI is considered as the area that could be directly impacted; however, the Project will also have implications for employment, the economy, planning, and service provision in the whole of the island of Dominica. Therefore, the entire island of Dominica will be considered as the Area of Indirect Influence (AII).

14.2 Roles and Responsibilities

In order to properly implement the Community Health and Safety Plan, DGDC requires the involvement of the people listed below.

Table 14-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> Be familiarized, review and approve the Community Health and Safety Plan.
Director of Accounts	<ul style="list-style-type: none"> Ensure the availability of resources necessary for the implementation of the Community Health and Safety Plan.
Project Manager	<ul style="list-style-type: none"> Be familiarized with, review and update as necessary the Community Health and Safety Plan.
ESG Manager	<ul style="list-style-type: none"> Be familiarized and implement the Community Health and Safety Plan. Review, evaluate and verify the CHS management plans. Review and approve the contractor project-specific Community Health and Safety Plan. Update the Community Health and Safety Plan.
H&S Manager	<ul style="list-style-type: none"> Review, evaluate and verify the CHS management plans. Assure the development of an Emergency Preparedness and Response Plan for each Project Present, alongside the Community Liaison Officer, a monitoring report to the Project Manager.
Community Liaison Officer (CLO)	<ul style="list-style-type: none"> Coordinate and supervise the communication of information activities regarding this plan to the affected communities. Present, alongside the H&S Manager, a monitoring report to the Project Manager.
Contractor Company	<ul style="list-style-type: none"> Develop a project-specific Stakeholder mapping Plan aligned with the Community Health and Safety Plan.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> Read and be familiarized with the Community Health and Safety Plan. Develop a project-specific Community Health and Safety Plan.

14.3 Activities

This plan describes the actions that need to be taken to avoid or manage potential impacts associated with Community Health and Safety (CHS) issues, which may arise from activities related to the Project. DGDC will establish preventive and control measures in line with international best practices, such as the International Finance Corporation (IFC) Performance Standards.

14.3.1 Health and Safety Risk Identification Associated to Affected Communities

Prior to starting operations, the affected communities within the Project Area of Influence must be identified. Likewise, stakeholders will also be identified through the Stakeholder Mapping procedure (see Stakeholder Engagement Plan). At the same time, the risks associated with CHS will be determined and evaluated considering the planned and unplanned events associated with all stages of the Project. This prefeasibility assessment is the basis for defining the mitigation measures of the identified impacts and must be considered as a minimum:

- Water quality and availability;

- H₂S levels;
- Increase in local population due to the migration of the Project's workers;
- Community exposure to air, noise and water pollution;
- Design and safety of infrastructure and equipment;
- Road safety;
- Handling, storage and transport of hazardous materials and waste;
- Availability and quality of ecosystem services;
- Community exposure to communicable and non-communicable diseases, as well as vector control;
- Security personnel; and
- Emergency preparedness and response.

A specific plan will be developed to mitigate each of these impacts. The affected communities will be consulted during the aforementioned assessment process to ensure a collaborative perspective and common understanding. Likewise, stakeholder engagement activities will be conducted to inform affected communities and other external stakeholders on the potential risks identified and prevent confusion, rumors or misunderstandings. This is done through the Stakeholder Engagement Plan.

14.3.2 Emergency and Preparedness Response Plan

The H&S Manager must assure that DGDC's Emergency Preparedness and Response Management Plan is implemented by the Project, in all its facilities, as well as by all the contractors and subcontractors. The Disaster Risk and Emergency Management Plan along with the Occupational Health and Safety Plan, consider all the possible emergency scenarios that could have an impact on the CHS of the Project's area of influence. These Plans also consider the roles and responsibilities for implementing the Plans, as well as the equipment, resources and skills needed to effectively apply it. All scenarios identified during the prefeasibility assessment will be tested and documented on a regular basis.

14.3.3 Community Health and Safety Measures

A series of Project specific plans will be developed based on the identification and environmental and social prefeasibility assessment of CHS and the ESMP (e.g. Traffic Management Plan, Noise Monitoring Plan,), with the aim of ensuring the safety of communities within the Project Area of Influence; these plans will include the necessary controls to manage the risks. The ESG Manager along with the H&S Manager will review, evaluate and verify the development of this plan.

DGDC will select and implement the physical, engineering, and administrative controls. The responsibilities of these plans must be communicated and documented.

CHS management measures will be reviewed, evaluated and verified by the H&S Manager of the Project and then presented to the ESG Manager, who will give final approval before they can be implemented.

14.3.4 Communication of Information

The potential Project affected communities, shall be informed in a culturally appropriated manner on the specific content of this Plan and the emergency scenarios and emergency response actions, as well as of the rest of DGDC' ESMP procedures that directly involve them (e.g. Stakeholder Engagement Plan and the External Grievance Mechanism Plan). The CHS Plan will be communicated alongside the Stakeholder Engagement Plan; this process will be coordinated by the Community Liaison Officer (CLO).

The information will include the type and nature of the risks identified, the actions proposed to avoid and manage those risks, as well as the monitoring activities planned. When evaluating the communication and consultation activity, DGDC will consider within the communication its employees, contractors, affected communities, and other relevant stakeholders.

The affected communities shall have the opportunity to express their views on the identified risks, impacts, opportunities and mitigation measures of the company. DGDC will consider such views and seek to respond to them appropriately.

The CLO will gather the requests, concerns and questions of the affected communities and will ensure that they receive an adequate response in accordance with the External Grievance Mechanism Plan. Specific activities and measures are included below regarding the communication and disclosure of information about health and safety to each relevant stakeholder group.

14.3.4.1 Communication to the Affected Communities

DGDC will communicate relevant health and safety information to communities that may be affected by potential emergency or health and safety situations generated at DGDC facilities or due to their activities. The communication aims at making them aware on what to do in the event of an emergency and the importance of emergency preparedness and response.

DGDC will distribute the Community Health and Safety Management Plan to the communities in the Project's area of influence through different channels:

- DGDC's website;
- Printed copies will be made available at the Community Centre;
- DGDC's Newsletter for the communities/ radio programs/ etc. (for more information about the Newsletter, see the Stakeholder Engagement Plan).

Information will be disclosed before emergency drills that involve the community, these will be diffused through the same channels named above. Special emphasis will be put in the difference between a drill and a real emergency. Notifications of drills will be made in a timely manner to the communities.

DGDC plans to work in conjunction with industry partners, government agencies and community groups to develop programs and/or campaigns that enhance the communities' awareness of safety concerns that can be directly attributed to the Project.

Programs/initiatives may include, but are not limited to, addressing the issues of:

- Road safety;
- Community/ allied health infrastructure;
- Support for community services;
- Community health awareness and promotion; and
- Quality of life issues.

In addition, the Project will monitor the community grievance mechanism, which allows all levels of the community and stakeholders to provide feedback and/or raise concerns about the Project, including health and safety concerns. To achieve this DGDC has an External Grievance Mechanism Management Plan. The Project is committed to providing adequate procedures for the community to provide feedback on the Project and will maintain a database register, which will provide information for future decision making, stakeholder engagement and reporting.

The Project will measure, audit and publicly report Health, Safety, Security and Environment (HSSE) performance and maintain open dialogue with stakeholder groups and with communities where DGDC operates.

14.3.4.2 *Communication to Local Authorities, Governmental Departments and External Resources*

DGDC will share the final Community Health and Safety Plan and the emergency plans with the local governmental organizations and external resources that have roles in emergency response scenarios and with authorities required by applicable local regulations.

DGDC will communicate frequently with local emergency response resources, at least once every month during construction and once every quarter during operations, to maintain them informed about the Project's progress and collaborate in drills when necessary.

14.3.4.3 *Communication to Workers, Contractors and Subcontractors*

The ESG Manager ensures that the Community Health and Safety Plan, as well as the other emergency response and security plans are provided to all contractors. Employees and contractor employees are provided with the applicable plans and notified regarding their roles and responsibilities in the event of an emergency that might affect the community through training. In addition, every member of the Emergency Response Teams is trained in his or her responsibilities and DGDC will ensure that they have an adequate level of competency to carry out these responsibilities in the event of an emergency.

The specific training requirements for personnel and contractors consider the following:

- Training and simulations address the requirements of authorities and any existing mutual aid agreements;
- Relevant personnel receive training after significant updates or changes to this plan;
- Refresher training is conducted at a predetermined frequency for all members of the emergency response organization (typically annually); and

Each of the emergency response position alternates also attend the full training program.

14.3.4.4 *Communication to Visitors*

Visitors are provided with basic safety instructions and information on evacuation routes before entering a DGDC facility. If a drill is planned that day, they will be informed about it. Assembly points are clearly identified at the facility. In addition, they are accompanied at all times while at a DGDC facility.

14.3.5 Training

The Project will ensure that personnel responsible for the execution of tasks and requirements in this Plan are competent on the basis of education, training, and experience. Health and safety trainings will be carried out through community focal groups at least once a quarter.

Project training activities associated with the Community Health and Safety Management Plan shall be appropriately documented by a training matrix/plan and records of training undertaken. Training will include, but not be limited to:

- COVID-19 prevention awareness;
- STI and HIV/AIDS prevention and awareness training for all employees;
- Respiratory illness and infectious disease management;

- Vector-borne disease awareness including malaria and dengue;
- Speed restrictions in populated areas, safe driving in rural areas, safe driving in dusty environments, safe driving to avoid wildlife, defensive driving and basic first aid;
- Benefits of vaccinations and disease prevention;
- Wildlife Management; and
- Adverse impacts of drug and alcohol usage.

14.4 Documentation and Monitoring

Once every two months, the H&S Manager and the Community Liaison Officer will collectively share with the Project Manager a consolidated report showing the status of the indicators presented below.

This plan will be monitored continuously and is designed to facilitate the integration of lessons learned during its execution. The Project will be able to respond adequately to situations as soon as they develop.

14.5 Key Performance Indicators

The Community Health and Safety Management Plan is to be reviewed on a six-month basis for the initial two years and then annually or as necessary in consultation with key stakeholders.

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 14-2: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
Communities Health and Safety	Number of incidents/accidents or emergencies affecting the community per year	Zero incidents, accidents or emergencies	Construction and operations	Accident and Incident Recording, Reporting and Investigation System / Yearly
	Number of grievances from the community related to health and safety issues	100% grievances addressed and solved in a timely manner related to health and safety issues	Construction and operations	DGDC Community Liaison Officer in collaboration with the ESG Manager. External Grievance Mechanism database log. / Quarterly
Health and Safety Trainings	Number of community members trained in health and safety topics and focused groups per year	One training/ focus group with community members 15 days before construction begins. One health and safety training for community members focused on emergency scenarios and road safety near the Project, 15 days before construction begins	15 days before construction Once every six months during construction and operations	DGDC Human Resources in coordination with Contractors / Yearly

	Number of DGDC's workers and contractors trained in: Community Health and Safety, Code of Conduct, Fit for Work and Drug and Alcohol policies, and Emergency Trainings	100% of trained DGDC workers, contractors and subcontractors	Construction and operations	DGDC Human Resources Training Records / Yearly
Disclosure of Information	Number and topics of health and safety information disclosed for the communities in the Project's area of influence	At least once per quarter during construction and once per six months during operations	Construction and operations	Newsletter for the Communities / Quarterly during construction, bi-annually during operations
	Health and Safety posters and/or flyers available at DGDC's Community Relations Office	Printed copies available at all times regarding health and safety measures for the community	Construction and operations	Community Liaison Officer / Quarterly

15. EXTERNAL GRIEVANCE MECHANISM

15.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the Environmental and Social Management Plans (ESMP) policies and procedures.

The Project is committed to maintaining lasting, transparent, culturally appropriate and efficient relationships with its internal and external stakeholders, through communication and engagement measures that allow receiving, analyzing and solving any concern, doubt, question regarding the environmental and social performance of the Project in all of its activities. The External Grievance Mechanism is an instrument to guarantee transparency and commitment between the Project and the local population.

Based on the foregoing, the Project has developed an External Grievance Mechanism with the objective of identifying and managing the potential external nonconformities (e.g. from the affected communities) and/or complaints in a timely and effective manner.

15.1.1 Objective

Establish an External Grievance Mechanism so that the Project can handle external complaints, presented by stakeholders outside the Project (e.g. affected communities, external stakeholders, interested groups, etc.), during the development of its projects by giving them an adequate response, generating satisfactory agreements and implementing compensatory and corrective actions, when necessary.

By establishing an effective External Grievance Mechanism, DGDC will be able to manage potential conflicts of interest by segregating the roles and responsibilities of individuals involved in the concern, suggestion or grievance management process and avoiding placing individuals in a position where conflicts could be perceived to arise. The Project recognizes that unforeseen impacts may occur, and that the maintenance of an open line of communication with the communities and/or those potentially affected by the Project is important to maintain transparent and cordial relations. In addition, international standards require the establishment of an External Grievance Mechanism in order to address the interested parties' concerns.

As a general policy, DGDC will work proactively towards preventing grievances through the implementation of mitigation measures (as identified by the ESIA) and liaising with the community. These activities are designed to anticipate and address potential issues before they become grievances. This will be the responsibility of the Project Manager and the Community Liaison Officer (CLO).

The sections below consider types of grievances that may arise, confidentiality and anonymity, and the Project's grievance resolution process.

The grievance mechanism covers the various aspects of the Project, including:

- the Project in general, including planning, construction and operation;
- the process of environmental impact assessment; and
- the compensation and resettlement processes.

Each affected person is free to register a grievance, in accordance with procedures specified below. The grievance process focuses on first identifying whether the grievance can be addressed through additional communication between the complainant and members of the Project Team, or by providing additional information to the complainant. If the grievance cannot be resolved internally, the Project Team will then seek to resolve the grievance through mediation by local authorities, and finally, if a resolution cannot be reached, judicial appeal. The procedure does not replace the public mechanisms of resolution of conflicts

in Dominica's legal system but covers the legal process in the Grievance Mechanism to minimize the management of grievances and escalation to the judicial system.

15.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that reception complaints are aligned to international best practices.

15.1.3 Definitions

The main terms used in this document are defined below:

Table 15-1: Terms and Definitions

Term	Definition
Claim	Concern, suggestion, complaint, or grievance raised by an individual or group of individuals that need to be addressed.
Claimant	Person or group of people communicating a claim to DGDC.
Concern	Requests for information or general negative perceptions unrelated to a specific Project impact or incident. If not addressed to the satisfaction of the claimant, concerns may become claims.
Conflict of interest	A conflict of interest exists where there is a divergence between the interests of an employee or contractor and his or her responsibilities or capabilities under this directive, such that an independent observer might reasonably question whether the actions of that person are influenced by his or her own interests.
Contractor	An individual or a company that has entered into a contract to provide goods or services to DGDC. The term covers parties directly contracted by DGDC and those contracted by a Contractor company, also referred to as subcontractors.
Grievance	An actual or perceived problem raised by an individual or group of individuals that that might give grounds for complaint and needs to be addressed. Claims can result from either real or perceived impacts of DGDC's operations. The terms "claim" and "grievance" can be used interchangeably.
Suggestion	Proposal, insinuation, or indication that is submitted with the aim of proposing an action to improve DGDC's internal processes.
Retaliation	Any adverse action taken against a Claimant, employee, or contractor whose purpose is to frustrate the operation of this directive.
External Grievance Mechanism	A procedure through which a grievance can be raised by a member of the community, assessed, investigated and responded to. It is also a framework through which workers can gain access to remedy for any adverse impacts or damage they have suffered as a result of business activities.

15.2 Roles and Responsibilities

In order to properly implement the External Grievance Mechanism, DGDC requires the involvement of the people listed below.

Table 15-2: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> ■ Review and approve the External Grievance Mechanism.
Director of Accounts	<ul style="list-style-type: none"> ■ Ensure the availability of resources necessary for the implementation of the External Grievance Mechanism.
Head of ESG	<ul style="list-style-type: none"> ■ Ensure the correct implementation of the External Grievance Mechanism.
Representative of DGDC's Legal Area	<ul style="list-style-type: none"> ■ Evaluate and determine the origin of the complaints received and define the measures to be taken in response, as suitable according to what is stated in this plan.
Project Manager	<ul style="list-style-type: none"> ■ Be familiarized with the External Grievance Mechanism and provide the necessary resources to ensure its proper implementation.
ESG Manager	<ul style="list-style-type: none"> ■ Ensure the correct implementation of the External Grievance Mechanism. ■ Review and approve the contractor project-specific External Grievance Mechanism. ■ Update the External Grievance Mechanism.
Grievance Mechanism Team	<ul style="list-style-type: none"> ■ Be familiarized and disseminate the External Grievance Mechanism among external stakeholders. ■ Prepare the Communication Report, and follow up on the feedback received. ■ Share the External Grievance Mechanism Database with the Project Manager. ■ Share the received feedback with the Project Manager.
Community Liaison Officer (CLO)	<ul style="list-style-type: none"> ■ Collect on a weekly basis the complaints presented, whether submitted physically or via website. ■ Review the nature of the complaint, as well as the company's departments potentially involved. ■ Solve, as immediate as possible the feedback received, if there are conditions to do so. ■ Keep a record of the solutions that were given for documentation, monitoring or verification of the solution applied.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Read and be familiarized with the External Grievance Mechanism.

15.3 Activities

The External Grievance Mechanism Plan establishes the guidelines for external stakeholders to submit complaints, grievances and concerns arising from any project's activities and operations, ensuring the accessibility and effectiveness of the process.

15.3.1 Principles

DGDC recognizes that this plan has to guarantee the same level of integrity and respect for all the people involved, as well as for any type of claim. To this regard, the Project's External Grievance Mechanism will be:

- **Understandable and reliable** (e.g. the affected stakeholders must understand the procedure, the confidentiality of the person filing the complaint must be protected, the expected deadline for receiving a response must be shared);

- **Culturally appropriated and accessible** (e.g. complaints can be filed in the local language, the technology required to file a complaint must be of common use, illiterate people can file complaints verbally);
- **Free of charge** (e.g. raising a complaint will not have any cost);
- **Anonymity** (e.g. the claimant will have the option to remain anonymous);
- **Proportional** (e.g. to provide the appropriate level of management to address the grievance promptly);
- **Rights-Compatible** (e.g. outcomes and remedies will be in line with internationally recognized human rights legislation and national law. No aspect of the mechanism will prevent community members from enforcing their legal rights. Community members will be protected against retaliation for having raised complaints);
- **Inclusive and non-discriminatory** (e.g. all grievances, from all community members regardless of age, ethnicity, mental or physical disability, race, religion, gender, sexual orientation or gender identity, will be accepted, reviewed and solved as needed);
- **Transparent** (e.g. every complaint will be treated seriously, and dealt with consistently and in an impartial, confidential and transparent manner. The process is transparent and provides timely feedback to the claimant).

The present plan establishes the guidelines of the External Grievance Mechanism and describes how the Project along with its CLO will proceed in order to adequately and satisfactorily address the possible complaints expressed by the community or other external stakeholders. Complaints related to internal stakeholders (e.g. workers, contractors, subcontractors, etc.) are covered on the Internal Grievance Mechanism Management Plan.

The External Grievance Mechanism aims to prevent social contingencies and conflicts with the people that might be affected by the development of the Project, since it will provide, at all times, effective attention, and it has the obligation to respond to the requests of all claimants.

DGDC has established a process for the reception, registration, review, analysis, resolution and evaluation of complaints, claims and concerns to be implemented in all of its projects. The process will be documented through a physical record file and will end with the closure and written agreement on the resolution of both parties (i.e. the claimant and the Project).

15.3.2 Publication of the Mechanism

Based on the Stakeholder Engagement Plan, the Project Manager and CLO will inform the affected communities and other external stakeholders about the Grievance Mechanism and the communication channels to submit complaints, claims or suggestions regarding any activities related to the Project, as well as how and where to submit them. This information will be shared through:

- Direct dialogue;
- Distribution of printed material such as brochures and posters, which will be proposed by the ESG team and reviewed by the Marketing and Communication management of DGDC;
- Available information at the Project's Community Relations Office;
- Press and media;
- Didactic educational tools (e.g. games, videos, books, etc.).

15.3.3 Grievance Mechanism Procedure

In order to ensure the proper implementation of the External Grievance Mechanism, and the resolution of the feedback received, this mechanism is divided into four main steps. These steps are presented in the figure below.



Source: ERM, 2020

Figure 15-1: General Grievance Mechanism Procedure

These steps are designed based on the recommendations of the International Finance Corporation (IFC), through which a communication channel and responsible for monitoring in each of them is designated.

15.3.3.1 Reception and Registration

The CLO will manage the External Grievance Mechanism. The external claimants will be able to submit their grievances through the following reception channels:

- Website – <https://www.geodominica.dm/>

Telephone and emails. The points of contact for grievances and comments are:

Table 15-3: Grievance Contacts

Name:	Allan Toussaint
Address:	Floors 1&2, 18 Kennedy Avenue, Roseau
Email:	Allan.toussaint@geodominica.com
Telephone Number:	(767) 448 6178/79; 275 7392
Name:	Lyn John-Fontenelle
Address:	Floors 1&2, 18 Kennedy Avenue, Roseau
Email:	Lyn.fontenelle@geodominica.com
Telephone Number:	(767) 448 6178/79; 235 5462

- A Grievances Mailbox placed at the Community Centre. The mailbox's precise location will be shared with the community during public consultation and other disclosure of information events.

Any complaint or suggestion that is entered by the aforementioned means must follow the External GM form, attached to the present procedure as **Appendix 15-A**, which shall contain the following information:

- Place and date of the complaint or suggestion;
- Reason for the feedback, with details of the events;
- Claimant's contact information (In case the grievance is not anonymous);
- Claimant's proposed solution to the issue.

The process will begin with the receipt of a complaint or suggestion by the CLO and notify the claimant that the claim has been received, will be reviewed and taken for analysis. DGDC's grievance flow chart is provided in the figure below.




Figure 15-2: DGDC’s Grievance Flow Chart

Once the suggestions and/or complaints have been received, the CLO will complete the Communication Report (**Appendix 15-B**) and the information collected regarding the complaint and/or suggestion will be captured in the External GM Database (**Appendix 15-C**) to register the complaints and/or suggestions.

If the claim is readily resolvable (e.g., a request that can be immediately granted or an easy solution can be applied without an investigation process), the person from the CLO receiving the claim takes action to

address the issue directly and records the details in the External GM Database (**Appendix 15-C**). If the claim subject is considered sensitive by the claimant (e.g., in cases regarding abuse, sexual harassment, or other forms of gender-based violence), a special point of contact with adequate training will be provided. The claimant will have the option to talk to a point person of their same gender, if requested.

Claims will not be applicable in cases when:

1. It is not directly related to DGDC, its contractors, or subcontractors;
2. It is out of DGDC's influence;
3. Its nature exceeds the scope of the present External Grievance Mechanism;
4. The claimant has no standing to file; and/or
5. There are other formal mechanisms/institutions or community procedures more appropriate to address the issue.

When the claim is classified as **non-applicable** following the above criteria, DGDC will clearly communicate the reasons why it cannot be considered to the claimant, and when possible, DGDC will provide information to help them redirect their claim to the right institution or party.

The External Grievance Database is updated weekly to reflect the current state of the claim until the claim has been resolved according to the claimant. Reception of the claim will be acknowledged within ten (10) days after the claim is received. If an investigation is needed, this will take up to 30 days (low risk claims), up to 15 days (medium risk claims) and 5 days (high risk claims).

The Project provides a means by which all external stakeholders will be able to raise **anonymous complaints**. This gives the most vulnerable members of the affected communities, the confidence that they will not be retaliated against for raising concerns, and can be fundamental to shifting power dynamics in between the Project and the communities. Therefore, in case of an anonymous case, the resolution will be published on a visible and accessible notice board at the Community Centre.

15.3.3.2 *Review, Analysis and Investigation*

Once the complaints have been filed, the review, analysis and investigation process will unfold as follows:

1. The CLO will collect on a weekly basis the complaints presented, whether submitted physically or via website, and will review the nature of the complaint, as well as the company's departments potentially involved;
2. The CLO will make an initial assessment of severity in coordination with the H&S Manager, if necessary. The grievances will be classified in four categories:

Table 15-4: Classification of Grievances

Classification	Risk Level	Validity	Response
Non-Admissible	None	Unsubstantiated	CLO will clearly communicate the reasons why it cannot be considered to the claimant, and when possible, provide information to help them redirect their claim to the right institution or party.
Low	No or low	Unsubstantiated	CLO will conduct investigation, document findings and provide a response
Medium	Possible risk and likely a	Possible substantiation	CLO and an appropriate investigation team will conduct investigation. The Site Manager or Occupation Health and Safety Manager may decide to stop work during the

	one-off event		investigation to allow the corrective preventive actions to be determined. The CLO will provide a response.
High	Probable risk and could reoccur	Probable substantiation	CLO will get the contractor to organise a Major Investigation Team including DGDC and GoCD for prompt investigation and resolution. Work will be stopped in the affected area. The CLO will provide a response.

- a. **Non-Admissible** (e.g. claims that are no directly related to the Project, its contractors or subcontractors, out of DGDC's influence);
 - b. **Low Risk** (e.g. claims that do not require resolution per se, but instead only require information or a certain clarification to be provided to the claimant. If there are recurring complaints that have been previously received and addressed by the Project, DGDC will reconsider elevating the importance of the complaint, as this might be a sign that the response to the grievance has been insufficient or inadequate);
 - c. **Medium Risk** (e.g. claims that require resolution and are related to minor risks associated with health, the environment, construction, transportation, and external stakeholders. Although important, they do not pose an immediate risk); and
 - d. **High Risk** (e.g. claims related to the security and safety of the community stakeholders, as well of those that, according to criteria of the Community Relations team, require immediate response as the claim poses an immediate major health and safety risk or a risk to an individual, to a large or small group or several groups of stakeholders. This includes claims regarding illegal and abusive activities).
3. The CLO will prepare the Communication Report that includes the information listed below:
- a. Internal tracking folio number provided to the claimant;
 - b. Type of feedback,
 - c. Area potentially involved;
 - d. Claimant's information (In case the grievance is not anonymous);
 - e. Date the complaint or suggestion was originated;
 - f. Grievance Risk Category (Low, Medium or High);
 - g. Brief description of the complaint or suggestion;
 - h. Area responsible for monitoring and solution;
 - i. Recommended solution;
 - j. Term of resolution.

Once the claim has been reviewed, the investigation must be carried out in the first instance by the CLO. In case the feedback transcends and involves more areas of the Project, the suggestions and/or complaints will also be channeled to the Managing Director and the HR Manager, as appropriate, to coordinate resolution with the departments involved, depending on the scope of each, and to determine the actions to follow.

Regardless of the categorization of the claim, the claimant must always be informed that her or his grievance has been received and it is being investigated. The answer must be given in written and/or verbal form, in a clear and precise language, preferably respecting the claimant's language. In cases where the complaint is anonymous, the response will be published at the Community Centre. The deadline for the resolution of a complaint or claim is according to the categories is presented in the table above.

In high-risk situations, where there is a possibility of serious danger (e.g., death, sexual harassment), DGDC will consider involving other member teams to weigh in on the resolution strategy. In these type of cases, an alternative timeline will be established for addressing and involving third parties as needed, such as police and hospitals. The Project will always protect the confidentiality of the claimant. The special procedure for High Risk Claims is described below.

1. The claim enters an expedited process for investigation and resolution by the CLO and if applicable, the Major Investigation Team, when appropriate.
2. The Major Investigation Team initiates the investigation immediately and coordinates with local authorities to appropriately address the matter for claims related to allegations of illegal or abusive acts.
3. The CLO meets the claimant to gather additional information as necessary. Subsequently, he or she investigates the claim (e.g., meets with members of the security team involved in the claim), develops, and implements corrective actions in collaboration with other project staff, as necessary.
4. If both the CLO and other staff involved in the resolution of the claim are all the same gender, and the claimant prefers to speak to a person of his or her same gender, DGDC will facilitate this request. This option will be disseminated when disclosing the procedure. If additional investigations are needed, these are promptly undertaken.

The CLO will log the receipt of a comment, formally acknowledge it, track progress on its investigation and resolution, and respond in writing with feedback to the aggrieved party. They will initiate the investigation and ensure its speedy conclusion aiming to provide a response with **ten** (10) working days, unless there are exceptional circumstances. If the Project receives a large number of unsubstantiated grievances, the process will be reviewed to define instances when no response is needed.

If the person responsible of the claim is not able to obtain a resolution within 10 days of the reception of the claim, he or she submits the claim to the CLO, who notifies and seeks advice from the H&S Manager.

Where investigations are required, Project staff and outside authorities as appropriate will assist with the process. The CLO will collaborate with GoCD to identify an appropriate investigation team with the correct skills to review the issue raised and to decide whether it is Project related or whether it is more appropriately addressed by a relevant authority outside the Project.

The investigation will also aim to identify whether the incident leading to the grievance is a singular occurrence or likely to reoccur. Identifying and implementing activities, procedures, equipment and training to address and prevent reoccurrence will be part of the investigation activities. In some cases, it will be appropriate for the CLO to follow up at a later date to see if the person or organization is satisfied with the resolution or remedial actions.

Before the final resolution is issued, the agreed resolution will be reviewed by the claimant, or his or her worker representative, and will confirm his or her agreement with the solution proposed.

15.3.3.3 *Resolution*

Once the complaints have been categorized and reviewed, the resolution and closure process will unfold as follows:

1. The first step for the resolution is the determination of the timeframe and its inclusion in the registration file previously elaborated.
2. The claim will be discussed by the CLO, and if necessary, the managers of the areas involved. In the case of complaints related to allegations of illegal or abusive acts, the Project will immediately

initiate the investigation to adequately address the matter. Based on the investigation, the complaint may or may not proceed.

3. Depending on the risk category, the approach will be defined. The CLO, together with a representative of the Legal Area will evaluate and determine the origin of the complaint and define the measures to be taken in response. All responses must be signed by the ESG Manager before being communicated to the employee and/or interested parties.
4. If the complaint is not admissible, the claimant will be notified.
5. The CLO and the Project Manager will have performed an analysis of all the viable resolutions, seeking to, at all times, provide solutions that respond to the claimant, from a position of dialogue and respect. A complaint will be dismissed only when all the instances of solution have been exhausted, explaining in writing to the claimant, in a clear and indubitable manner, the reasons for the refusal on the resolution of the complaint.
6. All documentation issued during the process by the company to interested parties must be sent by email or written notification. In any case, the answer must have the corresponding record (the folio of complaint or suggestion) and will be properly archived as part of the process.

Right to Appeal

If an external stakeholder who is not satisfied with the procedure or resolution, she or he can contest DGDC's decision. The claimant will have a maximum period of fifteen (15) business days to express any disagreement with the response and appeal it. Once the deadline has elapsed and there are no new grounds for complaint, the process will be considered closed.

In the event that a claimant wishes to challenge/appeal DGDC's decision or propose a counter offer, the Board of Directors will decide whether DGDC can resolve the dispute or it is necessary to involve a third party (e.g. a mediator, technical expert, local authority, or ombudsman) to reach an agreement between the parties and resolve the dispute. The claimant will always have the right to seek other legal or administrative resources. The last resort will be the national judicial process.

When a resolution agreement is established, both parties, the Head of HR acting as the representative of DGDC and the claimant, will sign it in writing. Once the solution is implemented, both parties in recognition of compliance with the agreement will sign a compliance agreement again.

15.3.3.4 Evaluation and Follow Up

It will be the responsibility of the CLO to follow up on all responses to suggestions and/or complaints in written and/or verbal form, especially those of medium and high priority, so as to confirm that the response given to the interest group was adequate, given the circumstances and criteria applicable at the time of filing the complaint. The External GM Database will be used to follow up each claim until it is resolved and closed.

15.4 Confidentiality and Protection from Retaliation

The Project is committed to protecting the identity of claimants and anyone else involved in the claim, and to handling personal information in accordance with legal requirements. This duty extends to all employees and representatives of DGDC, its contractors and community members who participate in the External Grievance Mechanism process.

Information about a claim is shared within the company on a need-to-know basis and only to the extent necessary to complete the steps in this directive. DGDC will not share personal information with third parties unless required by law or authorized by the claimant.

When a claim relates to a specific DGDC or contractor employee, that person cannot play a role in the External Grievance Mechanism process in order to prevent conflicts of interest.

DGDC does not tolerate retaliation against claimants, be they an employee, contractor or external stakeholder. When concerns about retaliation are raised, Human Resources/ CLO is responsible for leading an investigation into the alleged retaliation under DGDC’s Human Resources Policy and Code of Conduct.

15.5 Documentation and Monitoring

Weekly during construction and bi-annually during operation, the CLO will send the External GM Database to the Project Manager with information on the feedback received through a consolidated report showing the status of each claim and its indicators, removing identification information to protect the confidentiality of the complainant and guaranteeing anonymity.

This plan will be monitored continuously and is designed to facilitate the integration of lessons learned during its execution. The Project will be able to respond adequately to situations as soon as they develop.

The External Grievance Mechanism Plan will be reviewed annually, however, if required, the mechanism could be updated as necessary. It will also ensure that contractors update their procedures at least once a year.

15.6 Key Performance Indicators

The table below present the key performance indicators that will evaluate the implementation of this plan:

Table 15-5: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Method/Tool/ Frequency
GM attainment	DGDC will review the External Grievance Database, including complaints closed and those unresolved. Number of grievances received per month versus number of grievances resolved.	100% of grievances resolved in a timely manner	External Grievance Mechanism Database and Community Relations Team / Quarterly
GM time efficiency	DGDC will review the External Grievance Database, especially the number of days between the grievances submission until its resolution and closure to calculate the average length of time needed to resolve grievances.	Max. 10 days	External Grievance Mechanism Database and Community Relations Team / Quarterly
GM Focus/ Risk Areas	DGDC will review the External Grievance Database and if necessary talk to the Community Relations Team to breakdown the grievances topics (e.g. health, safety, etc.) and grievance source	Resolve 100% of grievances from all sources and about all topics. Disseminate information regarding the different solutions when there are recurrent complaints in order to decrease recurrent grievances.	External Grievance Mechanism Database and Community Relations Team / Quarterly

Method of grievance reporting	DGDC will review the External Grievance Database and engage with community members to check the use and success of the different grievance reporting methods (e.g., number of grievances received by phone, at the office, website, and boxes).	100% of reporting methods will be functional and accessible at all times.	Community Relations Team / Quarterly
GM dissemination	DGDC will monitor all GM informational documents, meetings, and events where the GM was disclosed and explained to the affected communities.	GM dissemination of information in at least 70% of disclosure of information events, consultations and other activities.	Community Relations Team Records / Quarterly

16. CONTRACTOR MANAGEMENT PLAN

16.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the implementation of the Environmental and Social Management Plans (ESMP) policies and procedures.

DGDC implements technical and organizational measures to ensure all the conducted work by Contractors and Subcontractors is managed in a correct manner, in conformity with local, state and internal requirements.

16.1.1 Objective

The objective of this plan is to define the minimum requirements for contractors and subcontractors working on behalf of DGDC to minimize environmental, social, health, and safety (ESHS) risks associated with the contracted services. DGDCs own Contractor Management requirements are provided below in order to provide contractors procedures when doing their own subcontractor management.

The Contractor Management and Supervision Plan is a management tool that will be updated periodically to ensure the efficiency of contractor management.

16.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's Environmental and Social Management Plans (ESMP) policies and procedures, which are aligned with international best practices.

Contractors will use this procedure and develop it further to provide specifics on how the various requirements from the Project-specific Environmental and Social Management Plans (ESMP) will be applied on the ground. DGDC will review and approve these documents before any implementation.

16.2 Roles and Responsibilities

In order to properly implement the Contractor Management and Supervision Plan, DGDC requires the involvement of the people listed below.

Table 16-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none">■ Be familiarized, review and approve the Contractor Management and Supervision Plan.
Director of Accounts	<ul style="list-style-type: none">■ Ensure the availability of resources necessary for the implementation of the Contractor Management and Supervision Plan.
Head of ESG	<ul style="list-style-type: none">■ Assure the correct implementation of the Contractor Management and Supervision Plan
ESG Manager	<ul style="list-style-type: none">■ Assure the correct implementation of the Contractor Management and Supervision Plan■ Update the Contractor Management and Supervision Plan.■ Review and approve the contractor project-specific contractors' supervision plan.
Project Manager	<ul style="list-style-type: none">■ Implement the Contractor Management and Supervision Plan.■ Manage and record the performance of the Contractors
H&S Manager	<ul style="list-style-type: none">■ Implement the Contractor Management and Supervision Plan.

Role	Responsibilities
	<ul style="list-style-type: none"> ■ Ensure the generation of evidence and reports for compliance with the IFC PS as well as maintaining DGDC's KPIs. In addition, ensure the internal coordination to follow the Contractor Management and Supervision Plan.
Contractor Company	<ul style="list-style-type: none"> ■ Develop project-specific Plans aligned with DGDC's ESMP
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Contractor Management and Supervision Plan

16.3 Activities

The following sections explain the activities and requirements for the proper management of contractors and subcontractors.

16.3.1 Current DGDC Contractor Management Procedures

DGDC does not perform engineering and construction work in-house. Instead, the company contracts out engineering, procurement and construction work to one or more contractors. Contractor management plays a key role in DGDC's business. As of the date of this management plan, DGDC has not selected Contractors for the Project.

DGDC selects and approves its contractors, as well as product suppliers, through a pre-qualification process. Pre-qualification ensures that DGDC only works with suppliers of goods and services that are able to comply with DGDC's policies.

Contractor management can be achieved through six steps:

1. Definition of the scope of work
2. Pre-qualification of the contractor
3. Contractor selection
4. Contract award and terms establishment
5. Contractor monitoring
6. Post contract review

Collaboration between Head of EPC, ESG Manager and Project Manager is essential for the efficient implementation of these steps.

16.3.1.1 Definition of the Scope of Work

Once the project is defined, the Project Manager reviews the project description and prepares the ESHS-related requirements to be included in the tender specifications. These requirements will address ESHS needs and red flags identified during the Project design process. As appropriate, this will also reflect requirements found in project-related and authorizations (e.g., licenses and permits).

Special design requirements to avoid or mitigate potential impacts must also be included in the ESHS requirements to be disclosed to the contractors in the tender specifications.

If the bidders have any questions before submitting the proposal, the DGDC management may meet with the bidder to provide guidance on how to comply with ESHS requirements. When considered appropriate, the bidders are given the opportunity to address gaps identified in their proposals. The Project Manager

evaluates the proposals once they are received. The objective is to determine if the proposal adequately addresses ESHS requirements. Proposals that do not adequately address these requirements will be either rejected, or returned to the bidder for improvements.

16.3.1.2 Pre-Qualification of the Contractor

DGDC shall maintain a register of qualified contractors. Each contractor shall be evaluated as to the level of risks of supplied products and services in terms of environmental, health and safety and social aspects. For instance:

- A supplier of chemical products is of higher risk than a supplier of pipes
- A provider of electrical installation and maintenance services is of higher risk than a provider of IT services

Information should be systematically gathered from contractors related to high risk activities.

- Requesting information about certifications related to environmental, health and safety and social aspects (ISO14001, OHSAS18001, ISO45001)
- If no such certification is available, asking information about how the contractor manages key risks
- Performing audits of those contractors whenever deemed relevant and feasible.

Contractors with unsatisfactory management of risks should be identified as banned for use in the register of contractors. Other contractors should be identified as qualified for use. Certain may be identified as preferred contractors.

16.3.1.3 Contractor Selection

DGDC will only contract with contractors identified as qualified in the register of contractors, as per the qualification process above. For a given assignment, and depending on the risk level of the assignment, expectations from the contractor in terms of environment, health and safety and social aspects shall be included in the request for tender.

Depending on the level of risks, the evaluation of the bids from contractors should take into account the environmental, health and safety and social dimensions, on top of other factors such as price, technical aspects and quality.

Records of the tender process demonstrating the integration of environmental, health and safety and social aspects shall be maintained by DGDC.

16.3.1.4 Contractor Award

Once the contractor or supplier has been selected, a contract is drafted. At this point, the Project Manager with help of DGDC's Legal Department includes the necessary clauses in the contract to allow DGDC to enforce compliance with the company's ESHS requirements.

Per the contract with DGDC, the principal Contractor must align with the Project's ESHS standards and procedures, including communication methods, responsibility and contract monitoring.

16.3.1.5 Contractors Responsibility

The Contractors must develop a subcontractor risk management plan in conjunction with DGDC whenever high risk activities are identified. Risk management plans shall:

- Identify key risks related to the activities of the Sub-Contractor and interfaces with DGDC and other contractors, where relevant.
- Define how those risks are going to be managed and monitored.
- Define reporting on the management of those risks.

The latest version of risk management plans shall be communicated to DGDC, who shall record them as part of their ESMS.

If not already in place, the Contractor will establish policies and procedures to manage and supervise its own subcontractors. The responsibilities of the Contractors include, but are not limited to:

- Responsible for complying with all applicable host country ESHS regulations and permit or licenses commitments;
- Work safely to ensure the safety of their own employees, as well as that of other contractors, site visitors, the general public and the environment;
- Ensure that employees are properly trained, certified, qualified or competent for the activities they are expected to perform;
- Conduct or participate in the required meetings of Health, Safety and Environment;
- Provide and ensure that workers use all the required Personal Protection Equipment (PPE);
- Resolve any applicable corrective action that results from agency or DGDC inspections, promptly and to DGDC's satisfaction;
- Report all incidents to the Project Manager; and
- Conduct environmental monitoring for all relevant phases of work and report emerging risks to DGDC management.

Each Contractor is responsible for their employee's and subcontractor activities. Therefore, if the Contractor intends to subcontract part of the service, the third party must meet all the requirements described in this plan for the duration of the contract. The Contractor will be responsible for conducting supervision and enforcing DGDC's standards.

16.3.1.6 Review and Approval of Contractor ESHS Documents

Contractors and subcontractors are required to send all of the ESHS plans and procedures that intend to utilize during the Project to the Project Manager, prior to the initiation of any activities controlled by these documents. DGDC Management and the Project Manager, review the documents to ensure that contractors and subcontractors comply with DGDC policies, and management plans, as well as with host country ESHS laws and regulation. The activities controlled by these documents cannot be initiated until the documents are approved by DGDC Management and the Project Manager. The ESHS documents must be available for DGDC review at the Contractor office and on-site whenever possible.

In the event that a contractor has ESHS documents that cover the same topics as DGDC corporate and/or Project documents, DGDC Management will determine which documents will apply to the contractor's work for the Project. Then, the documents that apply will be listed in a Bridging Document.

Contractor documents must clearly describe the objective, process, responsibilities, and relation to other elements of the ESHS documents. Specifically, management plans will include the following information:

1. Objectives;
2. Legal requirements;

3. Roles and responsibilities;
4. Training;
5. Process description;
6. Monitoring;
7. Performance indicators; and
8. Reporting and notification requirements.

16.4 Training and Competency

Prior to the start of any activity, contractors must ensure and provide evidence that their workers have received the necessary information and training to recognize the present work risks to protect their health, and to have the necessary skills to do the assigned activities.

Before starting the assigned work, employees must have, at least the following information:

- Knowledge of materials, equipment and tools;
- Identified risks associated to operations and the control measures;
- Potential risks for health and safety along with prevention measures;
- Health and safety norms that can be applied;
- PPE use;
- Emergency procedure;
- Incidents or accidents reporting method;
- Insurance for risks and environmental associated risks;
- Waste disposal standards;
- Environmental protection norms;
- Understanding of the grievance's mechanism;
- Existence of Human Resources Procedure or mechanism to make sure that work conditions are in agreement with national regulation; and
- Labor law elements.

16.5 Contractor Supervision Procedure

Depending on the level of risks, DGDC shall evaluate the performance of the contractor in the management of environmental, health and safety and social aspects throughout the realization of the contract. Surveillance is made of a combination of the following:

- Kick-off meeting (mandatory)
- Periodic meetings, depending on risks
- Audits
- Reporting by the contractor
- Contract closure and return on experience meeting

The surveillance method shall be defined for each contract.

The above surveillance shall result in an evaluation at the end of each contract, which shall be recorded in the register of contractors of DGDC. The result of this evaluation may be considered for future contracting processes to ensure the provision of quality services and strong commitment in the environmental, social, health and safety occupational dimensions.

The Contractors, in collaboration with DGDC, will establish, maintain, and strengthen as necessary an organizational structure that defines roles, responsibilities and authority to implement the ESMS and ESMP. Specific personnel with clear lines of responsibility and authority will be designated in this section. Key ESMS responsibilities will be communicated to the relevant personnel and to the rest of the Contractor workforce as well as DGDC and any Subcontractors. Sufficient management sponsorship and human and financial resources will be provided on an ongoing basis to achieve effective and continuous ESMS performance.

16.5.1 Direct Supervision

16.5.1.1 Construction

DGDC shall perform at least the following types of meeting with the EPC Contractor:

Table 16-2: Supervision of the EPC Contractor

Meeting	Frequency	Content	Attendants
Morning meeting	Daily	<ul style="list-style-type: none"> Key events from the past day Presentation of key activities of the day Identification of activities presenting specific risks; presentation and discussion on how those risks are going to be controlled and monitored 	DGDC operational representative, ESHS EPC Contractor representative for operations
Weekly meeting	Weekly	<ul style="list-style-type: none"> Activity planning for the coming weeks with key risks Planning on how to manage key risks 	DGDC representative EPC Contractor representative ESG and H&S representatives from DGDC and Contractor
Monthly meeting	Monthly	<ul style="list-style-type: none"> Actions from last meeting Monthly ESMS performance ESMS monitoring activities performed by the contractor ESMS monitoring activities performed by DGDC Complaints Incidents, accidents and resulting actions Non-conformities and their status Improvement actions 	ESMS representatives from DGDC and Contractor

ESMS review	Twice a year	<ul style="list-style-type: none"> • Actions from last meeting • Key events and changes affecting the ESMS • Surveillance activities and results by the contractor and DGDC • Complaints • Incidents, accidents and resulting actions • Non-conformities: analysis, trends • Improvement actions 	DGDC Director(s) and ESMS representative EPC Contractor Director(s) and ESMS representative
-------------	--------------	---	--

The above types of meeting, contents and frequencies shall be regularly reviewed in light of return on experience and risks.

DGDC shall audit the adherence of the EPC contractor to agreed procedures through the audit plan, defined in the audit procedure (DGDC-ESMS-006).

16.5.1.2 Operation

DGDC shall perform at least the following types of meetings with the O&M Contractor:

Table 16-3: Supervision of the O&M Contractor

Meeting	Frequency	Content	Attendants
Weekly meeting	Weekly	<ul style="list-style-type: none"> • Activity planning for the coming weeks with key risks • Planning on how to manage key risks 	DGDC representative O&M Contractor representative ESMS representatives from DGDC and Contractor
Monthly meeting	Monthly	<ul style="list-style-type: none"> • Actions from last meeting • Monthly ESMS performance • ESMS monitoring activities performed by the contractor • ESMS monitoring activities performed by DGDC • Complaints • Incidents, accidents and resulting actions • Non-conformities and their status • Improvement actions 	ESMS representatives from DGDC and Contractor

ESMS review	Twice a year	<ul style="list-style-type: none"> • Actions from last meeting • Key events and changes affecting the ESMS • Surveillance activities and results by the contractor and DGDC • Complaints • Incidents, accidents and resulting actions • Non-conformities: analysis, trends • Improvement actions 	<p>DGDC Director(s) and ESMS representative</p> <p>O&M Contractor Director(s) and ESMS representative</p>
-------------	--------------	---	---

The above types of meeting, contents and frequencies shall be regularly reviewed in light of return on experience and risks.

DGDC shall audit the adherence of the O&M contractor to agreed procedures through the audit plan, defined in the audit procedure (DGDC-ESMS-006).

16.5.2 Reports

The contractor must deliver to the Project Manager a corresponding reports of the social and environmental activities carried out, to be delivered monthly. This report will include:

- Environmental reports (e.g. activities, relevant findings, national legislations etc.);
- Social reports (e.g. activities, relevant findings, compliance to national legislation).

The contractor will also submit reports regarding occupational health and safety activities to the H&S Manager on a monthly basis. Among the information that will be included in the reports are:

- Compliance with the occupational health and safety aspects established in the corresponding Project-level procedures.
- Accident Statistics Report.
- Report of compliance.
- Follow-up report and compliance of audit's findings.

16.5.3 Monthly Audits

The Project Manager will carry out a monthly audit to the contractor, in order to verify the existence of the documentation requested by the Project and review it. Monthly audits will be scheduled. The documentation review will be randomly as well as the Key Performance Indicators (KPIs); as a result, the level of performance of the contractor and subcontractors will be assessed. Thus, corrective measures will be defined, when applied, as well as the time of its completion.

The H&S Manager will hold monthly audits to the contractor in order to verify that activities are running according to established procedures work, in order to prevent incidents and accidents, while running the activities. The result of the audit is sent to the contractor for monitoring and compliance with the health and safety recommendations established in the audit.

16.5.4 Accommodation Auditing Protocol

During the initial stages of construction, the Project expects to hire local workers located within a daily commute distance of the Project site. However, several construction activities will require workers with

specialty skills who will live in local hotels and accommodations. Construction will require up to 50 workers. During operations, DGDC estimates that there will be 4-6 employees on site.

The migrant workforce is not expected to be significant; however, as some local hotels and accommodations will be used to lodge migrant workers an accommodation auditing protocol will be required.

The Accommodation Auditing Protocol is a tool to verify and check on the suitability and appropriateness of housing conditions for expatriate subcontractors working on the DGDC Project. The purpose of these audits is to detect, assess, support and control the problems and needs of the expatriate workers, enhancing autonomy and improving the quality of life of the worker for their better performance and productivity on the Project. The audits will be focused on the health of the expatriate workers, if the house complies with health standards, vector control standards, and has basic services (such as water, electricity, easy access to the project, and if the worker has access to transportation services).

DGDC's Contractors will be responsible to carry out the Home Auditing Protocol to guarantee that the audits are completed according to what is established in this plan and that it is executed in an efficient way.

DGDC's Contractors will perform at least two visits per month to a random sample of the homes. The home visit will consist of the activities listed below.

1. **Planning of the Visit:** The Contractor's staff member (such as the HR manager or ESG manager) will plan and organize the monthly visits to worker homes. The visits will be carried out every month, and will only take place on weekdays.
2. **Arrival at the house:** Once the date and time have been established, the worker is committed to be present at the house while the audit is taking place. A DGDC staff member (such as the HR manager) will accompany the Contractor for the visit.

Upon their arrival, the team will greet the worker, introduce himself or herself, and personalize the contact. The number of people who live with the worker will be verified, as well as the type of housing in which he/she lives. In addition, the Contractor will verify if the house has basic services such as water and electricity, and whether the house is located in an area where it is easy to get to the Project site, as well as if the house is in an area that represents social risk or is high in crime. The visit will be focused on studying and observing the social and family environment.

3. **Survey:** Attached as an appendix to this Plan (**Appendix 16-A**). Once the inspection has been completed, a survey form will be completed and submitted.
4. **Close of the visit:** Once the visit is over, the Contractor will present a summary report of the audit findings to the Project's ESG Manager about the visit, who will determine the actions that will be carried out according to the social report presented.

16.5.5 Subcontractor Monitoring by the Contractor

The contractor is responsible for the performance supervision of the subcontractor's social, environmental and occupational health and safety performance. It is responsible for their compliance with the required E&S standards.

16.6 Documentation and Monitoring

DGDC will keep a record of the following documents:

- Contractor's pre-qualification documentation;
- ESHS Plan, and any other plans, developed by the Contractor;

- Evidence of compliance with national legislation in environmental, health and safety matters, including work conditions (training certificates, medical care records, work contracts, environmental license, among others); and
- Evidence of compliance with the standards and policies established in the ESMP.

16.7 Key Performance Indicators

The Contractor Management and Supervision Plan is to be reviewed on a six-month basis for the initial two years and then annually or as necessary in consultation with contractors and subcontractors.

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 16-4: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool/ Frequency
Contractor's policies compliance	Contractor's compliance with labor conditions and policies	100% compliance with terms and conditions of employment, with human resources policy and code of conduct (or similar), with labor relations, with non-discrimination and equal opportunities and retrenchment	All Project phases	Contractor's policies and management plans / Quarterly
Worker's Health and Safety	Number of reports generated indicating the number of accidents and incidents	100% of reported accidents (total days and hours). Correct implementation of corrective measures when applicable.	All Project phases	Contractor's Monthly Reports / Monthly
	Contractor's compliance with H&S management plans	Compliance with 100% of H&S management plans	All Project phases	Contractor's Monthly Reports and Management Plans / Monthly
Environmental and Social Impacts	Contractor's compliance with Environmental and Social management plans	Compliance with 100% of Environmental and Social management plans	All Project phases	Contractor's Monthly Reports and Management Plans / Monthly
Community Health and Safety	Contractor's compliance with the Community Health and Safety management plan	Full compliance with the Community Health and Safety management plan	All Project phases	Contractor's Monthly Reports and Management Plans / Monthly
Worker's accommodation	Compliance with the Accommodation Auditing Protocol	100% compliance with the Accommodation Auditing Protocol	All Project phases	Accommodation Auditing Protocol Checklist / Quarterly
Supervision	Number of reports, follow-up meetings and monthly audits	At least one meeting per week. At least one report per month. At least one audit per month.	All Project phases	DGDC records / Weekly and Monthly

17. STAKEHOLDER ENGAGEMENT PLAN

17.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the implementation of the Environmental and Social Management Plans (ESMP) policies and procedures.

Stakeholder engagement is an essential part of the ESIA and project development process. It ensures that stakeholders, including Project-affected communities, are provided with timely and transparent information regarding the Project, and allows stakeholders to provide input on potential issues of concern relating to the Project.

This Stakeholder Engagement Plan (SEP) outlines the program of engagement for the communities in the Project's Area of Influence. Development, update and implementation of this SEP are the responsibility of DGDC (the Project). This SEP conforms to international good practice and has been developed to align with the IFC's Guidelines for meaningful stakeholder consultation, and to enable a positive community change through community participation. DGDC acknowledges the importance of an adequate management of the environmental and social risks and impacts associated with its Project, alongside the expansion of the positive effects of its activities. DGDC believes that a two-way communication and participation with internal and external stakeholders is essential for the development and success of its operations.

This SEP is designed for an ongoing exchange of information that allows the Project to 1) identify, understand and address community/stakeholders priorities and concerns, and 2) improve decision-making and transparency. Furthermore, this is an evergreen document that will evolve according to DGDC's activities.

Aligned to the above, the Stakeholder Engagement Plan establishes the guidelines for the:

- Identification of Stakeholders within the Project's Area of Influence (AOI) and definition of their characteristics;
- Stakeholder Mapping and prioritization of stakeholders;
- Disclosure of information and community participation;
- Defining the appropriate communication tools;
- Scheduling communication and engagement activities; and
- Keeping a record of the interactions with stakeholders.

17.1.1 Objective

This SEP has been developed to meet the expectations of the company, regulators and the communities. The SEP describes the stakeholder identification process and outlines an engagement program to promote meaningful, timely and effective engagement with stakeholders. It builds on previous engagement efforts, such as the public consultation carried out in June of 2017.

Engaging stakeholders is an important aspect of managing ongoing social and environmental performance and non-technical risks. The objectives of stakeholder engagement are to:

- Promote the development of respectful and open relationships between stakeholders and DGDC;
- Identify stakeholders and understand their interests, concerns and influence in relation to ongoing activities as well as relevant interested parties such as government agencies and other key

stakeholders. Vulnerable groups (elderly, disabled, unemployed) will also be identified as stakeholders;

- Provide stakeholders, both interested and affected stakeholders, with timely information about the Project's activities, in ways that are appropriate to their interests and needs;
- Provide a disclosure plan, including the identification of any locations where relevant project documentation will be available locally and elsewhere as well as languages to be used;
- Guarantee the active participation and consultation of the stakeholders throughout the life of the Project. During the consultations there will not be any form of manipulation, interference, coercion or external intimidation;
- Support alignment with the international requirements, corporate standards and guidelines for stakeholder engagement and identify the local legal framework of consultation activities and disclosure requirements, particularly in respect of those public consultation activities that are directly required under the local permitting process;
- Describe how concerns or grievances will be handled via a Grievance Mechanism and record feedback and resolve any grievances that may arise through a formal feedback mechanism;
- Identify the resources and responsibilities for the SEP execution, including the monitoring activities; and
- Monitor and evaluate the actions carried out to adapt or modify the SEP as necessary.
- Record all consultation activities, including those prior to the commencement of the ESIA process; and
- Provide an action plan for further consultation including at least two meetings bi-annually in each affected community during preparation, construction and operational phases of the Project, including details on appropriate formats for effective and culturally meaningful interaction with the community and relevant stakeholders.

17.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's ESMP policies and procedures, which are aligned to international best practices.

Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP will be applied on the ground. DGDC will review and approve this document before any implementation.

The geographical scope of the stakeholder engagement plan is described by the Project's Area of Influence (AOI), which comprises Roseau (in the Area of Direct Influence, ADI) and the entire island of Dominica (which is the Area of Indirect Influence (AII)).

17.2 Roles and Responsibilities

In order to properly implement the Stakeholder Engagement Plan, DGDC requires the involvement of the people listed below.

Table 17-1: Roles and Responsibilities

Role	Responsibilities
Executive Chairman and Board of Directors	<ul style="list-style-type: none"> ■ Be familiarized, review and approve the Stakeholder Engagement Plan.
Finance & HR Manager	<ul style="list-style-type: none"> ■ Ensure the availability of resources necessary for the implementation of the Stakeholder Engagement Plan.
Managing Director	<ul style="list-style-type: none"> ■ Be familiarized with the Stakeholder Engagement Plan and provide the necessary resources to ensure its proper implementation.
Safeguards & Administration Manager	<ul style="list-style-type: none"> ■ Responsible for office management and administration of stakeholder engagement systems
Site and Office Attendant	<ul style="list-style-type: none"> ■ Monitor sites for maintenance purposes, to provide local guiding services to visitors and undertake office activities as required
Community Liaison Officer	<ul style="list-style-type: none"> ■ Implement the Stakeholder Engagement Plan. ■ Coordinate, together with the Administration and Safeguards Officer, the implementation of the relationship and communication actions. ■ Ensure a constant communication channel with the Project Stakeholders.
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Stakeholder Engagement Plan.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Read and be familiarized with the Stakeholder Engagement Plan.

17.3 Activities

The identification, mapping and analysis of stakeholders will be a dynamic and continuous exercise in the execution of any project, since it allows a deep understanding of its context and guarantees the effectiveness and adaptation of engagement strategies. The activities found in this SEP establish the guidelines for the management of external communication channels, as well as the mechanisms to manage the participation of interested stakeholders.

17.3.1 Stakeholder Identification

The identification of stakeholders is essential, since it provides the basis for designing the relationship strategies with each interest group in order to achieve the greatest possible participation and social acceptance. To the extent that as the participation and acceptance grows, social impacts and risks may be minimized in greater proportion.

Likewise, the mapping helps to define which interest and affected groups DGDC will contact and how to manage the risks. This section of the SEP focuses on the stakeholder identification and mapping identified for the early stages of the Project.

Considering previous experiences, direct sources of information (e.g. interviews, surveys) and publicly available information, the Project's stakeholders have been identified by:

- Analyzing who could be affected by the Project activities and how. For doing so, the Project geographical location as well as its activities and potential impacts will be considered (e.g. primary site, related facilities, transport routes, etc.);
- Avoiding limited criteria for the identification of stakeholders affected and prioritizing groups of neighboring people;

- Phone interviews were carried out with different stakeholders.

17.3.1.1 Methodology

One of the first steps in stakeholder engagement planning is the identification of stakeholders. Stakeholders typically include government officials, regulators, members of the community and public at large, Non-Governmental Organizations (NGOs) and civic leaders, media, employees and contractors, and industry associations. Stakeholders can be individuals working on a project, groups of people or organizations, or even segments or sectors of a population. A stakeholder may be actively involved in a project's work, affected by the project's outcome, or in a position to affect the project's success.

After identifying the stakeholders, it is key to understand their needs and expectations for engagement, and their priorities and objectives in relation to the Project.

As part of this process, it is particularly important to identify individuals and groups who may find it more difficult to participate and those who may be differentially or disproportionately affected by the project because of their marginalized or vulnerable status. It is also important to understand how stakeholders may be affected – or perceive they may be affected – so that ongoing engagement can be tailored to inform them in an appropriate manner and address their views and concerns.

While an interest in an effort or organization could be just that – intellectually, academically, philosophically, or politically motivated attention – stakeholders are generally said to have an interest in an effort or organization based on whether they can affect or be affected by it. The more they stand to benefit or lose by it, the stronger their interest is likely to be; and the more heavily involved they are in the effort or organization, the stronger their interest is as well.

Stakeholders' interests can be many and varied. A few of the more common interests include:

- Labor
- Social Change
- Economics
- Indigenous Peoples Rights
- Environment
- Natural Resources
- Safety and Security

The identification of stakeholder groups for DGDC should be made through publicly available information, local knowledge from the Project team and data collected during the any interviews with stakeholders. The stakeholder groups have been "mapped" according to their influence, interest and probable position in relation to the Project. This assignment is based on knowledge of the social, cultural, political, environmental, and factors associated with the development of the Project.

Vulnerable groups who may be differentially or disproportionately affected by the Project because of their disadvantaged or vulnerable status should also been identified as part of the stakeholder mapping. This group of affected stakeholders should be determined based on factors, data and status of gender, ethnicity, culture, physical or mental disability, poverty or economic disadvantage and dependence on unique natural resources.

Once the stakeholder groups are identified, their position, interest and influence regarding the Project are evaluated. The position has been defined as the degree of acceptance by the interest group towards DGDC. The criteria are presented in the table below.

Table 17-2: Assessment of Position Criteria

Assessment	Position
In favor	The interest group's position in relation to the Project is favorable; given that it perceives that, it has or will have a positive performance in relation to its topics of interest.
Neutral	The stakeholder's position in relation to the Project is neutral, indefinite. You may have the expectation that he/she will have a position to minimize the existing impacts. However, he/she needs more information, since it is not clear to him/her how the Project will be developed in the future.
Against	The position of the group of interest in relation to the Project is unfavorable, since it identifies more negative aspects than positive ones in the current or future development of the Project.

Source: ERM, 2020.

The interest has been defined as the stakeholder's interest degree that he/she has on the issues associated with DGDC. The evaluation criteria are presented below.

Table 17-3: Interest Evaluation Criteria

Assessment	Interest Position
Low	The interested party does not know or recognizes few links between the Project and their own interests, and shows little interest in knowing more about it.
Average	The interested party recognizes some relations between the Project and its interests.
High	The interested party recognizes a set of common interests with the Project and shows a strong interest to know more information about it.

Source: ERM, 2020

Finally, the influence has been defined as the degree of articulation with other actors and the capacity to generate mobilization as seen on the table below.

Table 17-4: Influence Evaluation Criteria

Assessment	Influence Position
Low	The interested party has little capacity for mobilization and/or few networks and relationships with local actors.
Average	The interested party has the ability to articulate and mobilize media, exerts influence in social networks with important connections with local actors such as inhabitants, workers, tourists, politicians, among others.
High	The interested party has a high capacity for articulation and mobilization with significant local networks and actors such as inhabitants, workers, tourists, politicians, among others.

Source: ERM, 2020

17.3.1.2 Stakeholder Groups

Stakeholder groups are individuals, groups or institutions that have a stake or a particular interest in the Project. They may be affected by it (either positively or negatively) or they may have an interest in it and be in a position to influence its outcomes. Therefore, the stakeholder groups have been classified as:

- Interested groups, which can be Project beneficiaries and commonly favor the Project; and
- Affected groups, which are individuals or groups adversely affected by the Project and consequently some might oppose the Project.

The Project will follow a different consultation rationale per stakeholder group. The Project will closely monitor, engage and consult the affected groups in the AOI. Meetings with these groups, described below, are prioritized by the Project. On the other hand, the Project engages with interested groups to keep them informed about the Project, to collaborate in topics related to common issues, such as health and safety measures, and provide specific information when they request it. While the consultation rationale towards interested groups is not as intense and frequent as with the affected groups, DGDC is committed to maintain a close relationship and frequent communication with government entities and financial institutions, among others.

Table 17-5: Affected and Interested Stakeholder Groups in the Project's AOI

Affected Stakeholder Groups	Interested Stakeholder Groups
<p>Communities in the Area of Influence and landowners near the Project site: Residential communities in the Project's wider socio-economic Study Area. Several land plots and houses have been identified near the Project site. For example, Laudat, Trafalgar and Wotten Waven communities.</p>	<p>Government entities relevant to the Project: Government agencies, elected officials and public service providers that may be at the local or national levels. For example, Ministry of Public Works, Energy & Ports, Office of Disaster Management</p>
<p>Tourism sector: This sector includes different groups within the sector such as hotels, restaurants and government agencies. For example, Wotten Waven Spa Operators and Papillote Wilderness Retreat.</p>	<p>Neighboring Projects: Includes companies carrying out activities near the Project.</p>
<p>Vulnerable groups in the AOI: This stakeholder group could include women, children and elderly, indigenous people, families and individuals in extreme poverty, people with physical and psychological disabilities, and individuals that depend on natural resources. These groups are commonly more vulnerable to social inequality. In addition, vulnerable groups have a higher sensitivity to potential Project impacts, in many cases do not have the means to defend their interests and concerns and it is more challenging for them to benefit from the Project's benefits. For example, women.</p>	<p>Financial Institutions: Financial Institutions that will finance the Project. For example, World Bank, IDB.</p>
<p>NGOs, Associations and civil organizations: Local and regional NGOs and associations that could generate opinions about the development of the Project or that could participate in conflict resolution that could take place within the communities. For example, Community Leaders of the Roseau Valley, Laudat Community, Laudat Improvement Community.</p>	<p>Mass media: It refers to media present in the Area of Influence, including social media platforms linked to the Project.</p> <p>Contractors: It includes DGDC's contractors and sub-contractors.</p> <p>Workers and Staff: It includes all of DGDC's workers and staff.</p>

Source: ERM, 2020

17.3.1.3 Stakeholder Analysis

The table below presents each stakeholder group description, identified actors, and their potential position, interest and influence. Ten (10) categories of interest groups have been identified: i) Communities and landowners in the Area of Influence, ii) Neighboring Projects, iii) Tourism Sector, iv) Government Entities, v) NGOs and Associations, vi) Financial Institutions, vii) Mass Media, viii) Contractors, ix) Workers, and x) Vulnerable Groups.


Table 17-6: Analysis and Identification of Stakeholder Groups

Stakeholder Group	Description	Identified Actors	Potential Position (Against, Neutral, In favor)	Interest (Low, Average, High)	Influence (Low, Average, High)
Communities in the Area of Influence and landowners near the Project Site	It refers to those locations that are within the perimeter of the Project or neighboring areas and may be affected by the Project.	Laudat, Trafalgar and Wotten Waven Communities, Roseau Valley Constituency	In Favour	High	Average
Local Authorities and Government entities relevant to the Project, including the management authority of the Morne Trois Piton National Park	It refers to Dominica island authorities that might be affected by the Project.	Ministry of Public Works, & Digital Economy, Office of Disaster Management, Forestry Department, Invest Dominica Authority, Statistics Department, Environmental Health Department, Discover Dominica Authority, Ministry of Agriculture, DOWASCO, DOMLEC, Ministry for Blue & Green Economy; Ministry of Planning, Economic Development and Investment; Environmental Coordinating Unit; Ministry of Housing & Lands; Ministry of Health and New Health Investment; Independent Regulatory Commission	In Favour	High	High
Tourism Sector	Businesses in the tourism sector, such as restaurants, hotels, or the tourism department.	Wotten Waven Spa Operators, Papillote Wilderness Retreat, Dominica Hotel and Tourism Association, vendors, , Café Mon Plaisis, Rainforest Cottages; Le Petit Paradis;; Symes Zee Villa; Roxy's Mountain Lodge; tour guides	In Favour	Average	Average
Neighboring Projects	Refers to any projects that are being developed near the Project site	<ul style="list-style-type: none"> ■ 3 River's Eco resort 	Neutral	Low	Low
Vulnerable Groups in the AOI	This category includes identified vulnerable groups in the AOI	<ul style="list-style-type: none"> ■ Women, children and elderly ■ Families and individuals in extreme poverty ■ People with physical and psychological disabilities ■ Individuals that depend on natural resources 	In Favour	High	Average
NGOs and Associations	Local and regional NGOs and associations that could generate opinions about the development of	Community Leaders of the Roseau Valley, Laudat Improvement Committee, Geothermal Awareness	Neutral	Average	Average

	the Project or that could participate in conflict resolution that could take place within the communities.	Committee; Laudat Church Committee; Laudat Farmers Group; Wotten Waven Improvement Committee; Wotten Waven Development Committee; Wotten Waven Farmers Group; Trafalgar Village Council; Trafalgar Vendors Association; Trafalgar Church Committee; Trafalgar Farmers Group			
Contractors	It includes DGDC's contractors and sub-contractors.	The Project's clients, suppliers, contractors and subcontractors. They will be defined once the Project begins.	In favor	Average	Average
Workers and Staff	It includes all of DGDC's workers and staff.	The Project's workers,	In favor	High	Low
Financial Institutions	Includes financial institutions interested in financing the Project	<ul style="list-style-type: none"> ■ Inter-American Development Bank ■ Caribbean Development Bank ■ World Bank 	Neutral	High	High
Mass Media	Includes mass media in the Project area.	<ul style="list-style-type: none"> ■ Dominica Broadcasting Corp, Wice FM, Kairi Radio, Dominica Newsonline 	Neutral	Average	High

The following figure shows the identified actors that have been engaged with and their probable position and influence on the Project according to the qualitative analysis.

The categories of stakeholder groups were assigned in an X-Y axis according to their position (X-axis) and the influence (Y-axis) with respect to the Project. A qualitative mapping criteria scale was applied in order to position the stakeholders on the X-Y axis. The level of influence of each interest group was determined as High, Average or Low. Just as the probable position was determined as *Positive* (grey), *Negative* (blue) or *Neutral* (light blue).



Source: ERM, 2020

Figure 17-1: Mapping of the Stakeholder Groups

17.3.2 Community Participation

Effective participation requires sharing information related to the Project with affected communities and other key stakeholders, facilitating a well-informed consultation process and the contribution of interested citizens to the design and planning of the Project.

In order to promote a better understanding of the Project and instill confidence among its stakeholders, DGDC will ensure transparency in the communication of relevant information by:

- Disclosing information on a timely manner;
- Disclosing relevant information by managing expectations adequately (e.g. employment opportunities) and avoiding downplaying the potential negative aspects (e.g. inconvenience during the construction phase);
- Disclosing relevant information in a culturally appropriated manner to facilitate the participation of local population;
- Disclosing information in a way that supports the consultation process, allowing enough time to pass between the communication of information and the start of the consultations.
- Disclosing the existence of the External Grievance Mechanism and its communication channels.

17.3.2.1 Communication Tools

Media and Disclosure of Written Information

DGDC has set up a Project specific website (<https://www.geodominica.dm/>) which is regularly updated highlighting progress, minutes of meetings that have taken place, the latest grievances that have been

raised and other issues as appropriate. This site will be functional throughout the duration of the scoping and construction periods and for at least the first years of operation.

Community Visual Aids

DGDC will produce visual aids to support community engagement. Visual aids shall describe the Project and impacts using images and photographic examples of the types of activities and infrastructure planned. Images shall be used to facilitate discussion potential impacts.

Community Meeting Records

Records of community consultation meetings, meetings with government and civil society shall be kept in a separate document with the detailed stakeholder database. All records shall include attendance lists and photos.

Language

All community materials shall be translated into Creole and English to meet the needs of local stakeholders. Meetings shall be conducted in English and Creole as necessary. Materials for government and civil society stakeholders shall be in Creole and/or English.

17.3.2.2 Engagement Activities to date

Stakeholder engagement and outreach activities have been carried out by the Project since 2012. Since this date, the Project has carried out some consultation activities to provide the public with information about the Project and its potential impacts, to elicit public input and feedback on various Project aspects and access local knowledge on baseline environmental, social and health conditions in the Project area communities. These activities included:

- In 2012 school visits were conducted in February and March from the Wotten Waven Primary School, Trafalgar Primary School, Morne Prosper Primary School and Laudat Primary School, where students and staffed toured the drilling sites;
- Laudat Public Meetings: January 20, 2011; November 11, 2011; February 15, 2012, April 13 and 16th 2012; November 14, 2013; December 11th 2013; January 23, 2014; July 2017; and March 17, 2018 (for details see Appendix A of Appendix J in Volume 5 of the Jacobs ESIA);
- Trafalgar Public Meetings: January 12, 2011; November 8, 2011; March 28, 2012; November 12, 2013; December 12th, 2013; December 2016; and March 18 and 25, 2018 (for details see Appendix A of Appendix J in Volume 5 of the Jacobs ESIA);
- Wotten-Waven Public Meetings: January 16, 2011; November 10, 2011; June 13, 2012; December 13, 2013; March 24, 2018 (for details see Appendix A of Appendix J in Volume 5 of the Jacobs ESIA);
- A town hall meeting was held in Trafalgar in December 2016 with approximately 40 in attendance, where the project and ESIA were discussed. In July 2017, a town hall was held in Laudat with 43 in attendance. An additional town meeting was held in Wotten Waven in August 2017.
- The Grievance Mechanism was shared with the community during the 2017 social baseline survey process
- 15 focus groups were held in 2016, 2017 and 2018 in Wotten Waven, Trafalgar and Laudat. These included meetings with community women, vendor meetings, meetings with hotels and resorts, hot

springs businesses and unemployed parties. Groups consisted of 5-15 people and target questions were asked and recorded. See table below for a summary of interviews with these focus groups.

- The ESIA non-Technical Summary was disclosed to the communities of the Roseau Valley via three public meetings: one in Laudat, one in Trafalgar and one in Wotten Waven in the first week of July 2018. Meetings were attended by Jacobs, DGDC, and approximately 20 members of each community. The community had another opportunity to express concerns and ask questions about the Project and ESIA findings. Concerns generally included community health and safety issues, natural hazards, employment and construction impacts. A summary of the meetings is included in **Appendix 17-A** below. For additional meeting minutes, please see Appendix J in Volume 5 of the Jacob's ESIA.
- Two national consultations on the Jacobs ESIA were conducted in February 2019 one in the south and one in the north (Portsmouth). A series of public meetings to update the community on the changes in the project were held in June 2020. Given the COVID-19 public gathering protocols, the DGDC conducted 3 sessions per day for three days to allow for maximum community participation. Eclipse Inc conducted three focus group meetings in August 2020 and another meeting to present the findings of the ESIA to the community in November 2020. Lastly, consultation with landowners was held in October 2020 by Eclipse and by DGDC in June 2020.

Table 17-7: Summary of DGDC Interviews with Key Stakeholders

Consultation	Comment Category	ESIA Reference	Response
Laudat Community at Laudat Primary School (29/06/2017)	Noise level of the project and effect on the community	ESIA Volume 2: EIA, Section 12 – Noise (Section 12.5 Assessment of Impacts)	Operational noise will be within acceptable community noise standards. Noise from construction will be reduced to the extent feasible using best practice mitigation measures.
Papillote Wilderness Retreat (30/06/2017)			
Wotton Waven Spa Operators			
Laudat Community at Laudat Primary School (29/06/2017)	Community Benefits	ESIA Volume 3: SIA, Employment and community benefits, Section 6.1.1 – Assessment of Impacts and Section 8.1.1 Employment and Tourism.	The GoCD is committed to providing a community benefits package for this Project. There are several ideas for community benefit/investment options detailed in the ESIA.
Papillote Wilderness Retreat (30/06/2017)			
Wotton Waven Spa Operators			
Papillote Wilderness Retreat (30/06/2017)	Will there be a social/community development fund	ESIA Volume 3: SIA Employment and community benefits, Section 6.1.1 – Assessment of Impacts and Section 8.1.1 Employment and Tourism	The GoCD is committed to providing a community benefits package for this Project. There are several ideas for community benefit/investment options detailed in the ESIA.
Laudat Community at Laudat Primary School (29/06/2017)	Will the re-injection pipeline pass	ESIA Volume 3: SIA, Preferred route of reinjection pipeline, Figure	The re-injection route pipeline has been selected with the intent of avoiding

Consultation	Comment Category	ESIA Reference	Response
	through villages?	4.3 - Location of Power Plant and Reinjection Pipeline.	settlements to the extent feasible.
Papillote Wilderness Retreat (30/06/2017)	What will be the visual impact of the project?	ESIA Volume 2: EIA, Section 9 – Landscape and Visual (Section 9.3 – Assessment of Impacts).	The Project is expected to have minor visual impacts with the exception of those living immediate adjacent to the power plant.
Papillote Wilderness Retreat (30/06/2017)	What will the impact on tourism be? Concerns that it will have a negative impact	ESIA Volume 3: SIA, Tourism impacts: Section 6.2.5 Impacts to Tourism. ESIA Volume 3: SIA, Tourism enhancement and mitigation, Section 8.1.1 Employment and Tourism.	Impacts are tourism including thermal spas, etc. are considered to be minor. The thermal resource is not likely to be reduced as a result of the Project and the Project could become an educational tourist destination.
Papillote Wilderness Retreat (30/06/2017)	Traffic impacts on the community and local businesses	ESIA Volume 2: EIA, Traffic impacts, Section 16 – Traffic and Access (Section 16.3 Assessment of Impacts).	Traffic congestion could result during construction and will be mitigated to the extent feasible. Long-term traffic increases are considered minor.
Wotten Waven Spa Operators			
Papillote Wilderness Retreat (30/06/2017)	Air quality impacts	ESIA Volume 2: EIA, Air Quality impacts, Section 4 – Air Quality (Section 4.3 Assessment of Impacts).	Air quality emissions will be within acceptable community standards. Dust from construction will be reduced to the extent feasible using best practice mitigation measures.
Wotten Waven Spa Operators			
Papillote – Community Leaders of the Roseau Valley	Resettlement and land acquisition impacts and plans for the community and businesses	ESIA Volume 3: SIA, Resettlement mitigation plans, Section 8.1.2 Physical and Economic Displacement. ESIA Volume 3: SIA, Land acquisition impacts, Section 6.2 Land Acquisition, Physical Displacement and Resettlement Impacts.	Impacted land owners will be properly consulted and compensated in accordance with International Standards.
Papillote Wilderness Retreat (30/06/2017)			
Wotten Waven Spa Operators			
Wotten Waven Spa Operators	What would happen if the reinjection pipe has a leak and dangerous fluids are flowing on the surface?	ESIA Volume 2: EIA, Section 15, Hazardous Substances and Waste and ESIA Volume 3: SIA, Emergency Response Plan.	An Emergency Response and Disaster Management Plan will be developed and implemented for the Project in line with best practices.
Laudat Community at Laudat Primary	When and how will	See the RAP.	Impacted land owners will be properly

Consultation	Comment Category	ESIA Reference	Response
School (29/06/2017)	payment be made for property and land acquisitions?		consulted and compensated by the GoCD in accordance with International Standards prior to the commencement of any construction activity.
Laudat Community at Laudat Primary School (29/06/2017)	Potential for community shares in the Project	Outside the scope of the ESIA.	This is outside the scope of the ESIA.
Papillote Wilderness Retreat (30/06/2017)			
Papillote Wilderness Retreat (30/06/2017)	Why was solar power not considered?	ESIA Volume 2: Introduction, Section 4, Project Alternatives.	This Project evolved on the basis of the geothermal resource.
Papillote Wilderness Retreat (30/06/2017)	Why was this type of consultation not done before decision was made to drill?	See SEP for a full list of consultation activities in Appendix C of the ESIA.	Consultation has been conducted throughout the development of the Project.
Papillote Wilderness Retreat (30/06/2017)	Total cost of the Project.	Outside the scope of the ESIA.	This is outside the scope of the ESIA.
Wotten Waven Spa Operators	Project start date and duration	ESIA Volume 2: Introduction, Section 3, Project Description.	Construction date estimated to be first quarter 2019. Estimated 18 -24 months for construction of Project.



Figure 17-2 Stakeholder Engagement with the Laudat Community

17.3.2.3 Disclosure of Information

The Project will select which information will be communicated, taking into account the following:

- Project phase, activities and schedule;
- Analysis of previous interactions between DGDC and the stakeholders;
- Area where the information will be communicated;
- Stakeholder type (affected vs. interested and considering their potential influence and position regarding the Project);
- Tool chosen to share the information;
- Type of information to be communicated;
- Date of communication; and
- Responsible party for sharing the information (whether DGDC or a contractor).

The Community Liaison Officer, together with DGDC Management, will select what type of environmental, social, or occupational or community health and safety documentation regarding the Project's phases and activities will be communicated. This information will be confirmed with the contractor at each site and addressed taking into account the identified key stakeholders.

The main topics to consider during engagement activities with stakeholders are:

- Project status update: Publicize all the activities and stages of the Project;
- Project objectives in the short, medium and long term, to avoid creating misguided expectations among stakeholders;
- Information and update regarding positive and negative impacts, when applicable: Provide information on the impacts generated during each phase of the Project, as well as the mitigation measures to be implemented or already being implemented;
- Grievance mechanism: take into consideration the opinions of stakeholders to continually improve the external grievance mechanism procedures (e.g. preferred location of grievance boxes), and continue to reinforce its communication, according to positive or negative experiences;
- Emergency Plan and Community Health and Safety Plan: Share the procedures of the Project Emergency Plan and the Community Health and Safety Plan to all communities and related stakeholders for their knowledge and implementation;
- Aspects of the Project that have attracted stakeholders' attention: Contemplate the opportunity to learn about the perception of stakeholders that may not have been formally transmitted through the grievance mechanism (e.g. retrenchment plans of the Project);
- Invitations to meetings or information communication sessions where general information on the Project will be provided (stages, activities, times); and
- Other relevant plans such as the, Traffic Management Plan.

The Project will keep photographic evidence of all the relevant activities carried out with stakeholders as well as Project related developments (e.g., construction development, labor training, flora and fauna rescue and preservation activities). This will complement the communication process with stakeholders.

DGDC is aware that the lack of information can lead to an erroneous perception of the Project, and trust from local communities may be affected. DGDC will continue to share and distribute meaningful and relevant information among the Project's stakeholders throughout the Project's life cycle.

In order to do this, the Project will build solid relationships with external stakeholders (e.g. government institutions, universities, other academic entities) who can help DGDC to be known among local communities and people directly or indirectly involved in the Project (e.g. through press announcements). DGDC will work with these stakeholders to perform actions that could represent an improvement in the quality of life of community members and/or the region where the Project is located.

Depending on the type of stakeholder the means of communication will be defined, such as through the Project's website, by phone, memos, letters, email, informative sessions or meetings, brochures and copies of relevant documents placed in accessible and strategic locations.

17.3.2.4 *Consultation and Participation Action Plan*

Public consultation is a process that promotes a two-way dialogue between local communities and the Project, which will aim to ensure the establishment and maintenance of constructive relationships throughout the life of the Project. For local communities, the consultation process offers the opportunity to obtain information about the Project's activities, to update the company of the local context in which the Project is framed, to share problems and concerns, to ask questions and even, to make suggestions.

The consultation process and participation plan with local communities will follow the five basic steps detailed below, which can be repeated as many times as necessary throughout the different phases of the Project.

1. Plan ahead, before beginning a process of consultation with local communities, it will be clear who will be consulted, on what issues and for what purpose;
2. Conduct the consultations applying the basic principles of the recommended practices and adapted to the local situation and to the local communities;
3. Consider the opinions and observations received and make every effort to resolve the issues raised;
4. Document the consultation process and its results;
5. Prepare reports for stakeholders, in order to keep them informed about which of the concerns raised will be addressed and how, and explain what suggestions have not been taken into account and the reasons, so as to promote credibility, control expectations and maintain interest.

The table in the section below presents the consultation and participation plan per each stakeholder group. The table includes the consultation and participation methods, the consultation topics, shared information and objectives, the Project phase and frequency, the priority and person in charge.

17.3.2.5 Engagement in Extraordinary Situations

DGDC will endeavor to maintain engagement with stakeholders throughout the project's continuity. In the case of health-related crises, pandemics and or epidemics, DGDC will develop, when necessary, an action plan for engagement with stakeholders in this scenario.

The action plan must be developed in order to guide DGDC's performance during this period, and must contain at least the following items: (i) target audience; (ii) organizational structure; (iii) communication channels; (iv) risk prevention and mitigation measures for the teams involved in the engagement actions; and (v) list of actions.

Table 17-8: Consultation and Participation Action Plan

Stakeholder Groups	Consultation and Participation Methods	Consultation Topics, Shared Information and Objectives	Project Phase and Frequency	Priority	Person in Charge
<i>Interested Stakeholder Groups</i>					
Government entities	Meetings with representatives, either in groups or individually	<ul style="list-style-type: none"> ■ Identify any concerns regarding Project impacts and progress ■ Answer their questions regarding the Project ■ Receive feedback about the Project's social management plans, health and safety measures, community communications and community grievance mechanism 	Construction: At least once a month Operations: at least once per six months	High	Managing Director
Neighboring Projects	Meetings with other Project developers		Construction: At least bi-monthly Operations: at least once per six months	Medium	Community Liaison Officer
Financial Institutions	Meetings with representatives, either in groups or individually		Construction: At least once a month Operations: at least once per six months	High	Managing Director
Mass media	Meetings with representatives, either in groups or individually		Construction: At least bi-monthly Operations: at least once per six months	Medium	Community Liaison Officer

Workers	Meetings with representatives, either in groups or individually		Construction: At least once a month Operations: at least once per six months	High	HR Manager
Contractors	Meetings with representatives, either in groups or individually		Construction: At least once a month Operations: at least once per six months	High	Safeguards Manager

Affected Stakeholder Groups

Communities and landowners near the Project site	Group meetings (virtually) with people from nearby residences, including women, young people and other vulnerable groups	<ul style="list-style-type: none"> ■ Identify any concerns regarding Project impacts and progress ■ Answer their questions regarding the Project ■ Receive feedback about the Project's social management plans, health and safety measures, community communications and community grievance mechanism 	Construction: At least once a month Operations: at least once per six months	High	Community Relations Officer
Tourism sector	Meetings with tourism representatives, either in groups or individually		Construction: At least bi-monthly Operations: at least once per six months	Medium	Community Relations Officer
Vulnerable populations in the Area of Influence	Vulnerable groups will be invited and encouraged to attend the community meetings If a group identifies a need to meet with the Project, the Project will organize an individual meeting with the person or particular group.		Construction: At least once a month Operations: at least once per six months	High	Community Relations Officer
NGOs	Meetings or communication exchange by email or phone call	<ul style="list-style-type: none"> ■ Identify their concerns regarding the Project's impacts and progress ■ Answer their questions regarding the Project ■ Receive feedback about the Project's social management plans, health and safety measures, community communications and community grievance mechanism 	Construction: At least bi-monthly Operations: at least once per six months	Medium	Community Relations Officer

		<ul style="list-style-type: none"> ■ Discuss collaboration opportunities (e.g. environmental and social programs) 			
--	--	--	--	--	--

17.3.3 Registration Process: Stakeholder Database

Every time a communication or activity is carried out with any stakeholder, the CLO will register the details in the Stakeholder Engagement Database in order to reflect the development of the relationship with each stakeholder and the evolution of the respective negotiations.

The stakeholders' database will include a summary of each contact, participants, issues or agreements with stakeholders, including, but not limited to:

- Stage and activity of the Project;
- Stakeholder being represented;
- Type of interaction;
- Date of interaction;
- Place of the interaction;
- Background of the interaction with the stakeholder (if applicable);
- Reason for the interaction (e.g. information disclosure, follow-up meeting);
- Type of information provided (if applicable); and
- Reference to evidence supporting the interaction (e.g., minutes, photographs).

In the event that complaints or feedback are received, these will be dealt through the External Grievance Mechanism (see the External Grievance Mechanism Plan) as appropriate.

17.4 Documentation and Monitoring

Evidence of meetings and interactions with stakeholders will be maintained through the Stakeholder Engagement Database. When possible, evidence will be collected, such meeting minutes, videos, attendance lists and photographic evidence. The CLO will be responsible to maintain the documentation and records.

17.5 Reporting

Further, there will be internal and external reporting. The following sections describe the minimum reporting to be conducted.

17.5.1 Meeting Minutes

Records of community consultation meetings, meetings with government and civil society shall be kept in a separate document with the detailed database maintained by the CLO. All records shall include attendance lists and photos.

17.5.2 Recording Grievances

A formal log of grievances will be developed and the CLO will be responsible for logging all grievances except those related to land acquisition which will be handled directly by designated government

representative] of the GoCD. A comments sheet will also be provided for complaints or other comments. Comments or complaints can be made directly to DGDC or the contractor, through the CLO or through a community representative (e.g. through the village elders).

17.5.3 Stakeholder Database

The DGDC will maintain a current and regularly updated stakeholder engagement database. The database will contain:

- details of the various stakeholder groups (including their representatives, their interests and concerns);
- details of any consultations held (including when these took place, the topics discussed and the outcomes);
- any commitments made by the Project Sponsor to stakeholder groups, including outstanding commitments
- and commitments that have been delivered; and
- a record of specific grievances lodged and the status of their resolution.

17.5.4 Commitments Register

The DGDC will maintain a commitments register that keeps track of the commitments made by the DGDC throughout stakeholder consultation (including those made by any contractors or members of the Project Team).

17.5.5 Annual Reporting

The CLO will maintain engagement reports on a monthly basis. The objective of these engagement reports are to demonstrate and record the ongoing engagement process and progress made. These reports may include records of engagement including meeting registers, photographs.

These reports will be used to address and incorporate social issues into Project management. Engagement reports shall be stored with the detailed stakeholder database and retained for a minimum of five years.

At a minimum these reports will contain:

- Engagement activities undertaken;
- Grievances received as per grievance management;
- Updated stakeholder database;
- Feedback received during the engagement process;
- Update on complaints and grievances, expectations and requests,
- Investment made, and commitments and promises made; and
- Key records of communication with stakeholders.

17.6 Key Performance Indicators

The Stakeholder Engagement Management Plan is to be reviewed on a six-month basis for the initial two years and then annually or as necessary in consultation with key stakeholders.

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 17-9: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
External Grievance Mechanism	Number of confirmed grievances by community	Total number reducing each year	Construction, Operations	External Grievance Database / Quarterly
	Number of confirmed grievances resolved in a timely manner	100%	Construction, Operations	External Grievance Database / Quarterly
	Audit the grievance mechanism to ensure implementation and that grievances are being adequately addressed	Every six months, the first two years, and then once a year.	Construction, Operations	Community Liaison Officer / Yearly
Local Community & Stakeholders	Number of resolved incidents involving local community members	100% resolved incidents	Construction, Operations	Stakeholder Engagement Database, External Grievance Database and the Community Liaison Officer / Quarterly
	Number of consultation and participation activities	100% reported meetings and activities, with evidence when possible	Construction, Operations	Stakeholder Engagement Database and the Community Liaison Officer / Quarterly
	Type, materials and methods of Disclosure of Information	Cover 100% of the relevant topics as established in the Consultation and Participation Action Plan	Construction, Operations	Stakeholder Engagement Database and the Community Liaison Officer / Quarterly
	Report back and feedback to the local community and stakeholders when needed (e.g. implementation of the grievance mechanism, conflicts solved and implemented solutions, etc.)	Delivery of reports to the community and communication channel chosen	Construction, Operations	Community Liaison Officer / Quarterly
	Audit the stakeholder engagement activities	Every six months, the first two years, and then once a year.	Construction, Operations	Community Liaison Officer / Yearly
Community Relations Staff/ Team	DGDC will monitor the number of new community relations staff and staff changes per period. This will be reported on the community engagement performance report.	Every six months.	Construction, Operations	Community Liaison Officer / Quarterly

18. COVID-19 CONTINGENCY PLAN

18.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the implementation of the Environmental and Social Management Plans (ESMP) policies and procedures.

This plan aims to establish good practices to be adopted by the Project with regards to the current new coronavirus (COVID-19) pandemic, including minimum procedures and strategies that must be observed by DGDC, its subsidiaries and its employees. DGDC aims to develop its activities in safe conditions, especially concerning health and safety conditions, as well as preserving its jobs and activities.

This document will be shared with DGDC's contractors and subcontractors to incorporate the presented best practices throughout all their activities.

18.1.1 Objective

The overall objectives of the COVID-19 Contingency Plan are to:

- Define guidelines and practices regarding COVID-19;
- Establish procedures and strategies to contain and protect workers, contractors and subsidiaries from COVID-19;
- Develop activities in healthy and safe conditions;
- Promote fair treatment, non-discrimination and equal opportunity of workers, and compliance with healthy and safe (H&S) working conditions; and
- Protect workers', contractors' and local community members' wellbeing, health and safety.

18.1.2 Scope of Application

This plan will apply for the duration of the pandemic while the development of DGDC's activities take place. It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to DGDC's Environmental and Social Management Plan (ESMP) policies and procedures, which are aligned to international best practices.

Contractors will use this plan and develop it further to provide specifics on how the various requirements from the project-specific ESMP and COVID-19 measures will be applied on the ground. DGDC will review and approve this document before any implementation.

18.2 Roles and Responsibilities

In order to properly implement the COVID-19 Contingency Plan, DGDC requires the involvement of the people listed below.

Table 18-1: Roles and Responsibilities

Role	Responsibilities
Board of Directors	■ Be familiarized, review and approve the COVID-19 Contingency Plan.
Finance Manager	■ Ensure the availability of resources necessary for the implementation of the COVID-19 Contingency Plan.
Managing Director	■ Be familiarized with, review and update as necessary the COVID-19 Contingency Plan.

Role	Responsibilities
ESG Manager and HR Manager	<ul style="list-style-type: none"> ■ Be familiarized and implement the COVID-19 Contingency Plan. ■ Review, evaluate and verify the COVID-19 Contingency Plan. ■ Review and approve the contractor project-specific COVID-19 Contingency Plan. ■ Update the COVID-19 Contingency Plan.
H&S Manager	<ul style="list-style-type: none"> ■ Review, evaluate and verify the COVID-19 Contingency Plan. ■ Assure the development of an Emergency Preparedness and Response Plan for each Project ■ Present, alongside the Community Liaison Officer, a monitoring report to the Managing Director
Community Liaison Officer	<ul style="list-style-type: none"> ■ Coordinate and supervise the communication of information activities regarding this plan to the affected communities. ■ Present, alongside the H&S Manager, a monitoring report to the Project Manager.
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific COVID-19 Contingency Plan.
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Read and be familiarized with the COVID-19 Contingency Plan. ■ Develop a project-specific COVID-19 Contingency Plan.

18.3 Activities

In the light of the declaration of Public Health Emergency of International Importance (ESPII) by the World Health Organization (WHO) in January 2020, international, national and local health authorities have issued a series of recommendations. DGDC will adopt and recommend preventive and mitigating measures as well as best practices as described below throughout the Project's development and implementation and its corporate activities.

The best practices and recommendations are directed to prevent the spread and contagion of COVID-19 in the work environment and work activities. DGDC is committed to maintain safe working conditions for the people involved in the development and implementation of the Project, especially for those people whose activities and functions require face-to-face action.

18.3.1 DGDC COVID-19 Committee

DGDC will designate an internal COVID-19 Committee to:

- Provide support and information to assist the DGDC Directors' decision-making process regarding crisis management related to COVID-19.
- Define and monitor the guidelines for this Contingency Plan and its updates.
- Call meetings and disseminate the results to all participants.
- Archive the documents generated in the execution of the contingency plan and other actions related to COVID-19.
- Ensure the active participation of all DGDC areas involved in the Committee.

The COVID-19 Committee may suggest the creation of specific Working Groups, including groups between DGDC and its contractors in order to monitor compliance with actions to control the spread of the virus among workers and the community; or other actions such as enabling communication between the Project and contractors and subcontractors, among others.

18.3.2 Monitoring of Normative Acts and COVID-19 Cases

Daily, through the COVID-19 committee and their regulatory and legal areas, DGDC will monitor the measures adopted by the National and Public Administration entities to contain the spread of COVID-19, strengthen the health system and safeguard the economy. All information will be shared on internal communication channels and serve as a reference for adapting measures to prevent and respond to the pandemic internally.

DGDC's COVID-19 committee will monitor the number and location of COVID-19 cases in the world, especially in the Caribbean region, in Dominica, and locally on a daily basis. When necessary, and taking into the account the evolution of the statistics, this Contingency Plan will be further adjusted to prevent and respond to the pandemic in the Project's areas of influence.

18.3.3 Disclosure of Information

DGDC will reinforce the importance of communication and information disclosure and trainings to reduce the risks of COVID-19 both internally (workers and contractors) and for the nearby communities in the Project's areas of influence. DGDC will adopt the following main initiatives:

- Reinforcement of communications and information disclosure on best practices for preventing COVID-19 transmission, especially regarding specific recommendations on social distancing and hygiene measures;
- Training of teams to be able to recognize the COVID-19 symptoms;
- Identification of the Project's focal points and communication channels (WhatsApp, e-mail, internal social network, internal grievance mechanism) to address workers' concerns about COVID-19 on a regular basis;
- Creation of a specific working group in charge of the institutional communication actions between DGDC and its contractors; and
- Adaptation of DGDC's internal communication materials and those of the contractors to distribute them to external stakeholders, as a way of reinforcing social responsibility and the joint work between DGDC and its contractors.

As long as there are preventive measures and recommended guidelines from the health authorities in favor of social distance, DGDC will adhere at all times to those guidelines, including observing social distancing in its interaction with the local community and where practical, replacing in person activities with virtual tools. In addition, DGDC will enable internal communication channels for its workers and its contractors (toll-free phone, email, website and direct communication with DGDC teams) to ensure access and interaction between employees, the local community and the Project when needed.

In addition, while the pandemic continues, DGDC's Stakeholder Engagement activities will also be adjusted to avoid in-person events. DGDC will put a special emphasis to distribute information regarding the external grievance mechanism and other tools to disclose information, such as participating in local radio programs or distributing a newsletter, for more details see the section below.

18.3.4 Social Actions and Community Engagement

As mentioned in Section 18.3.3, as a preventive measure and in order to respect the health authorities' guidelines that recommend social distancing, all activities that require direct contact with the local community will be either postponed or replaced with virtual tools. The External Grievance Mechanism and other available communication channels (toll-free phone, e-mail, website and direct communication with

DGDC teams) will continue to function normally. When possible, DGDC will collaborate with the local authorities to contribute to the fight against the spread of COVID- 19.

In order to have a positive impact in reducing the pandemic cycle, from prevention to response, DGDC plans to implement the following lines of action:

- **Disclosure of Information:** In order to prevent the spread of COVID-19, DGDC will disseminate clear and accurate information and guidance documents, using simple and accessible language to reach the largest number of people;
- **Support health professionals:** Should PPE for health professionals be needed, DGDC will consider contributing on this line of action as a response to the epidemic;
- **Support the most vulnerable population in the AOI:** One of the side effects of the pandemic is the economic crisis, mainly affecting the population in a situation of socioeconomic vulnerability. DGDC aims to contribute with actions specifically aimed at the vulnerable groups located in the Project's AOI.

18.3.5 Identification of Essential Activities to Begin and Continue the Project

DGDC aims to identify and define the services and activities essential to begin and continue the Project, considering activities of design, pre-construction and construction, and if applicable later on for the operations phase by monitoring the evolution of the pandemic, the competent authorities' guidelines, regulatory aspects, recommendations from shareholders and financiers, among others. Furthermore, attention will be given to technical criteria regarding the number of workers needed without compromising the practice of social distancing and the preservation of everybody's health and safety throughout the different activities.

18.3.6 Social Distancing Measures

Scientific studies have demonstrated there is a spread of expelled micro droplets, not only during sneezing or coughing, but also during human speech, capable of carrying the virus over long distances, especially in closed and poorly ventilated environments. Consequently, DGDC will implement strict social distancing measures, preferably 2 meters (6 feet apart), in all activities and environments, including transportation, accommodation, cafeterias, bathrooms, meeting rooms, and workstations, in order to minimize the potential COVID-19 contagion.

Social distancing measure will also be implemented for the field and construction activities. Thus, as a good practice for the continuity of the activities considered essential during the emergency period, it is advisable that the contractors (especially EPC directly involved in the implementation of the Project) act in order to respect the 2 meters-social distancing in all their activities. Social distancing in the field and construction areas is considered critical and necessary to maintain optimal health and safety conditions at the Project during the emergency period and avoid exposure and contagion of workers. All activities in closed environments with little ventilation will be forbidden. The following specific measures will be adopted in order to implement health and safety guidelines at work:

- Maintain a safe distance (2 meters between people) in places where people work or meet regularly.
- Identify all places where people normally work within 2 meters of each other and adjust those areas to meet the safe distancing requirements, as well as establishing a regular inspection routine in offices, control rooms, meeting rooms, construction sites, work fronts. A checklist and photographic records will be completed in order to confirm adherence. In places where 2 meters of spacing cannot be reached, the possibility of expanding the workplace in previously vacant areas or placing acrylic dividers between workplaces will be evaluated.
- Increase the frequency of cleaning and spacing of sanitary appliances and offices.

- Install marks or signs on the floor, indicating safe distances, where people normally wait in lines (access to buses, time clock, cafeteria, among others).
- Expand the use of videoconferencing to replace face-to-face meetings, safety dialogues and trainings, as well as the possibility of distributing videos of HSE campaigns to workers and contractors through WhatsApp and DGDC social networks.
- Establish alternate working days or extra shifts to reduce the total number of workers at any given time, allowing workers to maintain the recommended distance between them and, at the same time, ensuring the completion of work activities and comply with the construction schedule.

18.3.7 Activity Security Analysis and Work Permit

Based on the field activities' assessment, those considered critical and necessary to start during this emergency period will need to reinforce in the routine of such activities the need to avoid exposure of workers to social proximity less than 2 meters (whenever possible) and precautionary measures for carrying out activities in closed environments, such as places with poor ventilation. Each activity will be described in the Activity Safety Analysis and, eventually, in the Work Permit. These documents will be completed as evidence of the application of COVID-19 preventive measures at work.

18.3.8 Control Measures and Working Conditions

DGDC will distribute surveys to identify the workers' physical and health conditions to prevent potentially ill workers from feeling under pressure to show up for work, risking the transmission of the virus to the rest of the workforce. The surveys will contain a simple checklist with information on the workers' conditions, which can be confirmed by establishing a routine inspection.

In addition, DGDC and its subcontractors will ensure that their employees have access to in-person or remote medical consultation services (by phone or video call) if they encounter COVID-19 symptoms. DGDC will closely collaborate with local authorities to benefit its workers and the local community.

DGDC and its contractors will provide and enforce face protection masks for all people in the working areas. DGDC will specify the type of mask required, the replacement frequency and will provide appropriate training. DGDC and its contractors will make 70% alcohol gel available in all working areas.

18.3.9 Food Supply and Preparation Measures

DGDC will evaluate the possibility of hiring meal delivery services from local restaurants that have already been mapped and previously contacted. DGDC will also let employees bring their own meals from home if preferred.

18.3.10 Control Measures for Mobilizing Workers

If mobilization of workers from other communities or regions is required for the Project, both DGDC and its contractors will take the following measures:

- Lists of workers and their arrivals will be reviewed at least 7 days in advance, to analyze the workers that might come from high-risk areas (areas with higher community transmission rates). These cases must be subjected to prior isolation for 15 days before starting work and access the Project area or nearby community.
- Monitor the list of workers, indicating the city of origin, estimated start of work and address at which the worker(s) will be kept in isolation.

- Ensure that when accessing to the Project area, all workers are wearing identification badges and essential service documentation.

DGDC will observe the travel restrictions imposed by the local, national and international authorities, as well as the recommendations of the health authorities. DGDC will implement the following protocols about mobilization and travel for its employees:

- International Corporate travel: suspension of international corporate travel. Any exceptions to the recommendations described here will be dealt on a case-by-case basis and aligned with the authorities' guidelines, as well as approved directly by the DGDC Managing Director.
- Private trips: workers shall inform HR about their private trips by email and/ or phone.

18.3.11 Control Measures for potential Workers' Accommodations

DGDC does not expect to have a significant number of workers that will need accommodation, as the Project will focus on hiring locally. Nonetheless, workers who need accommodation, will be either placed in hotels or rented homes.

The following best practices will be applied in the workers' accommodations:

- Promoting, respecting and applying occupancy density limits in workers' accommodation;
- If new workers arrive from countries or areas with high COVID-19 risk, these people will have to complete a proper quarantine in accordance with local regulations and/ or recommendations of relevant international organizations;
- Whenever possible, the accommodation coordinator or the persons in charge of managing the accommodation will coordinate the daily health and safety measures of the residents, such as taking the persons' body temperature with thermometers to prevent contagion;
- Carry out the necessary measures and efforts in order to ensure that all workers have access to medical professionals, including adopting measures that remove possible language barriers, in the case of foreign workers.
- Provision of hand soap for workers in all bathrooms, as well as the adoption rigorous daily cleaning routine.
- Implement the necessary measures and efforts in order to ensure that door handles, taps, TV/ media devices, kitchen equipment, controls, buttons and any other common objects located in the areas that are touched regularly are cleaned several times a day. The cleaning frequency will be determined by each installation. Likewise, ensure that necessary measures are taken to ensure that common surfaces, including those on vehicles that transport workers from their accommodations to the workplace, counters, floors and walls, will be treated as potentially contaminated areas and therefore will be cleaned regularly.
- Keep a minimum distance of 2 meters between the beds, as well as reducing the number of people in a single room, when possible let only one person per bedroom.
- Carry out actions to maximize natural or forced ventilation within the limitations of comfort, safety and privacy, as well as considering any changes in the installation to allow ventilation during working hours.
- Mandatory use of a mask, also during off-hours. Additionally, exits that are not for the purpose of essential needs should be avoided, and it is important to have clear rules for the use of common areas in the accommodation.

18.3.12 Preventive Measures for Drinking Water Supply, Sanitation and Solid Waste Management

This section presents the main guidelines to prevent the contagion of COVID-19 through the drinking water supply, sanitary sewage and solid waste management services in all DGDC activities and its contractors (offices, construction sites, work areas). The content was adapted from the Interim guide about Water, sanitation, hygiene, and waste management for COVID-19, published on March 19, 2020 by the World Health Organization, considering the DGDC context and characteristics.

18.3.12.1 Safe Water Supply

DGDC will take several measures to improve the water supply, by protecting the water source; treat water at the point of distribution, collection or consumption; and ensure that treated water is safely stored at the DGDC facilities in regularly cleaned and covered containers.

For effective centralized disinfection, there must be a residual concentration of free chlorine of ≥ 0.5 mg / L after at least 30 minutes of contact time at pH <8.0. A chlorine residual must be maintained throughout the distribution system.

18.3.12.2 Safe Management of Waste Water and Feces Waste

Best practices to protect the health of workers in sanitation treatment facilities must be followed. Workers must wear appropriate personal protective equipment (PPE), which includes protective clothing, gloves, boots, glasses or face shield and mask; they must wash their hands frequently; and avoid touching their eyes, nose and mouth with unwashed hands.

18.3.12.3 Hand Hygiene

Hand hygiene is extremely important. Hand cleaning with soap and water or an alcohol-based hand scrubber will be carried out according to the instructions as stated in “My 5 moments for hand hygiene” (WHO, Infection prevention and control) available at <https://www.who.int/infection-prevention/campaigns/clean-hands/5moments/en/>.

When the hands are not visibly dirty, the preferred method is to perform hand hygiene with alcohol (rub your hands for 20 to 30 seconds using the appropriate technique). When hands are visibly dirty, they will be washed with soap and water for 40 to 60 seconds using the appropriate technique. Hand hygiene must be carried out before putting on the PPE and after removing it, when changing gloves, after any contact with a patient with suspected or confirmed COVID-19 infection or its residues, after contact with some respiratory secretion, before eating and after using the bathroom.

Functional facilities to wash the hands must be present for all workers throughout the Project site and in areas where PPE is placed or removed. These facilities must be available within 5m of bathrooms, as well as in public areas.

18.3.12.4 Cleaning Practices

The recommended cleaning and disinfection procedures must be followed consistently and correctly. Clothes will be washed and surfaces in all environments will be cleaned at least once a day. Many disinfectants are made to kill viruses, such as COVID-19, including commonly used hospital disinfectants. WHO currently recommends the use of:

- 70% ethyl alcohol to disinfect small areas between uses, such as dedicated reusable equipment (for example, thermometers);
- 0.5% sodium hypochlorite (equivalent to 5000 ppm) for disinfecting surfaces.

18.3.12.5 *Disposal of Dirty Water from Washing PPE, Surfaces and Floors*

The WHO recommends to clean public utility gloves or heavy reusable plastic aprons with soap and water and decontaminate them with 0.5% sodium hypochlorite solution after each use. Disposable gloves (nitrile or latex) and aprons must be discarded after each use and not reused; hand hygiene will be performed after removing the PPE. If the gray water includes disinfectant used in the previous cleaning, it will not need to be chlorinated or treated again. However, it is important that this water be discharged into drains connected to a septic or sewer system or into a drainage well. If gray water is discharged into a submerged pit, the pit will be enclosed within the health facility to prevent tampering and to avoid possible exposure in the event of an overflow.

18.3.12.6 *Sanitation and Hygiene Practices at Homes, Accommodations and Communities*

Maintaining best practices for drinking water supply, sanitation, hygiene and solid waste management at home and in communities near the Project is also important to prevent the spread of COVID-19 and to care for patients at home. Regular and correct hand hygiene is of particular importance.

- Hand Hygiene:

Regular hand washing is one of the most important measures that can prevent COVID-19 infection. In homes, schools and crowded public spaces - such as markets, places of worship, train or bus stations, regular washing of hands will occur before preparing food, before and after eating, after using the bathroom or changing a child's diaper and after touching animals. Functional hand washing facilities with soap and water must be available within 5 meters of the bathroom.

- Other recommendations:

The safe management of human excreta will be considered, starting with ensuring access to regularly cleaned, accessible and functioning toilets or latrines, as well as containment, transportation, treatment and eventual disposal of sewage.

When there are suspected or confirmed cases of COVID-19 in the home environment, immediate measures will be taken to protect healthcare professionals and other family members from the risk of contact with respiratory secretions and excrement that may contain the COVID-19 virus.

Surfaces that are touched frequently throughout the patient care area will be cleaned regularly, such as next to tables, beds and other bedroom furniture. Bathrooms will be cleaned and disinfected at least once a day. Regular household soap or detergent will be used for cleaning first and then, after rinsing, a common household disinfectant containing 0.5% sodium hypochlorite (i.e. equivalent to 5000 ppm or household bleach with 1 part hydrochloride sodium to 5% water and 9 parts water) be applied. PPE will be used while cleaning, including wearing a mask, goggles, liquid-resistant apron and gloves, and hand hygiene with a hand rubbing alcohol or soap and water will be carried out after removing the PPE.

18.3.12.7 *Rapid Tests to Diagnose COVID-19*

Rapid antibody tests for the new coronavirus (Sars-CoV-2) can be used to support the assessment of the immune status of workers who have symptoms of COVID-19. This type of examination indicates whether or not the person had contact with the virus, through the detection of antibodies produced as a defense mechanism of the organism. According to ANVISA (<http://portal.anvisa.gov.br/coronavirus>), the examination is done using blood, serum or plasma samples. The method used is called immunochromatography, which is the generation of color from a chemical reaction between antigen (substance foreign to the organism) and antibody (defense element of the organism). The results obtained

are called IgM and IgG. IgM and IgG are the body's defenses against an external agent, such as the virus that causes Covid-19.

DGDC contractors will perform rapid tests for the diagnosis of COVID-19 following technical criteria that consider good industry practices, guidance to health agencies and specificities of each service provision contract (e.g. location, duration, occupational risks, number mobilized workers, and need for accommodation). The following testing strategy is suggested:

- Monitoring of workers who might need testing by applying a rapid test every 15 days;
- Application of a rapid test to all non-local workers after a quarantine period of 15 days of arrival on island;

All suspected cases will be referred to the local health authorities as per national guidelines.

18.3.12.8 *Internal Grievance Mechanism and Employment Protection*

Within the measures related to the pandemic period, it is important to note the need and concern of DGDC to protect its employees, their jobs and health and safety. DGDC will also emphasize this to its contractors, to take the necessary care so that the employment protection measures are also applied to their employees, reducing the workers' general insecurity and concerns in the pandemic scenario.

The internal grievance mechanism will be monitored regularly in order to identify claims and concerns regarding COVID-19 or any grievance related to the pandemic circumstances.

DGDC will avoid layoffs, and will only use layoffs as a last resort. DGDC will adopt government measures and policies issued in the context of this public crisis to reduce employer costs, while ensuring the maintenance of jobs. DGDC will maintain a constant communication with workers and their representatives to understand their demands and insecurities in order to periodically review internal contingency plans to guarantee the continuity of the Project's activities, as well as their job security.

18.3.13 *Measures for the Office Spaces*

DGDC will adopt specific corporate preventive and mitigating measures at the offices in the Project and for its subcontractors, if applicable.

18.3.13.1 *Preventive Measures at Work*

DGDC will reinforce all guidelines and recommendations for medical health and hygiene care in the work environment, especially in the corporate environment. DGDC will disclose information through its communication channels, as well as constantly refilling the alcohol gel containers placed in different locations of the DGDC offices and working areas for the hygiene of its employees and people who have access to DGDC facilities.

More frequent cleaning will take place in areas where exposure to possible contamination is higher, such as meeting rooms, pantry, bathrooms, material/ work equipment, etc. In cases when a suspected case of contamination is reported or confirmed, a thorough cleaning process will be carried out.

DGDC will take the individual body temperature using digital infrared thermometers, twice a day. If the temperature is 37.7°C or above, preventive social isolation measures, medical assistance and monitoring will be recommended.

DGDC will disclose information constantly, including Health and Safety guidelines for employees and contractors, on hygiene measures to prevent the spread and contagion of the virus, such as washing hands with soap and water or alcohol gel whenever possible, maintain preventive social isolation and avoid greeting with a hand or hug.

If a worker suffers any of the symptom associated with COVID-19 (fever, cough, difficulty breathing), the employee will be instructed to stay at home and contact the health teams available to assist employees and their families. Workers shall also inform the Human Resources team, by email and/ or telephone. The HR team shall provide the necessary support and immediate referral to medical care, whenever this is recommended by the medical evaluation. HR is responsible for gathering and controlling the employees' information related to symptoms and / or suspicious cases, as well as monitoring their situation during the duration of the contingency period.

18.3.14 *Management of Meetings or Events*

DGDC and its contractors' organizers of meetings and events will be required to evaluate the need and potential risk from a COVID-19 infection due to:

- The risk of people attending the meetings or event might be unwittingly bringing the COVID-19 virus to the meeting. Others might be unknowingly exposed to COVID-19.
- While COVID-19 is a mild disease for most people, it can make others very sick and even risk their lives. Around one of every five people who are infected with COVID-19 need hospital treatment.

Key considerations to prevent or reduce COVID-19 risks in meetings or events:

BEFORE the meeting or event DGDC and its contractors will:

- Double-check the authorities' advice where the meeting or event takes place. DGDC and its contractors will follow the official guidance and advice.
- Develop and agree a preparedness plan to prevent infection at the meetings or events.
- Consider whether a face-to-face meeting or event is needed. Should the face-to-face meeting or event be replaceable, DGDC and its contractors must choose a teleconference, videoconference or any other online mean for such meeting or event.
- Evaluate the number of people for the meeting or event is required. In case of the number of attendees could potentially be lower, the number of people will be reduced even further.
- Ensure and verify information and communication channels in advance with key partners such as public health and health care authorities.
- Pre-order sufficient supplies and materials, including tissues masks and hand sanitizer for all participants.
- Advise participants in advance that if they have any symptoms or feel unwell, they are not allowed to attend.
- Make sure all organizers, participants, caterers and visitors at the event provide contact details: mobile telephone number, email and address where they are staying. State clearly that their details will be shared with local public health authorities if any participant becomes ill with a suspected infectious disease. If they disagree with these measures, they will not be allowed at the event or meeting.
- Develop and agree a response plan before the meeting occurs, in case someone at the meeting becomes ill with symptoms of COVID-19 (dry cough, fever, malaise). This plan will include at least:
 - Identification of a room or area where someone who is feeling unwell or has symptoms can wait alone (no contact with other coworkers or meeting participants) until he/she can be safely evacuated or transferred to receive proper medical attention.
 - A plan for safely transfer meeting participants with symptoms, or meeting participants that have had contact with someone who is confirmed to have the disease, to a health facility.

- DGDC will make its best efforts to identify meeting participants who might have a higher risk factor or be more affected/sensitive to the disease, for instance people older than 60 years old, pregnant women, people with chronic diseases such as a cardiovascular illness, diabetes, or any other condition advised by the governmental authorities. This type of personal information will be kept as confidential and obtained based on medical records. People with this kind of conditions will not participate in meetings.
- Inform local authorities if a meeting participant, staff member or service provider appears to have COVID-19 symptoms during or just after the meeting.

DURING the meeting or event:

- The organizers will provide information or a briefing, preferably both orally and in writing, on COVID-19 and the measures that have been taken to make the event safe for participants, such as:
 - Avoid touching common surfaces.
 - Encourage regular hand washing or use of an alcohol rub by all participants at the meeting or event.
 - Encourage participants to cover their face with the bend of their elbow or a tissue if they cough or sneeze. Supply tissues and closed bins to dispose of them in.
 - Provide contact details or a health hotline number that participants can call for advice or to provide information.
 - Display dispensers of alcohol-based hand rub prominently around the venue.
- If there is space, arrange seats so that participants are at least two meters apart.
- Open windows and doors whenever possible to make sure the venue is well ventilated.

AFTER the meeting:

- Organizers will retain the names and contact details of all participants for at least one month. This will help public health authorities trace people who may have been exposed to COVID-19 if one or more participants become ill shortly after the event.
- If someone at the meeting or event was transferred to a room alone without any contact with other persons as a suspected COVID-19 case, the organizer will let all participants know this. They will be advised to monitor themselves for symptoms for 15 days and take their temperature twice a day.
- If someone develops even a mild cough or low-grade fever (i.e. a temperature of 37.3 C or more) will stay at home and self-isolate. This means avoiding close contact (2 meters or nearer) with other people, including family members. They will also call their healthcare provider to give them details of their recent travel and symptoms.
- The room where the meeting or event took place shall be cleaned and disinfected thoroughly.

18.3.15 *Visitors*

DGDC will not allow visitors at the Project sites or offices for an indefinite period until the COVID-19 pandemic is resolved. Any exceptions to the recommendations described here must be dealt with on a case-by-case basis and approved directly by the DGDC's Managing Director.

18.3.16 Remote Work (Home Office)

If possible, and to prevent the spread of the virus, DGDC will enable remote work (home office) for employees that solely carry out administrative activities at the Project, in order to maintain a minimum number of employees in the office, whose activity is related to functions that cannot be performed remotely.

DGDC will generally consider these three case scenarios:

1. Employees whose remote presence severely impacts the continuity of DGDC's activities, with the physical presence of the employee being indispensable, even in the contingency scenario.
2. Employees whose remote presence impacts the continuity of DGDC's activities, making it possible to work in the home office.
3. Employees whose remote presence has a slight impact on the continuity of DGDC's activities, making it possible to work in the home office.

The assessment of remote work (home office) requests will also take into account the higher-risk groups who could suffer from more severe consequences of a possible viral contamination, such as, older employees (over 60 years old), employees with pre-existing respiratory diseases or immunodepressants, employees who live with elderly people or with family members who suffer from respiratory diseases, or immunodepressants.

The remote work options will be evaluated and resized, with the possibility of implementing a rotation system among employees allocated within each level, depending on work demands, in order to guarantee the continuity of activities and workers' safety.

DGDC will provide the appropriate infrastructure for remote work, such as laptops and access to DGDC's virtual private network by employees, which shall include the company's internal systems, file sharing networks and platforms for electronic timekeeping. Employees will have support from the Project's IT services for remote access.

18.4 Documentation and Monitoring

The Human Resources Manager and Health and Safety Manager will be responsible for the implementation of what is stated in this plan and will keep evidence of it (e.g. checklists, COVID-19 cases at the Project, working conditions, internal grievance mechanism, workers who come from other communities, etc.).

18.5 Key Performance Indicators

The COVID-19 Contingency Plan is to be reviewed on a monthly basis until the pandemic is resolved in consultation with the Human Resources Manager and Health and Safety Manager. The Project will ensure that contractors update their procedures as needed.

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 18-2: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
Health and Safety Conditions at Work	Availability of preventive COVID-19 material (cleaning products, disinfectant, masks, gloves, alcohol gel, etc.)	All Project areas shall have cleaning materials and available PPE at all times.	Until the pandemic is resolved.	Human Resources, Internal Grievance Mechanism and Health and Safety Manager / Daily
	Hand hygiene facilities	One sink available to wash the hands per 20 workers. Alcohol gel available in all Project areas at all times.	Until the pandemic is resolved.	
	Internal Grievance Mechanism	100% reported, evaluated and solved grievances regarding COVID-19 claims or concerns	Until the pandemic is resolved.	

19. CHANCE FIND PLAN

19.1 Introduction

This Chance Find Procedure complies with Dominica laws and ESIA commitments and aligns with international standards for the protection of cultural heritage. It includes a Cultural Heritage Monitoring Program, Chance Find Plan, Cultural Heritage Training Program, and Site Protection Program, as detailed in the sections below.

19.1.1 Objective

This Chance Find Plan has the following objectives:

- To protect known cultural heritage from Project-related impacts; and
- To properly identify and mitigate impacts to cultural heritage inadvertently discovered during ground-disturbing construction activities (i.e., chance finds).

19.1.2 Scope of Application

This Chance Find Procedure applies to all Project activities that involve ground-disturbing activities.

19.2 Roles and Responsibilities

The Table below presents the roles and responsibilities for the implementation of this Chance Find Procedure.

Table 19-1: Roles and Responsibilities

Role	Responsibilities
ESG Manager	<ul style="list-style-type: none">■ Implementation of the Cultural Heritage Monitoring Program, including contracting an on-call Cultural Heritage Specialist.■ Implementation of the Chance Find Procedure, including notification of chance finds to relevant governmental authorities and cultural heritage stakeholders.■ Implementation of the Cultural Heritage Training Program, including ensuring that workers involved in ground-disturbing activities are properly trained in the identification of chance finds and implementation of the Chance Find Procedure.■ Implementation of the Site Protection Program, including ensuring that the Hamilton Estates sugar work ruins are properly marked with flagging tape and signs throughout the construction phase.
Cultural Heritage Specialist (On call)	<ul style="list-style-type: none">■ Evaluation of potential chance finds.■ Development of chance find treatment plans in consultation with governmental authorities and cultural heritage stakeholders.■ Implementation of chance find treatment plans.■ Reporting on the results of chance find evaluations and on the implementation of chance find treatment plans.

19.3 Regulatory Background

19.3.1 National Requirements

Neither the DGDC nor the EPC will disturb any chance finds further until a competent specialist (Cultural Heritage Specialist) appointed by either the Ministry of Youth, Sports, Culture and Constituency Empowerment, or the Dominica Museum has assessed the situation and actions identified the appropriate

measures to be taken. The DGDC will liaise closely with the GoCD and the EPC to ensure that the assessment and recommended actions are carried out in a manner that will not be prejudicial to the planned works.

Upon discovery of a physical artefact work will be stopped, the site will be fenced and procedures for reporting will commence. Following internal reporting, the first external notification will be to the GoCD Ministry of Youth, Sports, Culture and Constituency Empowerment, followed by the Dominica Museum in Roseau.

19.3.2 International Standards

The principal international standard for the protection of cultural heritage is Performance Standard (PS) 8 (Cultural Heritage) of the International Finance Corporation (IFC) Performance Standards on Environmental and Social Sustainability (2012). The objective of PS 8 is to “protect cultural heritage from the adverse impacts of project activities and support its preservation... [and] promote the equitable sharing of benefits from the use of cultural heritage.” PS 8 defines cultural heritage as:

- Tangible forms of cultural heritage, such as tangible moveable or immovable objects, property, sites, structures, or groups of structures, having archaeological (prehistoric), paleontological, historical, cultural, artistic, and religious values;
- Unique natural features or tangible objects that embody cultural values, such as sacred groves, rocks, lakes, and waterfalls; and
- Certain instances of intangible forms of culture that are proposed to be used for commercial purposes, such as cultural knowledge, innovations, and practices of communities embodying traditional lifestyles.

PS 8 differentiates between replicable, non-replicable, and critical cultural heritage, which are defined as follows:

- Replicable Cultural Heritage: Defined as “tangible forms of cultural heritage that can themselves be moved to another location or that can be replaced by a similar structure or natural features to which the cultural values can be transferred by appropriate measures. Archaeological or historical sites may be considered replicable where the particular eras and cultural values they represent are well represented by other sites and/or structures.”
- Non-replicable Cultural Heritage: Includes “(i) cultural heritage [that] is unique or relatively unique for the period it represents; or (ii) cultural heritage [that] is unique or relatively unique in linking several periods in the same site.”
- Critical Cultural Heritage: Includes “(i) the internationally recognized heritage of communities who use, or have used within living memory the cultural heritage for long-standing cultural purposes; or (ii) legally protected cultural heritage areas, including those proposed by host governments for such designation.”

The preferred mitigation measure for all cultural heritage impacts is avoidance. When this is not possible, PS 8 provides the following mitigation hierarchy (from preferred to least preferred) for replicable cultural heritage:

- Minimize adverse effects and implement in situ restoration measures;
- Restore the functionality of the cultural heritage in a different location;
- Permanent removal of historical and archaeological artifacts following national laws and internationally recognized practices by competent professionals; and
- Compensation for the loss of cultural heritage.

The removal of non-replicable cultural heritage will only take place if there is no technically or financially feasible alternative and the benefits of the project outweigh any heritage losses. The removal of critical cultural heritage will only take place in “exceptional circumstances” and after extensive consultation with affected communities and other stakeholders.

PS 8 also requires the development and implementation of chance find procedures. Chance finds are defined as “tangible cultural heritage encountered unexpectedly during project construction or operation,” and a Chance Find Procedure is defined as “a project-specific procedure that outlines the actions to be taken if previously unknown cultural heritage is encountered.” The requirement is a recognition of the fact that no survey, regardless of methodology, is sufficient to ensure that all archaeological resources are identified in a project area, and that there is therefore always the potential for the inadvertent discovery of cultural heritage during ground-disturbing construction or operational activities.

According to the IFC Guidance Note 8, the Chance Find Procedure will “include record keeping and expert verification procedures, chain of custody instructions for movable finds, and clear criteria for potential temporary work stoppages that could be required for rapid disposition of issues related to the finds. It is important that this procedure outlines the roles and responsibilities and the response times required from both project staff, and any relevant heritage authority, as well as any agreed consultation procedures. The procedure will be incorporated into the Management Program and implemented through the client’s Environmental and Social Management System.”

19.4 Cultural Heritage Monitoring Program

Current baseline information collected by Caraïbes Environnement Développement & Coll in 2015 identified some culturally significant aspects in the Roseau Valley, including those related to agricultural heritage and architectural heritage.

DGDC will implement a Cultural Heritage Monitoring Program for all construction activities in consultation with the GoCD Ministry of Youth Sports, Culture and Constituency Empowerment (Ministry) and other cultural heritage stakeholders (the Dominica Museum in Roseau), as appropriate. The purpose of this monitoring is to:

- Identify, record, and protect cultural heritage that has not been previously identified (i.e., chance finds); and
- Protect cultural heritage identified during previous cultural heritage investigations (i.e., known resources).

The program will utilize “passive” cultural heritage monitoring. Passive monitoring means that there will be no Cultural Heritage Specialist on site during construction. Instead, all Project and contractor personnel are responsible for cultural heritage monitoring during their daily activities. Relevant Project and contractor staff will receive training in the identification of potential chance finds and the Chance Find Procedure described below, and will be responsible for reporting any potential chance finds to the ESG Manager. The ESG Manager will then report the potential chance finds to a CHS to be retained by the Project (i.e., on call).

19.5 Chance Find Procedure

The following types of cultural heritage are the most likely to be encountered during construction:


- Pre-Columbian archaeological features (e.g., habitations, hearths, burials);
- Pre-Columbian artifacts (e.g., ceramic sherds, stone tools);
- Historic archaeological features (e.g., brick wells and foundations); and

- Historic artifacts (e.g., clay pipes, bottle fragments and coins).

The Chance Find Procedure will use a multi-tiered approach for identifying, assessing, and resolving potential chance finds. The purpose of this approach is to empower the Cultural Heritage Specialist to resolve minor chance finds without requiring consultations with the Ministry and minimize construction delays by allowing for the quick resolution of non-significant finds by the Cultural Heritage Specialist in the field. The defining characteristics of each chance find tier and the processes for assessing them and determining if consultation is required will be developed in consultation with the Ministry and other cultural heritage stakeholders, as appropriate. A preliminary three-tiered chance finds hierarchy is presented in Table 19-2. All potential chance finds identified by Project personnel will be reported to the ESG Manager, who will then notify an on-call Cultural Heritage Specialist. The Cultural Heritage Specialist will determine if the potential find is a chance find and assign it to a chance finds tier. Figure 19-1 provides a flowchart of the Chance Find Procedure.

Table 19-2: Three-tier Chance Find Hierarchy

Chance Find Type	Characteristics	Evaluation Process
Minor Chance Finds	Modern features or objects. Isolated historic or prehistoric artifacts that are out of context or lack research potential or value.	Construction work will stop in the area of the find. The potential find will be reported to the ESG Manager, who will then notify the on-call Cultural Heritage Specialist, within 24 hours. The Cultural Heritage Specialist will then examine the potential find via photographs or a site visit. If the find is determined to represent a minor chance find, the find will be documented and collected/resolved in the field by the Cultural Heritage Specialist without Ministry consultation. Construction activities will then resume in the area.
Significant Chance Finds	Significant historic or prehistoric features or artifacts.	Construction work will stop in the area of the find. The potential find will be reported to the ESG Manager, who will then notify the on-call Cultural Heritage Specialist, within 24 hours. The Cultural Heritage Specialist will then conduct a site visit to examine the potential find. If the find is determined to represent a significant chance find, the Cultural Heritage Specialist will notify the Ministry within five days. The Cultural Heritage Specialist will develop a treatment plan in consultation with the Ministry. Construction activities will resume in the area upon completion of the Ministry-approved treatment plan.
Human Remains	Modern, historic, or prehistoric burials, isolated human remains, and/or associated features and/or artifacts (i.e., grave goods).	Construction work will stop in the area of the find. The potential find will be reported to the ESG Manager, who will then notify the on-call Cultural Heritage Specialist, within 24 hours. The Cultural Heritage Specialist will then conduct a site visit to examine the potential find. If the find is determined to represent modern human remains, the Cultural Heritage Specialist or ESG Manager will notify local, regional, or national law enforcement agencies. If the find is determined to represent archaeological human remains and/or burial goods, the Cultural Heritage Specialist will report the find to the Ministry within five days. The Cultural Heritage Specialist will develop a treatment plan in consultation with the Ministry and other stakeholders (e.g., potential descendent communities), as appropriate. Construction activities will resume in the area upon investigation and removal of the remains by law enforcement (modern) or completion of the Ministry-approved treatment plan (archaeological).



*CHS = Cultural Heritage Specialist

Figure 19-1: Chance Find Procedure Flowchart

Artifacts collected in connection with chance finds will be minimized. Photos of artifacts with a scale included in the frame will be taken as soon as possible. Artifacts and associated notes and photographs taken by any Project personnel will be given to the Cultural Heritage Specialist. Details of how artifacts will be collected and stored and what notes and photographs will be taken at the time of discovery will be provided in the Cultural Heritage Training. Artifacts found belong to the government of Dominica, and the Cultural Heritage Specialist will be responsible for giving them to the appropriate Ministry.

The Cultural Heritage Specialist and the ESG Manager will maintain records on chance finds and the implementation of management plans. These will include:

- Monthly reports summarizing reporting period activities, including chance finds identified, the results of any chance find assessments, internal and external communications and instructions, and supporting photographic documentation (or other reference materials as appropriate); and
- Any additional reports prepared to fulfil specific requirements of the Ministry.

19.6 Cultural Heritage Training Program

Relevant Project personnel will receive training and demonstrate competency in the identification of chance finds and the Chance Find Procedure described above. This training will be incorporated into the overall induction process for Project and contractor personnel, and will include a quick reference handout. The ESG Manager will maintain records of all Cultural Heritage Training provided to Project personnel.

All employees must be aware that it is illegal and forbidden to disturb or remove cultural heritage objects offsite for personal gain. To support the training process, the Project will develop training materials for use in the overall induction process.

19.7 Site Protection Program

Known cultural heritage sites will be protected from Project-related damage. This includes sites identified in advance of construction activities (if any) and those found during construction (i.e., chance finds). Sites may be located in Project areas or adjacent to them. In some cases, it may be necessary to modify construction techniques to protect sites in work areas. Site information will be provided to Project personnel in written and verbal form in official transmittals, meetings, and toolbox talks as appropriate to ensure that known cultural heritage sites are protected.

The following procedures will be followed for protecting archaeological resources located within the Project area (i.e., significant chance finds), when required by the Ministry, and for known archaeological sites located adjacent to or near ground-disturbing construction activities:

- The perimeter of the archaeological resource or site will be marked with high-visibility caution tape;
- Signs will be posted that the marked area is a protected archaeological site and that entry with mechanized vehicles is prohibited; and
- When ground-disturbing activities in the area are concluded, the caution tape and sign will be removed.

19.8 Key Performance Indicators

Table 19-3 presents the key performance indicators that will evaluate the implementation of this Chance Find Plan.

Table 19-3: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool / Frequency
Disturbance of Archaeological Remains	Number of chance finds encountered, evaluated, and treated	100% evaluation of potential chance finds 100% treatment of significant chance finds and archaeological human remains	Construction	Quarterly Reports
	Cultural Heritage Training of workers involved in ground-disturbing construction activities	100% of workers trained	Construction	Quarterly Reports

20. TRANSPORTATION MANAGEMENT PLAN

A Transportation Management Plan establishes measures to minimize the effects of the Project's construction and operations on traffic, road infrastructure, and accident risk within the Area of Influence. An Operational Health and Safety Plan which includes Traffic Management Procedures was prepared by DGDC. The Plan can be downloaded at: https://geothermaldominica-my.sharepoint.com/:w:/g/personal/admin_geodominica_com/EWke9HU0IM1lhZR75oRu0x8BUE7KaEzKt-swWcXzzT4bFA?e=6YRBrF

21. TRAINING PLAN

21.1 Introduction

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the implementation of the Environmental and Social Management Plan policies and procedures.

To promote the Project's alignment to best international practices, DGDC acknowledges that all personnel involved in the project, during both the construction and operation phases of the project, must be trained in order to ensure compliance with all of the requirements of the ESMP. This Training Plan compiles all of the training requirements detailed throughout the individual management plans specifically developed for all workers, including contractors and subcontractors.

21.1.1 Objective

The objective of this plan is to provide a quick reference guide which compiles all of the training requirements detailed throughout the individual Project's ESMP. The purpose of the required training is to ensure all Project personnel and their contractors are trained in all health, safety, environmental, social and Emergency Response procedures and requirements. All contractors, including their workers, will be responsible for complying with this Plan, as well as executing the works in accordance with current environmental and safety regulations. The specific objectives of the training requirements in the ESMP are:

- To be aware of the legal framework;
- To become familiar with International Standards, such as the IFC Performance Standards, and any other standards pertaining to the Project;
- To know the relevant aspects of environmental and social management in all Project activities and promote their implementation;
- To train technical personnel in relation to threats, possible risk situations, in order to adopt strategies to reduce the effects on the different processes, communities and resources in the area of influence; including potential accidents associated with the construction, operation and maintenance of the Project components;
- Train staff on environmental issues including the concept of non-hazardous and hazardous waste management including the implementation of the five (5) "Rs" (reuse, recycle, reduce, repair, reject) where appropriate, water conservation, and wildlife protection;
- Encourage an environmental culture in all Project workers, including staff sensitization on the importance of environmental sustainability;
- Train staff on social issues that include, for example, gender aspects, grievance mechanisms, workers' code of conduct, among others; and
- Train staff on health and safety matters.

21.1.2 Scope of Application

These procedures shall apply during the development of DGDC's activities and during the Project's life cycle (construction, operations and decommissioning). It is DGDC's responsibility to ensure that Employees, Contractors and Subcontractors are evaluated according to ESMS policies and procedures, which are aligned to international best practices.

This Training Plan provides training requirements related to all Project activities. This plan shall be distributed to all contractors / subcontractors, and it shall be included in all contractual documentation and used as a basis for all specific training of engaged parties. Contractors will use this plan and develop their specific training protocols to meet the various requirements of the Project’s ESMP and how they will be applied on the ground. DGDC will review and approve these document before any implementation.

21.2 Roles and Responsibilities

In order to properly implement the Training Plan, DGDC requires the involvement of the people listed below.

Table 21-1: Roles and Responsibilities

Role	Responsibilities
Board of Directors	<ul style="list-style-type: none"> ■ Be familiarized, review and approve the Training Plan
Finance Manager	<ul style="list-style-type: none"> ■ Ensure the availability of resources necessary for the implementation of the Training Plan
Head of ESG	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Training Plan
ESG Manager	<ul style="list-style-type: none"> ■ Assure the correct implementation of the Training Plan ■ Update the Training Plan ■ Review and approve the contractor project-specific Training protocols and/or plans
Environmental Coordinator or H&S Supervisor	<ul style="list-style-type: none"> ■ Ensure the generation of evidence and reports for compliance with the IFC PS as well as maintaining DGDC’s KPIs. In addition, ensure the internal coordination to follow the Training Plan
Contractor Company	<ul style="list-style-type: none"> ■ Develop a project-specific Training Plan or training protocols
DGDC Employees, Contractors and Subcontractors	<ul style="list-style-type: none"> ■ Understand and carry out the activities set out in the Training Plan

21.3 Required Training Activities

The following table presents the different types of training required by topic, their frequency and the required personnel for both the construction and the operational phases of the Project.

Table 21-2: Required Training Activities by Topic

Topic	Project Phase	Required Training	Personnel Required	Frequency of Training
Biodiversity Management	Construction and Operation	<p>Workers Health and Safety:</p> <ul style="list-style-type: none"> ■ Training and induction on the importance of biodiversity in the region, including: <ul style="list-style-type: none"> - Restrictions and prohibitions on harassment, hunting, trapping, gathering, buying, and/or selling of flora and fauna species (included contractors); - Information on species present within the area, especially endangered or threatened species; - Procedures regarding how to proceed if alive, injured, or dead animals are found; 	??	Induction training/yearly refreshers

Topic	Project Phase	Required Training	Personnel Required	Frequency of Training
		<ul style="list-style-type: none"> - Delimitation of work areas; and - Information regarding appropriate behavior prior to beginning construction. 		
Erosion and Sediment Control	Construction and Operation	<ul style="list-style-type: none"> ■ General awareness and procedures concerning water management and the prevention of erosion and sedimentation; ■ General awareness on key indicators of erosion and sedimentation in order to apply corrective actions; ■ The appropriate disposal methods of collected stormwater. 	All Employees of DGDC, contracts, and public	Induction training/yearly refreshers
Waste Management	Construction and Operation	Employees and contractors will be trained in proper waste management, including classification.	All Employees	Induction training/yearly refreshers
Water Management	Construction and Operation	<ul style="list-style-type: none"> ■ General awareness and procedures concerning water management and conservation ■ Emergency procedures in case of water leaks ■ The appropriate disposal methods of hazardous materials or industrial wastewater to ensure they are not disposed of in the facility's sanitary sewer system. 	All Employees	Induction training/yearly refreshers
Air Emissions	Construction and Operation	<ul style="list-style-type: none"> ■ General awareness and procedures concerning emissions management. ■ Personnel involved with the air emissions generation will receive additional training including refresher and updates to the training. 		
Noise Management	Construction and Operation	All Project construction and operational staff will be trained regarding proper use of PPE, and will be informed of tasks where noise levels exceed 85 dBA to ensure that PPE is used during completion of these tasks.	All Employees	Induction training/yearly refreshers
Natural Disasters	Construction and Operation	All personnel on site will receive training on procedures and actions to perform before, during, and after an emergency. After organizing the site's Emergency Brigade, they will be trained on the content of the Natural Disasters Management Plan and their responsibilities and duties in case of each type of emergency will be explained.	All Employees	Induction training/yearly refreshers
		In addition to the training, emergency response drills will also be conducted at least yearly. The drills will be conducted without notice and the response times will be monitored and recorded.	All Employees	Yearly
		The Emergency Response Plans will be reviewed and revised if improvements	All Employees	When changes are

Topic	Project Phase	Required Training	Personnel Required	Frequency of Training
		are needed after the drills. After the drill, trainings will be organized to resolve any faults encountered during the drills.		made to the plan in response to a drill or an emergency response.
Well Blowouts	Construction	Well control certification program (API, IADC, or similar governing body)	All tool pushers and drilling superintendents	At employment inception and every two years after
	Operation	Emergency Response Training and mock drills	All Plant Personnel	Induction training/yearly refreshers
Emergency Response	Construction and Operation	Drills – Practice Emergency Response Drills and evaluation	All Plant Personnel	Every 6 months
	Construction and Operation	Emergency Response Training – Implementation of the Emergency Response Plan, roles and responsibilities.	All Plant Personnel	Yearly for plant personnel, refresher every 6 months for Emergency Response Team
Site Security	Construction and Operation	Receive specific training on: <ul style="list-style-type: none"> ■ Site Security Plan and its implementation in order to ensure that response to any dangerous situation is adequate. ■ External Grievance Mechanism 	Employees with Security responsibilities	Induction training/yearly refreshers
Workers Health and Safety	Construction and Operation	During Health and Safety Training, all personnel will be trained on: <ul style="list-style-type: none"> ■ Risk Identification and Analysis ■ High risk activities and work permits ■ PPE ■ Personnel Health ■ Emergency response ■ Traffic and Site Access ■ Obligations and forbidden actions ■ Code of Conduct 	All Employees	Induction training/yearly refreshers
Labor Conditions	Construction and Operation	Anyone who has a supervisory role and/or a direct hiring role is required to be trained on: <ul style="list-style-type: none"> ■ Working Conditions and Management of Worker Relationship ■ Human Resources Policy ■ Working conditions and terms of employment ■ Worker's organizations ■ Non-Discrimination and Equal Opportunity ■ Gender Equality ■ Retrenchment ■ Grievance Mechanism ■ Workforce Requirements 	Managers and Human Resources Personnel	Induction training/yearly refreshers

Topic	Project Phase	Required Training	Personnel Required	Frequency of Training
		<ul style="list-style-type: none"> ■ Occupational Health and Safety ■ Hiring Requirements ■ Communication mechanisms ■ Workers engaged by third parties ■ Performance Management Process 		
	Construction and Operation	<p>All Employees will be trained on their rights including:</p> <ul style="list-style-type: none"> ■ Working conditions and terms of employment ■ Grievance Mechanisms 	All Employees	Induction training
Internal Grievances	Construction and Operation	All Employees will be trained on the implementation of the Internal Grievance Mechanism, its confidentiality and their protection from retaliation.	All Employees	Induction training
	Construction and Operation	<p>The Grievance Mechanism Team will be trained on:</p> <ul style="list-style-type: none"> ■ Roles and Responsibilities, ■ GM Database ■ Grievance Mechanism Procedures 	Grievance Mechanism Team	Induction training/yearly refreshers
Community Health and Safety	Construction and Operation	<p>Trained on:</p> <ul style="list-style-type: none"> ■ Health and Safety Risk Identification Associated to Affected Communities ■ Emergency and Preparedness Response Plan ■ Community Health and Safety Measures ■ Communication of Information 	Community Relations Team, Community Relations Supervisor and anyone else tasked with implementing the Community Health and Safety Plan	Induction training/yearly refreshers
External Grievances	Construction and Operation	<p>The Community Relations Team will be trained on:</p> <ul style="list-style-type: none"> ■ Roles and Responsibilities, ■ GM Database ■ Grievance Mechanism Procedures 	Community Relations Team	Induction training/yearly refreshers
Contractor Management	Construction and Operation	<p>Anyone who has a supervisory role and/or a direct hiring role is required to be trained on:</p> <ul style="list-style-type: none"> ■ Contractor Management Procedures ■ Training and Competency ■ Contractor Supervision Procedure 	Managers and Human Resources Personnel	Induction training/yearly refreshers
Stakeholder Engagement	Construction and Operation	<p>Training on the Stakeholder Engagement Plan, including:</p> <ul style="list-style-type: none"> ■ Identification of Stakeholders ■ Stakeholder Mapping and prioritization of stakeholders ■ Disclosure of information and community participation ■ Communication tools ■ Scheduling communication and engagement activities ■ Recordkeeping 	Community Relations Team, Contractors	Induction training/yearly refreshers
COVID-19	Construction and Operation	All personnel will be provided guidelines and practices regarding COVID-19	All Employees	Document shared at the

Topic	Project Phase	Required Training	Personnel Required	Frequency of Training
				start of site activities
Archeological Change Finds	Construction	All Project Construction personnel will receive training and demonstrate competency in the identification of chance finds and the Chance Find Procedure	All Construction Personnel	Induction training
Transportation	Construction and Operation	Personnel will be trained on the implementation of the Traffic Management Plan, including: <ul style="list-style-type: none"> ■ Driver Safety Measures ■ Vehicle Integrity ■ Route Management ■ Road Condition ■ Noise, Vibration and Dust ■ Transportation Safety within the Site ■ Communication with Community Stakeholders 	All Personnel	Induction training/yearly refreshers

21.4 Documentation and Monitoring

Documentation of all training is required to be kept on-site, by Human Resources, for DGDC and all contractors. Implementation of this procedure is reviewed through internal and external (when applicable and available) audit results and other inspection processes.

21.5 Key Performance Indicators

The table below presents the key performance indicators that will evaluate the implementation of this plan:

Table 21-3: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Project Phase	Method/Tool/Frequency
Trainings	Total number of trainings carried out in the stipulated time frame	100% of trainings carried out in the stipulated time frame	Construction and Operation	Human Resources records / monthly
Workers	Percentage of trained workers	100% of trained workers	Construction and Operation	Human Resources records / monthly

22. ESMP ESTIMATED COSTS

This chapter provides a list of proposed and recommended management and mitigation measures and provides a preliminary estimated cost for their implementation. This preliminary estimated costs will need to be reviewed at the exact moment of the implementation of the management plan. Some of the costs presented here will vary depending on the local market conditions and availability of the resources.

Table 22-1: ESMP Estimated Costs

Plan	Resource	Management Measure	Cost Type	Project Phase	Preliminary Estimated Cost
All	Staff	Personnel per roles and responsibilities of ESMP		Pre-construction	\$70-90k \$15-25k
Biodiversity Management Plan	Flora and Fauna	Pre-vegetation clearing surveys by a terrestrial plant and fauna specialists	Labor	Construction	\$3-5k
		Wildlife Specialist for Oversight and Animal rescue and relocation	Labor	Construction	\$2-4k
		Tree Fellers for vegetation removal	Labor	Construction	\$1-2k
		Revegetation	Labor and Supplies	Construction	\$3-5k
Biodiversity Management Plan	Health and Safety	Training and signs	Labor and Supplies	Construction	\$2k
Erosion and Sediment Control Plan	Soil and Water	Monitoring – Sample analysis	Labor and Supplies	Operation	\$3-5k
		Erosion and Sediment Control Measures – Silt fences, berms, temporary storage, seeding, tarps	Labor and Supplies	Construction	\$5-10k
		Monitoring – Sample analysis	Labor and Supplies	Construction	\$3-5K
	Health and Safety	Training and Inspections	Labor	Construction	\$2k
		Training and Inspections	Labor	Operation	\$2k
Waste Management Plan	Soil and Water	Material Storage	Supplies	Construction	\$1k
		Material Disposal Costs	Supplies	Construction	\$5-10K
		Monitoring – Sample analysis	Labor and Supplies	Construction	\$3-5k
		Material Storage	Supplies	Operation	\$1k
		Material Disposal Costs	Supplies	Operation	\$2-4k

Plan	Resource	Management Measure	Cost Type	Project Phase	Preliminary Estimated Cost
		Monitoring – Sample analysis	Labor and Supplies	Operation	\$1-2k
	Health and Safety	PPE	Supplies	Construction	\$6-10k
		Training and Inspections	Labor	Construction	\$2k
		PPE	Supplies	Operation	\$2-4k
		Training and Inspections	Labor	Operation	\$2k
Water Management Plan	Soil and Water	Monitoring – Sample analysis	Labor and Supplies	Construction	\$3-5k
		Wastewater storage and disposal	Supplies	Construction	\$1-5k
		Monitoring – Sample analysis	Labor and Supplies	Operation	\$1-2k
		Septic System maintenance	Labor and Supplies	Operation	\$1-2k
	Health and Safety	Potable water and storage	Supplies	Construction	\$5-10k
		Potable water and storage	Supplies	Operation	\$5-10k
Air Emissions Management Plan	Air and Health and Safety	Air Emissions Monitoring – Includes Hydrogen Sulfide and n-pentane	Supplies	Construction	\$5-10k
		Dust control practices – soil wetting, seeding.	Supplies	Construction	\$1k
		Training and Inspections	Labor	Construction	\$2k
		Air Emissions Monitoring – Includes Hydrogen Sulfide and n-pentane	Supplies	Operation	\$3-5k
		Dust control practices – soil wetting, seeding.	Supplies	Operation	\$1k
		Training and Inspections	Labor	Operation	\$2k
Noise Management Plan	Fauna and Health and Safety	Noise Monitoring	Supplies	Construction	\$3-6k
	Health and Safety	PPE	Supplies	Construction	\$2-4k
		Training	Labor	Construction	\$2k
		Noise Monitoring	Supplies	Operation	\$3-6k
		PPE	Supplies	Operation	\$2-4k
	Training	Labor	Operation	\$2k	

Plan	Resource	Management Measure	Cost Type	Project Phase	Preliminary Estimated Cost
Natural Disaster Management Plan	Health and Safety	Training	Labor	Construction	\$2k
		Emergency response equipment (flashlights, water, etc.)	Supplies	Construction	\$1-2k
		Audible Alarms	Supplies	Construction	\$1-2k
		Training	Labor	Operation	\$2k
		Emergency response equipment (flashlights, water, etc.)	Supplies	Operation	\$1-2k
		Audible Alarms	Supplies	Operation	\$1-2k
Well Blowout Prevention	Health and Safety	Training	Labor	Construction	\$2k
		Training	Labor	Operation	\$2k
Emergency Response Plan	Water, Soils, Health and Safety	Emergency response equipment – first aid/PPE, fire, spill response, security	Supplies	Construction	\$3-5k
		Emergency response equipment – first aid/PPE, fire, spill response, security	Supplies	Operation	\$3-5k
	Health and Safety	Training	Labor	Construction	\$2k
		Training	Labor	Operation	\$2k
Security Management Plan	Health and Safety	Training	Labor	Construction	\$2k
		Security Equipment – Cameras, fences, locks.	Supplies	Construction	\$3-4k
		Training	Labor	Operation	\$2k
Workers Health and Safety Management Plan	Health and Safety	Training	Labor	Construction	\$2k
		PPE/Safety Equipment for personnel – for example: steel toe boots, hard hats, high visibility vests, earplugs, safety glasses	Supplies	Construction	\$4-6k
		Training	Labor	Operation	\$2k
		PPE/Safety Equipment for personnel – for example: steel toe boots, hard hats, high visibility vests, earplugs, safety glasses	Supplies	Operation	\$3-5k
Labor Conditions and Workers Selection Plan	Socioeconomic, gender and social inclusion	Additional External Communications	Fees/Supplies	Construction	\$1-3k
		Training	Labor	Construction	\$2k
		Additional External Communications	Fees/Supplies	Operation	\$1-2k

Plan	Resource	Management Measure	Cost Type	Project Phase	Preliminary Estimated Cost
		Training	Labor	Operation	\$2k
Internal and External Grievance Mechanism	Socioeconomic	Additional External Communications	Fees/Supplies	Construction	\$1-3k
		Training	Labor	Construction	\$2k
		Additional External Communications	Fees/Supplies	Operation	\$1-2k
		Training	Labor	Operation	\$2k
Community Health and Safety Plan	Health and Safety	Training	Labor	Construction	\$2k
		Additional External Communications	Fees/Supplies	Construction	\$1-3k
		Training	Labor	Operation	\$2k
		Additional External Communications	Fees/Supplies	Operation	\$1-2k
Stakeholder Engagement Plan	Socioeconomic	Additional External Communications, Public Consultation, Disclosure of Information, Stakeholder Database	Fees/Supplies	Construction	\$2-4k
		Training	Labor	Construction	\$2k
		Additional External Communications, Public Consultation, Disclosure of Information, Stakeholder Database	Fees/Supplies	Operation	\$1-2k
		Training	Labor	Operation	\$2k
COVID-19 Engagement Plan	Health and Safety, Socioeconomics	Training	Labor	Construction	\$2k
		Additional External Communications, Community Engagement	Fees/Supplies	Construction	\$1-3k
		PPE – Face masks, hand sanitizer, cleaning supplies, testing kits	Supplies	Construction	\$2-3k
		Training	Labor	Operation	\$2k
		Additional External Communications, Community Engagement	Fees/Supplies	Operation	\$1-2k
		PPE – Face masks, hand sanitizer, cleaning supplies, testing kits	Supplies	Operation	\$1-2k
Chance Find Plan	Cultural Heritage	Training	Labor	Construction	\$2k

Plan	Resource	Management Measure	Cost Type	Project Phase	Preliminary Estimated Cost
Transportation Management Plan	Health and Safety	Training	Labor	Construction	\$2k
		Vehicle Inspections	Labor and Supplies	Construction	\$1k
		Vehicle, Equipment and Road Maintenance (includes dust suppression, erosion control, etc.)	Labor and Supplies	Construction	\$5-8k
		Road Signs/PPE	Supplies	Construction	\$1k
		Additional External Communications, Grievance Mechanism	Fees/Supplies	Construction	\$1-3k
		Training	Labor	Operation	\$2k
		Vehicle Inspections	Labor and Supplies	Operation	\$1k
		Vehicle, Equipment, and Road Maintenance	Labor and Supplies	Operation	\$3-5k
		Road Signs/PPE Repairs	Supplies	Operation	\$1-2k
		Additional External Communications, Grievance Mechanism	Fees/Supplies	Construction	\$1-2k

23. REFERENCES

ECLIPSE. 2020. Drilling of Geothermal Well RV-12 and Injection Pipeline. Draft Environmental and Social Impact Assessment. Dominica, September 2020.

IFC. 2012. Performance Standard 6: Biodiversity Conservation and Sustainable Management of Living Natural Resources.

https://www.ifc.org/wps/wcm/connect/topics_ext_content/ifc_external_corporate_site/sustainability-at-ifc/policies-standards/performance-standards/ps6

Jacobs. 2018. Dominica Geothermal Development – Environmental and Social Impact Assessment. NZ Ministry of Foreign Affairs & Trade. Environmental and Social Impact Assessment, Volumes 1-5. RZ020300-002-NP-RPT-0004 | 21, July 2018.

The Biodiversity Consultancy. 2020. Biodiversity Screening and review against STOA/AFD/EDFI exclusion list for the Wotton Waven geothermal project, Dominica.

World Bank. 2016. World Bank Environmental and Social Framework. www.worldbank.org

APPENDIX 13-A INTERNAL CLAIM FORM

INTERNAL CLAIM FORM			
GRIEVANCE FORM			
GRIEVANCE N°			
EMPLOYEE COMPANY			
GRIEVANCE TYPE			
<i>(indicate whether this is a concern, claim, or a suggestion)</i>			
PERSONAL INFORMATION*			
*Surnames:		*Address:	
*Names:		*Telephone:	
Gender:		Address:	
Age:		Professional occupation:	
Labor relationship with DGDC	Permanent	Professional Service	Other (specify)
* Not mandatory information. You may submit this form anonymously.			
REASON FOR THE CLAIM			
Details: <i>(indicate when did the events of this claim occurred, who was involved, foundations, evidence and any other relevant information).</i>			
Response requested (describe what is requested based on the claim)			
Attached and/or delivered documents Information attached: YES <input type="checkbox"/> NO <input type="checkbox"/> Indicate which are the documents and attach them.			
Signature:		Date:	
Receptor Signature:		Date:	
We appreciate your comments; please keep a copy for follow-up. Thank you.			

APPENDIX 15-A EXTERNAL CLAIM FORM

EXTERNAL CLAIM FORM			
GRIEVANCE FORM			
GRIEVANCE N°			
EMPLOYEE COMPANY			
GRIEVANCE TYPE			
<i>(indicate whether this is a concern, claim, or a suggestion)</i>			
PERSONAL INFORMATION*			
*Surnames:		*Address:	
*Names:		*Telephone:	
Gender:		Address:	
Age:		Professional occupation:	
Labor relationship with DGDC	Permanent	Professional Service	Other (specify)
* Not mandatory information. You may submit this form anonymously.			
REASON FOR THE CLAIM			
Details: <i>(indicate when did the events of this claim occurred, who was involved, foundations, evidence and any other relevant information).</i>			
Response requested (describe what is requested based on the claim)			
Attached and/or delivered documents Information attached: YES <input type="checkbox"/> NO <input type="checkbox"/> Indicate which are the documents and attach them.			
Signature:		Date:	
Receptor Signature:		Date:	
We appreciate your comments; please keep a copy for follow-up. Thank you.			

APPENDIX 16-A WORKERS ACCOMMODATION AUDIT

Key Performance Indicator	Yes	No	N/A	Comments
Accommodation				
The location of the facilities is designed to avoid natural hazards (storms, floods, etc.)				
Accommodation facilities are located at a reasonable distance from the workplace				
Accommodation facilities are constructed of suitable materials, maintained in good condition and clean				
Accommodation facilities have electricity and adequate drainage				
Accommodation facilities are heated/ventilated/air-conditioned (depending on climate)				
Accommodation facilities have adequate lighting systems				
Accommodation facilities have specific containers for garbage collection and are emptied regularly				
Pest extermination, vector control and disinfection are carried out on a regular basis				
Rooms/bedrooms are kept in good condition, and are ventilated and cleaned at regular intervals				
The rooms/bedrooms and sanitary facilities are located in the same buildings				
The number of workers sharing the same room/bedroom does not exceed five				
Mobile partitions or curtains are provided				
There are separate sleeping areas for men and women				
There is a separate bed for each worker				
There is a minimum space of 1 meter between beds				
The use of double-decker bunks is minimized				
When using double-decker bunks there is sufficient space between the upper and lower bed				
Triple deck bunks are prohibited				
Workers are provided with comfortable mattresses, pillows and clean bedding				

Bedding is washed frequently and applied with appropriate repellents and disinfectants				
The accommodation areas are separated from the kitchen space				
Adequate washing and drying facilities are provided				
Workers are provided with basic collective social spaces and adequate recreational areas				
Health and safety measures (including emergency preparedness and response measures) are visible within the facility				
The regulation with the rights and duties of the workers is visible inside the facilities				
Regulations regarding alcohol and tobacco consumption and third party access to the camp are visible inside the facilities				
Community relations management guidelines are visible within the facilities				
Worker housing policies and management plans are periodically reviewed and improved.				
The person appointed to manage the accommodation has the background, competence and experience necessary to carry out its mission and is given the appropriate responsibility and authority to do so.				
There are sufficient staff to ensure proper implementation of housing standards (cleaning, cooking, security, etc.)				
Transport				
Transportation provided to workers is safe				
An adequate transport system is provided to and from the surrounding communities				
Water				
Workers have easy access to an adequate supply of potable water within the Site				
Workers have easy access to an adequate supply of clean water within their accommodation				
The quality of the drinking water is regularly monitored.				
Medical services				
First aid kits are provided in adequate quantities				

Are the first aid kits properly stored				
There is an adequate number of staff/workers trained to provide first aid				
There are medical/paramedical staff on site.				
Ambulance or other means of transport are available for the transfer of staff to health facilities.				
Accommodation facilities have a first aid kit				
Food				
The kitchen facilities are built with adequate and easy to clean materials.				
The kitchen floor, ceiling and wall surfaces, adjacent to or above the cooking areas, are constructed of fire-resistant, non-absorbent, durable, non-toxic and easy-to-clean materials.				
The surfaces of the food preparation tables and adjacent walls are equipped with a smooth, durable, non-corrosive, non-toxic and washable surface.				
Suitable sealable containers are available for depositing food and other waste.				
Garbage is frequently removed from the kitchen to avoid accumulation				
The people in charge of the kitchen are adequately trained in the handling and cooking of food.				
The food provided to workers contains nutritional value appropriate to the activities they perform.				
The food provided takes into account the religious/cultural background of the workers.				
Workers are provided with sufficient space in the canteen/dining room.				
Health services				
The sanitary and cleaning facilities are built with easy to clean materials.				
Sanitary and washing facilities are frequently cleaned and maintained in working order.				
Toilets, shower/bathrooms and other sanitary facilities are designed to provide workers with adequate privacy, including roof-to-floor partitions and lockable doors.				
There are separate toilet and washing facilities for men and women.				

There are an adequate number of toilets, urinals and sinks.				
Toilet facilities are conveniently located and easily accessible.				
The shower floor is made of durable, washable anti-slip materials.				
There are an adequate number of showers.				
The shower facilities have an adequate supply of hot and cold running water.				

APPENDIX 17-A SUMMARY OF COMMUNITY MEETINGS

LAUDAT

In Laudat, a community meeting was held on Tuesday 4th July 2018. Concerns expressed by the community included technical questions about the pipeline and public health considerations associated with operations of the plant. Community members also voiced concerns about the risks associated with volcanic activity near the project, equipment failure, and other natural disasters. Community members also expressed the desire to see policy changes associated with the Project and the need for some community benefit projects that would be realised in the community. They also asked about land acquisition and noted that Laudat has been the location for several other projects where few benefits were realised in the local community. The DGDC Team explained the costs and the benefits of the project and the ESIA findings in terms of H2S. DGDC also explained the technology being utilised in the plant and the low risks associated with this type of equipment. The DGDC Team further explained the risks and the planning and design measures that were selected for this project given the topography, risk of landslides and recent flooding from Hurricane Maria and the EPC Contractor requirements that will be put in place to reduce nuisance and community health and safety impacts such as the emergency response and other planning procedures. The current status of land acquisition was also explained and the need to complete compensation before construction can begin, as per OP 4.12. Ongoing monitoring and preventative measures such as the traffic management plan and erosion control measures were also explained. Comments on policy and community benefits were noted, but it was explained that this is ultimately under the control of government and policymakers, rather than the project.

In July 2019, prior to an emergency drill on the production site, a meeting was held with the residents of Laudat

In third quarter of 2019, the DGDC had two consultations with the community of Laudat. The consultations were centered around the production well flow test carded for early October. Presentations at the first consultation, held on September 26, 2019, concentrated on defining a flow test and the flow test process and duration of the activity. Approximately twenty members of the community attended that meeting. The Engineering Department delivered a power point presentation explaining the flow test process and the mitigating measures to be employed for the duration of the test. Participants were allowed to ask questions and voice their concerns after the presentation. The consultation was recorded, and participants were requested to fill-out attendance forms. A second community consultation was held four days after the start of the flow test to receive feedback from the community and inform of any changes to plan.

In June 2020, community meetings were held to provide updates to the project following existing COVID-19 protocols. Further updates were provided in October 2020.

TRAFALGAR

In Trafalgar, a community meeting was held on Wednesday 5th July 2018. Fewer comments were made at this meeting than in Laudat or Wotten Waven, likely because the community is further from the power plant site. The community asked a few technical questions about the distance of the pipeline and natural hazards that could affect the project. They also asked about the proximity to the nearby communities from the power plant and emergency response. The DGDC Team explained the risks and the planning and design measures that were selected given the topography, risk of landslides and recent flooding from Hurricane Maria. DGDC also explained the emergency response and planning procedures that will be put in place for the Project. Examples of other projects where a geothermal plant was located in close proximity to the community were given.

In September 2019 prior to the flow test of the production well, One-on-one engagements were held with vendors of Trafalgar Village, Papillote Hotel owners and employees of the Trafalgar Tourist Facility. This was done to inform of the flow test and to highlight the restricted access to the Trafalgar Falls during the first few hours of the flow test. An information poster was placed at the Trafalgar facility to inform visitors of the planned test.

WOTTEN WAVEN

In Wotten Waven, a community meeting was held on Thursday 6th July 2018. A lot of concern was expressed at the meeting particularly about public health issues, employment, and direct benefits to the community. Specifically, people asked about job requirements, accidents at the plant and/or the pipeline, detrimental effects on thermal spas, the expected lifespan of a well, consumer benefits on electricity bills, health impacts of construction and noise, and property acquisition. A community member also suggested the need for a weekly briefing in the community during the construction phase. The DGDC Team explained the design of the plant and reinjection route given the topography, risk of landslides and recent flooding from Hurricane Maria and to reduce noise and visual affects at properties near the power plant. DGDC also explained the technology being utilized in the plant and the low risks associated with this type of equipment. The lack of changes anticipated for the thermal surface features were also explained given the depth of the wells and associated activity and the plan to conduct ongoing monitoring of these features was also shared. The DGDC Team further explained in detail the noise associated with the steam blowing phase and the limited timeframe for this testing. The current status of land acquisition was also explained and the need to complete compensation before construction as per OP 4.12.

Following the disclosure of the NTS, the full ESIA was made available to the community in August 2018 via the internet, and a hard copy being available at DGDC's offices. The DGDC held two public consultations on the Jacobs ESIA in February 2019. The first took place on 6 February 2019 in Roseau at the Goodwill Parish Hall and targeted persons living in Roseau and environs. The second consultation took place in Portsmouth of 7 February 2019 at the Central Cooperative Credit Union Hall and targeted persons living in Portsmouth and environs. Thirty-four (34) persons attended the consultation in Roseau while nineteen persons (19) attended at Portsmouth.

Engagements were also held with schools; during the period January to March 2019, a total of 25 schools were engaged - seven secondary and fifteen primary schools. Schools from the south, central, west, north and north east were part of the engagement. Three primary schools from the Kalinago territory were also part of our school engagement drive. Participation in these sessions amounted to a total of 1,049 students and 68 teachers. During April to June 2019, a total of 10 schools were engaged – nine primary schools and the Dominica State College. Participation in these sessions amounted to a total of 322 students and 24 teachers.

APPENDIX B Resettlement Action PLAN (RAP)



Resettlement Action Plan

February 2021

Document No.: RZ020300-002-RPT-0015| V1

February 2021

Resettlement Action Plan

Dominica Geothermal Development Company Ltd.
18 Kennedy Avenue, Roseau
Commonwealth of Dominica

© Copyright 2021 by Dominica Geothermal Development Company Ltd. ("DGDC").
All rights reserved. No part of this work may be reproduced or transmitted in any form,
or by any means, without the prior written permission of DGDC Ltd.

CONTENTS

1.	INTRODUCTION	1
1.1	Background.....	1
1.2	Project Location	1
1.3	Project Components	2
1.4	Efforts to Minimize Resettlement	6
	1.4.1 Power Plant.....	6
	1.4.2 Reinjection Pipeline Route.....	6
1.5	RAP Purpose, Scope and Approach.....	7
1.6	Structure of the RAP	8
2.	LEGAL AND INSTITUTIONAL FRAMEWORK	9
2.1	Introduction	9
2.2	National Requirements	9
2.3	Institutional Framework for Addressing Land Acquisition and Leases	12
2.4	International Requirements.....	13
	2.4.1 OP 4.12- Involuntary Resettlement.....	13
	2.4.2 IFC PS5.....	13
	2.4.3 IDB OP-710.....	14
2.5	World Bank Group Supporting Guidance Documents.....	16
3.	SOCIO-ECONOMIC BACKGROUND OF AFFECTED COMMUNITY AND PAP CENSUS.....	17
3.1	Regional and Local Socio-Economic Context	17
3.2	Regional Overview.....	17
3.3	Hurricane Maria 2017	17
3.4	Socio-Economic Area of Influence	18
	3.4.1 Trafalgar	18
	3.4.2 Wotten Waven	18
	3.4.3 Laudat.....	18
3.5	Economic Profile	18
	3.5.1 Agriculture.....	19
3.6	Educational Profile	19
3.7	Health Profile	20
3.8	Gender.....	20
3.9	Vulnerability	22
3.10	Detailed Socio-Economic Surveys	23
4.	IDENTIFICATION OF PROJECT IMPACTS.....	26
4.1	Land Acquisition, Physical Displacement and Resettlement Impacts	26
4.2	Economic Displacement and Livelihood Impacts.....	28
4.3	Gender Impacts	28
4.4	Ecosystem Services.....	28
5.	ELIGIBILITY AND ENTITLEMENT	29
5.1	Overview	29
5.2	Eligibility and Cut-Off Date.....	29
5.3	Entitlement Matrix for Compensation.....	29
5.4	Vulnerable Parties and Gender Considerations.....	33

6.	VALUATION AND COMPENSATION.....	34
6.1	Assessment of Land Value	34
6.2	Assessment of Crops/Trees/Livestock Compensation Values	36
6.3	Assessment of Assets, Residential and other Structures.....	38
6.4	Compensation Payment Procedure	38
6.5	Livelihood Restoration and Enhancement Measures.....	39
7.	VULNERABILITY ASSISTANCE	40
7.1	Forms of Assistance	41
7.2	Compensation for Vulnerable PAPs.....	41
8.	STAKEHOLDER ENGAGEMENT	42
8.1	Introduction	42
8.2	Consultation with the Affected Community.....	42
8.3	Consultation on the RAP	43
9.	RESETTLEMENT SITES.....	44
10.	ROLES AND RESPONSIBILITIES	45
10.1	Overview	45
10.2	Organizational Responsibilities	45
10.3	Compensation Payment Procedure	46
10.4	Resettlement Procedure	46
10.5	Livelihood Restoration and Enhancement Measures.....	47
11.	GRIEVANCE MANAGEMENT	48
11.1	Overview	48
11.1.1	Objective.....	48
11.1.2	Scope of Application	49
11.1.3	Definitions	49
11.2	Roles and Responsibilities	50
11.3	Activities.....	50
11.3.1	Principles	51
11.3.2	Publication of the Mechanism	51
11.3.3	Grievance Mechanism Procedure.....	52
11.4	Confidentiality and Protection from Retaliation	59
11.5	Documentation and Monitoring	59
11.6	Key Performance Indicators.....	59
12.	MONITORING AND EVALUATION	61
12.1	Monitoring Objectives	61
12.2	Monitoring Indicators.....	61
12.3	Monitoring Process	61
12.4	Evaluation Objectives	62
12.5	Evaluation Process	62
13.	BUDGET AND SCHEDULE	64
14.	REFERENCES	65

APPENDIX A	ASSETS INVENTORY – PHYSICAL STRUCTURES
APPENDIX B	BASIS OF VALUATION
APPENDIX C	COMPLETION AUDIT TABLE OF CONTENTS

List of Tables

Table 2-1: Policy GAP Analysis	11
Table 3-1: PAP Socioeconomic Census Data	24
Table 4-1: Estimated % of Land Acquired for Reinjection Line Route.....	26
Table 5-1: Entitlement Matrix	31
Table 6-1: Assessment of Property Values.....	34
Table 6-2: Crop/Tree/Livestock Values.....	36
Table 6-3: Structural Valuations.....	38
Table 7-1: Vulnerability Matrix.....	40
Table 10-1: Roles and Responsibilities.....	45
Table 11-1: Terms and Definitions	49
Table 11-2: Roles and Responsibilities.....	50
Table 11-3: Classification of Grievances	55
Table 11-4: Key Performance Indicators	59
Table 12-1: RAP Implementation Schedule.....	62
Table 13-1: Estimated RAP Budget	64

List of Figures

Figure 1-1: Location of Roseau Valley and Site of proposed	2
Figure 1-2: Project Component Location	3
Figure 1-3: Proposed Preliminary Plant Layout	5
Figure 1-4: Proposed Pipeline Route.....	7
Figure 2-1: The General Process of Acquiring Land through Compulsory Acquisition in Dominica	10
Figure 3-1: Number of Women Legislators (Percentage)	22
Figure 4-1: Properties Neighboring Power Plant Site	27
Figure 4-2: Properties Neighboring Preferred Reinjection Line	28
Figure 6-1: Photograph of Affected Rabbit Hutch.....	37
Figure 9-1: Photograph of Resettlement Site 1.....	44
Figure 11-1: General Grievance Mechanism Procedure	52
Figure 11-2: DGDC's Grievance Flow Chart.....	54

Acronyms and Abbreviations

<u>Name</u>	<u>Description</u>
Aol	Area of Influence
RAP	Resettlement Action Plan
CIA	Central Intelligence Agency
CLO	Community Liaison Officer
DGDC	Dominica Geothermal Development Company Limited
DOMLEC	Dominica Electricity Services Limited
DOWASCO	Dominica Water and Sewerage Company Limited
DSWMC	Dominica Solid Waste Management Corporation
EC	Eastern Caribbean Dollar
EIA	Environmental Impact Assessment
EHS	Environmental Health and Safety
EPC	Engineer, Procure and Construct
ESIA	Environmental and Social Impact Assessment
ESMP	Environmental and Social Management Plan
ESMS	Environmental and Social Management System
GDP	Gross Domestic Product
GIS	Geographic Information Systems
GoCD	Government of the Commonwealth of Dominica
HSE	Health, Safety and Environment
IFC	International Finance Corporation
kW	Kilowatt
LRP	Livelihood Restoration Plan
MTPNP	Morne Trois Pitons National Park
MW	Mega Watt
NZ	New Zealand
PAP	Project Affected Person
PS	Performance Standard
ROW	Right of Way
SEP	Stakeholder Engagement Plan
SIA	Social Impact Assessment
ToR	Terms of Reference
USD	US Dollars
WB	World Bank
WBG	World Bank Group
WHO	World Health Organisation

1. INTRODUCTION

1.1 Background


This Resettlement Action Plan (RAP) was prepared by Dominica Geothermal Development Company (DGDC) for the Dominica Geothermal Power Plant Project, located in the Roseau Valley, Dominica. The RAP has been developed based on the previous RAP, including the census information it collected, using the information from the updated reinjection pipeline route. This RAP has been updated with additional data collected by Eclipse Inc. during consultations for an ESIA.

It is also important to note that, in September 2017, the Island was devastated by Hurricane Maria. This RAP has been developed post Hurricane Maria and reflects changes in land use, land acquisition and livelihood restoration for the Project post the disaster.

1.2 Project Location

The proposed Project is located in the Commonwealth of Dominica, a small island developing state in the Caribbean with a population of approximately 72,000 people and a land area of approximately 750 km². Dominica is located near the centre of a string of islands known as the Lesser Antilles, between the neighbouring French territories of Martinique and Guadeloupe. The proposed Project is located in the Roseau Valley in the Wotten Waven Geothermal System (Figure 1.1).

Within the Roseau Valley, a primary area of influence has been identified, comprising the three main communities in closest proximity to the proposed Project footprint. Due to their proximity, they are the most likely to be affected by any employment, resettlement, community health and safety issues which arise from the Project. These communities of relevance are namely Trafalgar, Wotten Waven and Laudat, as shown in Figure 1.1.



Source: ERM, 2020

Figure 1-1: Location of Roseau Valley and Site of proposed

1.3 Project Components

The Project components will be located in four separate areas: Power Plant Site; Injection Area, Production Well Area, and the back-up Production Pad A. The Figure below depicts the location of these general areas as well as the access roads and the approximate location of the injection pipeline route.




Figure 1-2: Project Component Location

The proposed geothermal facility will consist of the following main components, which are explained in more detail in the Addendum to the ESIA:

Plant Equipment:

- Production and Injection Wells;
- SGS and Brine Reinjection Pipeline and Wellpads;
- Turbine Generator;
- Heat Exchangers;
- Recuperators;
- Condensers;
- Pumps (feed, wells, ponds, firefighting system);
- Storage Tanks;
- Transformers;
- Emergency Generator;
- Water Tank and distribution system;
- Fire Fighting Tank and System;
- HVAC System; and

- Oil System;

Facilities:

- Brine Ponds;
- Electrical Building which will include separate areas for offices, kitchen and meeting rooms, workshop and storage, a control room, and a machinery room; and
- Septic Tank and Leach Field.

The Figure below shows a preliminary plant layout based on site topography and existing components locations for the binary plant.




Figure 1-3: Proposed Preliminary Plant Layout

The Project comprises the development of a two-unit geothermal power plant with a gross capacity of 10 MW in the Roseau Valley, Dominica. This covers the following stages: construction, completion, testing, commissioning, ownership and operation including the steamfield, required electrical connections and integration with associated infrastructure. The power plant is proposed to be located close to the village of Laudat.

Land acquisition for the drilling phase of the Project is still being finalized. The Government has completed negotiations for ownership of the existing well pads (WW-01, WW-03 and R1). Negotiations for WW-02 are ongoing and are close to being complete. The power plant lands (one PAP, one parcel) have been acquired but no compensation has been paid and negotiations are ongoing and at an advanced stage. Lands surrounding the power plant site are still to be acquired.

Brief descriptions of the main locations of Project infrastructure are as follows:

- Power plant comprising 2 x 5 MW units (Organic Rankine Cycle units (binary turbine), which will be adjacent to wells WW-P1 and WW03;
- Production well WW-P1 – The existing geothermal production well at Laudat is indicated to have potential to generate 6 to 9 MW and will be used together with WW-03 (situated on same well pad) for the steam gathering;
- Reinjection well RVI2 (to be drilled) located in Laudat. The used geothermal fluid (brine and possibly some steam condensate) produced from production well WW-P1 & WW03 would be disposed of into reinjection wells RVI2 via a 250 to 300 mm diameter reinjection pipeline approximately 1.2 Km in length;
- Back-up production well RVP2 (to be drilled) in Laudat.
- Steamfield infrastructure including two phase piping, steam separator, atmospheric flash tank, brine collection and disposal system, condensate collection and disposal system, pressure relief system, storage sump and rock muffler;
- Supporting infrastructure including existing well pads, turbine building, primary and ancillary equipment, cooling system, workers camp, and water supply; and
- 11 kV interconnections to the DOMLEC electricity grid at the power plant site.

1.4 Efforts to Minimize Resettlement

1.4.1 Power Plant

Several power plant sites and reinjection pipeline route options were considered as part of the Project (refer to ESIA Volume 1: Introduction). Multiple sites were considered for the power plant once the geothermal resource was identified. The site was gradually moved south-east to increase the separation distance from the concentrated local population, in order to reduce noise impacts.

1.4.2 Reinjection Pipeline Route

In terms of the reinjection pipeline route, four options were considered. One proposed route through Laudat was ultimately rejected to avoid displacement/disruption and another route was rejected as it was scheduled to rely on DOMLEC infrastructure, which presented coordination challenges for the Project. The third option was rejected because it was considered technically too difficult due to topography e.g. steep ravines. Ultimately, the power plant site location and preferred reinjection pipeline route were chosen to avoid disruption to the community and in consideration of economic and technical constraints. It is also important to note that at this stage, there is still some flexibility in the exact footprint of the reinjection route pipeline. As the pipeline corridor is anticipated to only be 10 m (to allow for access, maintenance and flexibility around design), DGDC will still have some discretion to locate each portion of the pipeline within an individual property. In other words, there are still opportunities to avoid displacement of structures, crops or other assets along the reinjection route line

during this stage of design. The proposed length of the re-injection pipeline from the power plant to the reinjection site, is approximately 1.2 kilometers. The exact diameter has not yet been determined. It is located on the south-western periphery of the village of Laudat. The Figure below shows the updated reinjection pipeline route.




Figure 1-4: Proposed Pipeline Route

1.5 RAP Purpose, Scope and Approach

Development of the power plant site and reinjection route pipeline will result in the acquisition of up to 22 properties (mostly abandoned agricultural land) either partially or in their entirety, and as a result cause physical displacement of four residential structures and economic displacement of two farmers. Only one property is occupied by a one-person household. The other three structures are classified as residential, having been constructed for that purpose. One is an abandoned dwelling house, one a partly constructed abandoned house and the other one which could be converted into a home. According to OP 4.12, displaced persons may be classified as:

“those who are affected by the involuntary taking of land resulting in (i) relocation or loss of shelter; (ii) loss of assets access to assets; or (iii) loss of income sources or means of livelihood whether or not the affected person must move to a different location.”

World Bank and IFC resettlement policies recognize the need to provide resettlement, compensation, and / or livelihood restoration assistance to persons that are currently utilizing project-affected land. Thus, the displacement of residents and farmers from the site and reinjection route are addressed in this RAP.

The scope of the RAP process included the following steps:

- Establishing the legal and guidance framework for managing displacement impacts, including national and international requirements;
- Identification, consultation and socio-economic surveys with all of the PAPs;
- Socio-economic analysis, including establishing the extent of vulnerability of the PAPs;

- Inventory and valuation of properties, structures, and crop assets to establish the basis for associated compensation;
- Consultation with relevant parties to identify any potential alternative land of comparable productive value for relocation;
- Consultation with PAPs on potential options for resettlement site options, livelihood restoration, compensation or improvement measures. These may include, for example, assistance to diversify income generating activities (such as training in new skills), financial management training and credit opportunities, business and enterprise training; and
- Establishing the necessary steps for implementation including:
 - Confirming final compensation / implementation budget, including all financial compensation, and costs for land acquisition, loss of structures, loss of crops, transitional support, livelihood restoration measures and independent monitoring;
 - Establishing the grievance and redress mechanism;
 - Confirming the roles and responsibilities within the GoCD and DGDC team regarding the implementation process; and
 - Confirming requirements for monitoring and evaluation.

1.6 Structure of the RAP

The content of this document is as follows:

- Section 1: Introduction;
- Section 2: Legal and Institutional Framework;
- Section 3: Socio-Economic Background of Affected Community and PAP Census;
- Section 4: Identification of Project Impacts;
- Section 5: Eligibility and Entitlements;
- Section 6: Valuation and Compensation;
- Section 7: Vulnerability Assistance
- Section 8: Stakeholder Engagement;
- Section 9: Resettlement Sites;
- Section 10: Roles and Responsibilities;
- Section 11: Grievance Management;
- Section 12: Monitoring and Evaluation;
- Section 13: Budget and Schedule; and
- Section 14: References.

2. LEGAL AND INSTITUTIONAL FRAMEWORK

2.1 Introduction

The Project is required to meet nationally and internationally accepted environmental and social safeguard standards in order to ensure that community benefits from the Project are maximised, and that potential adverse environmental and social impacts are minimised. Relevant national and international requirements are summarised below. In the event that international standards and national standards differ, the higher standard shall apply to the Project.

All lands for the project will be acquired and paid for by the GoCD and then be granted to the DGDC for use. A cooperation agreement (November 2019) between the Ministry of Lands and DGDC outlines the roles and responsibilities of each party with respect to lands.

2.2 National Requirements

There are a number of national policies, laws, regulations and guidelines that guide relevant environmental, social and economic issues in Dominica. The laws and regulations also provide the relevant instruments for the effective management of land acquisition and proper institutional coordination. Of primary relevance is the Land Acquisition Act.

The Land Acquisition Act, Chapter 53:02 deals with the acquisition of land by the state and clearly outlines procedures in acquiring private lands for state use. The Act covers the following areas:

- i. Acquisition of land and abandonment of acquisition;
- ii. Appointment and powers of Board of Assessment;
- iii. Determination of Small Claims for Compensation;
- iv. Provisions Governing Assessment of Compensation;
- v. Miscellaneous:
 - a) Absentee owners;
 - b) Compensation to persons interested in adjacent land;
 - c) Special provisions as to leases;
 - d) Persons in possession to be deemed owners;
 - e) Fees and expenses of Board;
 - f) Conveyancing etc.;
 - g) Payment of compensation;
 - h) Exemption from stamp duty and fees;
 - i) Limitation of time for making claims;
 - j) Assaulting or obstructing officer; and
 - k) Saving.

The Act includes a description of how compensation should be determined. The general process of compulsory land acquisition under the Land Acquisition Act, Chapter 53:02 is described below in Figure 2.1.

Compulsory land acquisition according to the Land Acquisition Act consists of an evaluation of the market value of the land conducted by the Department of Lands, a Cabinet paper establishing government acquisition of the land, follow by a negotiation or agreement to compensation with the relevant land owner. Compensation values are determined by the government Land Surveys Department.




Figure 2-1: The General Process of Acquiring Land through Compulsory Acquisition in Dominica

This process differs from the World Bank land acquisition and resettlement requirements in that compensation under OP 4.12 requires the evaluation to cover full replacement cost for each party, rather than market value covered by national requirements. In addition, World Bank resettlement requirements consider compensation for land users without legal rights, support for vulnerable parties, and livelihood restoration measures that are not covered under national law. World Bank also requires that compensation be completed prior to Project construction and that consultation associated with this process be well documented. A gap analysis between National Law / Practice and World Bank requirements is shown in Table 2-1.

Table 2-1: Policy GAP Analysis

Conflict/Gap	Local Legal Framework/Policy	World Bank Policy Requirements	Measures to Address Conflict/Gap
Compensation & Restoration of livelihoods and living standards	There is no existing legislation or official policy document that specifically supports resettlement initiatives in Dominica except for that created specifically in response to TS Erika and Hurricane Maria	OP 4.12 Involuntary Resettlement: Section 6 (c) – Where necessary.....compensation should also include measures to ensure that displaced persons are offered support after displacement for a transition period, the time likely to be needed to restore their livelihood and standards of living. The displaced persons should also be provided with development assistance such as land preparation, credit facilities, training or job opportunities, in addition to the other compensation measures stipulated.	The Social and Environmental Safeguards of the World Bank take precedence. All PAPS should be eligible for compensation at full replacement cost for lost assets and assistance to support livelihood restoration per World Bank Policy OP 4.12 requirements
Support for displacement	World Bank type policy pertaining to the restoration of income sources and livelihoods, support after displacement for a transition period; do not apply except as has been developed in response to natural disasters	Section 2 (c) – Displaced persons should be assisted in their efforts to improve their livelihood and standards of living or at least to restore them in real terms, to pre-displacement levels or to levels prevailing prior to the beginning of project implementation, whichever is higher.	The Social and Environmental Safeguards of the World Bank take precedence. All PAPS should be eligible for full compensation benefits per World Bank Policy requirements
Development assistance	The provision of elderly assistance, employment under the National Employment Programme; Free health services for Elderly and needs based social support are all available to qualifying PAPS	Section 2 (c) – Displaced persons should be assisted in their efforts to improve their livelihood and standards of living or at least to restore them in real terms, to pre-displacement levels or to levels prevailing prior to the beginning of project implementation, whichever is higher.	The Social and Environmental Safeguards of the World Bank take precedence. All PAPS should be eligible for full compensation benefits per World Bank Policy requirements
Opportunity to derive development benefits from project	There is no existing legislation or official policy document that specifically supports resettlement initiatives in Dominica	Performance Standard 5, Section 9 – The client will also provide opportunities to displaced persons to derive appropriate development benefits from the project,	The project will create temporary job opportunities during the civil plant and pipeline construction While some of the jobs will require specialized skills that may not be available locally, for non-specialized jobs, the project is expected to create equal employment opportunity for both men and women. In that regard the DGDC will as far as possible ensure that service providers give priority to the employment of workers originating from the Roseau Valley Communities.
Timing for the Payment of Compensation and Taking possession of Land Acquired	The Land acquisition Act Chpt. 53:02 is silent on the timing for compensation payments Sections 3 and 5 permits for access to lands any time after the publication	OP 4.12 Possession of the land acquired and related assets only after compensation has been previously paid in full.	The Bank's policy will take precedence. Identification of land owners and tenants has already been done and notification to the authorized officer completed. MOUs between Ministries are pending to facilitate monitoring and reporting by the DGDC

2.3 Institutional Framework for Addressing Land Acquisition and Leases

The Department of Lands already has a process in place for addressing land acquisition and leases including any grievances associated with this process. As such, DGDC will work closely with the Department of Lands during the resettlement process for this Project to ensure consistent coordination. As part of this process, the World Bank will complete an audit of the GoCD's institutional capacity for resettlement along a proposed action plan for any steps proposed to enhance the institutional capacity of this agency.

The following are procedures covered by the Act are applicable to the land acquisition process required for the geothermal project:

- Preliminary notification and power to enter the land:
 - If the Commissioner of Lands (the Authorized Officer) determines that any land is required for public purpose and it is necessary to make a preliminary survey or other investigation of the land, he/she may cause the publication of notification to that effect; and thereafter it shall be lawful for the Authorized Officer or his/her agents to enter on to the land to undertake the investigative works required.
- Power to apply land to purposes of acquisition without waiting for formal vesting:
 - At any time after the publication of a notification of the intention to acquire land for public purpose, it appears to the Authorised Officer that this land should be acquired, he/she may make an immediate declaration to that effect; and it is lawful for him/her to direct the Authorized Officer to do any work on the land connected with the use for which the land is being acquired.
- Appointment of Board of Assessment:
 - In the event that the parties cannot reach agreement on compensation to be paid, a Board of Assessment may be appointed and granted full power to assess, award and apportion compensation in such cases, in accordance with the provisions of the Act.

Sections 3 of the Act permits access to the land for investigative purposes before compensation is paid; Section 5 allows the government to take possession of land acquired and to commence development before compensation is paid. These provisions are not consistent with the World Bank's policy on involuntary resettlement, which states that the client will take possession of land acquired and related assets only after compensation has been made available and, where applicable, resettlement sites and moving allowances have been provided to the displaced persons in addition to compensation.

Given the commitment of the Government to comply with the Bank's policy, the DGDC has been delegated with the authority to act on behalf of the Ministry of Energy to provide support to the department. A Co-operation agreement to effect this was signed in November 2019 between Ministry of Lands and DGDC.

In relation to payments, though estimates have been provided to enable realistic budgetary allocation to be made for land acquisition in the national budget, if this is deficient, it will likely hinder the ability of the government to comply with the provision. Further, in cases where agreement over the payment of compensation cannot be reached between the Authorized Officer and the land owner, the appointment of a Board of Assessment would further delay payment. Experience has shown that negotiations for compensation (using either medium) can sometimes take several years to be concluded.

2.4 International Requirements

Relevant World Bank Group (WBG) requirements for this Project are contained in OP 4.12. According to the standard, resettlement is considered involuntary when affected individuals or communities do not have the right to refuse land acquisition or restrictions on land use that result in displacement which can occur when the buyer can resort to lawful expropriation when negotiated settlement fails. As stated earlier, as this Project can resort to expropriation or impose legal restrictions on land use through the Government of Dominica if negotiations fail, this Project triggers OP 4.12. OP 4.12 addresses land acquisition and involuntary resettlement. It recognises that land acquisition for projects and restrictions on land use can have adverse impacts on communities and people that presently use the land intended for a project.

2.4.1 OP 4.12- Involuntary Resettlement

According to OP 4.12, involuntary resettlement may cause severe long-term hardship, impoverishment, and environmental damage unless appropriate measures are carefully planned and carried out. For these reasons, the overall objectives of the Bank's policy on involuntary resettlement are the following:

- Involuntary resettlement should be avoided where feasible, or minimized, exploring all viable alternative project designs.
- Where it is not feasible to avoid resettlement, resettlement activities should be conceived and executed as sustainable development programs, providing sufficient investment resources to enable the persons displaced by the project to share in project benefits. Displaced persons should be meaningfully consulted and should have opportunities to participate in planning and implementing resettlement programs.
- Displaced persons should be assisted in their efforts to improve their livelihoods and standards of living or at least to restore them, in real terms, to pre-displacement levels or to levels prevailing prior to the beginning of project implementation, whichever is higher.

OP 4.12 covers direct economic and social impacts that both result from Bank-assisted investment projects and are caused by:

- the involuntary taking of land resulting in relocation or loss of shelter;
 - loss of assets or access to assets; or
 - loss of income sources or means of livelihood, whether or not the affected persons must move to another location; or
 - the involuntary restriction of access to legally designated parks and protected areas resulting in adverse; and
- impacts on the livelihoods of the displaced persons.

2.4.2 IFC PS5

The International Finance Corporation's Performance Standard 5 covers Land Acquisition and Involuntary Resettlement. Its requirements include:

- **Project Design:** consider feasible alternative designs to avoid or minimize displacement;
- **Compensation and Benefits for Displaced Persons:** when displacement cannot be avoided, offer displaced communities and persons compensation for loss of assets at full replacement cost and other assistance to help them improve or restore their standards of living or livelihoods;
- **Community Engagement:** engage with affected communities through stakeholder engagement;
- **Grievance Mechanism:** establish a grievance mechanism to receive and address specific concerns about compensation and relocation;

- **Resettlement and Livelihood Restoration Planning and Implementation:** where involuntary resettlement is unavoidable, a census will be carried out to collect appropriate socio-economic baseline data to identify the persons who will be displaced by the project, determine who will be eligible for compensation and assistance, and discourage ineligible persons from claiming benefits;
- In the case of physical displacement, the client will develop a **Resettlement Action Plan**; and
- In the case of economic displacement, the client will develop a **Livelihood Restoration Plan**.

PS5 also includes provisions for “Private Sector Responsibilities Under Government Managed Resettlement”. It specifies that, where land acquisition and resettlement are the responsibility of the government, the client will collaborate with the responsible government agency, to the extent permitted by the agency, to achieve outcomes that are consistent with this Performance Standard. In addition, where government capacity is limited, the client will play an active role during resettlement planning, implementation, and monitoring.

2.4.3 IDB OP-710

The IDB’s Operational Policy OP-710 covers Involuntary Resettlement. It sets out two fundamental principles:

1. Every effort will be made to avoid or minimize the need for involuntary resettlement.
2. When displacement is unavoidable, a resettlement plan must be prepared to ensure that the affected people receive fair and adequate compensation and rehabilitation.

The resettlement plans have to include compensation and rehabilitation that are deemed fair and adequate by ensuring that the resettled and host populations will: (i) achieve a minimum standard of living and access to land, natural resources, and services (such as potable water, sanitation, community infrastructure, land titling) at least equivalent to pre-resettlement levels; (ii) recover all losses caused by transitional hardships; (iii) experience as little disruption as possible to their social networks, opportunities for employment or production, and access to natural resources and public facilities; and (iv) have access to opportunities for social and economic development.

The following criteria applies to the design and appraisal of the Resettlement Plan:

- **Baseline Information.** Accurate baseline information must be compiled as early as possible. It will include information on the number of people to be resettled, and on their socio-economic and cultural characteristics, including disaggregation by gender. In addition, the data will provide an important basis for the definition of eligibility criteria, and compensation and rehabilitation requirements.
- **Community Participation.** The resettlement plan will include the results of consultations carried out in a timely and socio-culturally appropriate manner with a representative cross-section of the displaced and host communities. Consultations will take place during the design phase and will continue throughout the execution and monitoring of the plan, directly or through representative institutions and community organizations. Care will be taken to identify the most vulnerable subgroups and to ensure that their interests are adequately represented in this process.
- **Compensation and Rehabilitation Package.** Compensation and rehabilitation options must provide a fair replacement value for assets lost, and the necessary means to restore subsistence and income, to reconstruct the social networks that support production, services and mutual assistance, and to compensate for transitional hardships (such as crop losses, moving costs, interruption or loss of employment, lost income, among others). These measures must be taken in a timely manner to ensure that transitional hardships are not unnecessarily prolonged and do not result in irreparable harm. The options that are offered should be appropriate for the people affected and should reflect their capabilities and realistic aspirations. The compensation and rehabilitation package must take adequate account of intangible assets, especially non-monetary

social and cultural assets and, particularly in the case of rural populations, of customary rights to land and natural resources. Housing and service options, when included, will be appropriate for the social and cultural context and will, at the very least, meet minimum standards of shelter and access to basic services, regardless of conditions prior to resettlement. The design of compensation packages, as well as the community consultation and decision making mechanisms included in the resettlement program, will take into account the characteristics of the resettled population as identified in the disaggregated baseline data with respect to gender, ethnicity, age, and any other factors pointing to special needs and/or vulnerability.

- **Legal and Institutional Framework.** The resettlement plan must identify the legal and institutional context within which the compensation and rehabilitation measures have to be implemented. The first step in designing the compensation and rehabilitation package is to determine the entitlements of affected persons under applicable laws and regulations, to identify any services or social benefits to which they might have access, and to ensure that sufficient resources are available. The next step is to assess what additional measures are needed, if any, to restore the livelihoods of the affected population to the pre-resettlement standard, and to design mechanisms capable of delivering the goods or services that are needed, including effective and expeditious procedures for the resolution of disputes. This allows the compensation and rehabilitation package to work within the constraints of local laws and institutions, complementing them only as required, with project specific measures. This may lead to the identification of gaps in the local institutional and regulatory frameworks, that need not be incorporated into the resettlement plan, but which can eventually be addressed through institutional strengthening or other components if the borrower and the Bank so agree.
- **Environment.** Resettlement plans must take environmental considerations into account in order to prevent or mitigate any impacts that result from the development of infrastructure, densification of the host area, or pressure on natural resources and ecologically sensitive areas. An environmental impact assessment, including carrying capacity and socio-economic induced impacts on the host community, will be carried out for each proposed relocation site, wherever the magnitude of the resettlement component or the nature of the affected areas so requires, and the environmental management plan will be included in the resettlement plan.
- **Timeliness.** A preliminary resettlement plan must be prepared as part of the Environmental and Social Impact Assessment (EIA). It must undergo a process of meaningful consultation with the affected population, and must be available as part of the EIA, prior to the analysis mission. It must include sufficient information to be evaluated along with other project components. At a minimum, it must include: (i) evidence that appropriate measures have been taken to prevent new settlements in the area subject to resettlement; (ii) a tentative cut-off date for compensation eligibility; (iii) an estimate of the number of people to be resettled based on sufficiently reliable data; (iv) a definition of the various options to be made available under the compensation and rehabilitation package; (v) an estimate of the number of people that will be eligible for each option; (vi) a preliminary budget and schedule of execution; (vii) a diagnosis of the viability of the regulatory and institutional framework, identifying issues to be resolved; and (viii) evidence of consultation with the affected populations. The plan will be summarized in the Environmental and Social Impact Report (ESIR).
- The final plan must contain: (i) the definition of the final package of compensation and rehabilitation options; (ii) the eligibility criteria for each option; (iii) a reasonably accurate estimate of the number of people that will receive each option or combination; (iv) institutional arrangements and/or an execution mechanism that provides for the implementation of applicable local laws and regulations dealing with expropriation, rights to property, and the management of resettlement activities in a timely manner, assigns clear responsibilities for the execution of all elements of the resettlement plan, and provides for proper coordination with other project components; (v) the final budget funded within the overall project budget; (vi) a calendar for execution of activities required to provide the goods and services that comprise the

compensation and rehabilitation package, linked to landmarks of the overall project so that relocation sites (or other services) are made available in a timely manner; (vii) provisions for consultation and involvement of local entities (public or private) that can contribute to execution and assume responsibility for the operation and maintenance of programs and infrastructure; (viii) provisions for monitoring and evaluation, including funding, from the beginning of the execution period through the target date for achievement of full rehabilitation of the resettled communities; (ix) provision for participatory supervisory arrangements, which combined with monitoring, can be used as a warning system to identify and correct problems during execution; and (x) a mechanism for the settlement of disputes regarding land, compensation and any other aspects of the plan.

- **Monitoring and Evaluation.** The resettlement component of an operation must be fully and specifically covered in the reports on the progress of the overall project and included in the logical framework of the operation. The monitoring activities will focus on compliance with the resettlement plan in terms of the social and economic conditions achieved or maintained in the resettled and host communities. The plan and the loan agreement will specify the monitoring and evaluation requirements and their timing. Whenever possible, qualitative, and quantitative indicators will be included as benchmarks to evaluate those conditions at critical time intervals related to the progress of overall project execution. The final evaluation will be scheduled at a target date estimated for completion of the plan, defined as the date on which it is expected that the living standards the plan was designed to provide are achieved. In the case of global loans, the operational regulations will require Bank approval of the resettlement plan before a commitment is made to finance any subproject requiring resettlement. In all cases, independent supervision and multidisciplinary evaluation will be provided to the extent required by the complexity of the respective resettlement plan.

2.5 World Bank Group Supporting Guidance Documents

The following summarizes some key reference and supporting documents that have been referenced in development of this RAP:

- OP 4.12 - Involuntary Resettlement Policy;
- International Finance Corporation Environmental and Social Development Department – Handbook for Preparing a Resettlement Action Plan (2002);
- World Bank - Involuntary Resettlement Source Book (2004);
- IFC's PS5; and
- IDB's OP-710.

3. SOCIO-ECONOMIC BACKGROUND OF AFFECTED COMMUNITY AND PAP CENSUS

3.1 Regional and Local Socio-Economic Context

A socio-economic baseline study was carried out in 2017 as part of the ESIA for the Project. Further detailed surveys were completed as part of the RAP process in March-August 2018 to inform resettlement and livelihood restoration planning post Hurricane Maria. An additional socio-economic baseline study for the updated reinjection pipeline site was carried out in 2020. A summary of the PAP socio-economic census surveys conducted are presented below in Section 3.9.

3.2 Regional Overview

Dominica is a mountainous Caribbean island nation with natural hot springs and tropical rainforests. According to the Population and Housing Census of 2011, Dominica's population was 71,293 (Commonwealth of Dominica Central Statistical Office, 2011). Between 1991 and 2001, the population of the main townships of Dominica declined, including within the capital Roseau. The population of Dominica shows little increase in general, due to the exodus of people to other countries such as the more prosperous the United States, the United Kingdom and Canada.

In the Project vicinity, approximately 1,800 people live in the Roseau Valley, of which nearly 1,000 live in Trafalgar and Shawford, and the remaining in the hamlets of Wotten Waven/Casseau, Copthall, and Laudat. According to the 2011 census, the Roseau Valley gained 500 inhabitants between 2001 and 2011, i.e. a substantial increase of 32% (Commonwealth of Dominica Central Statistical Office, 2011). According to the Central Statistical Office, average household size in the Roseau Valley is 2.7. The breakdown of population by gender shows that Dominica consists of slightly higher men than women, national averages 49% females and 51% males.

3.3 Hurricane Maria 2017

In September 2017, Hurricane Maria hit Dominica with catastrophic effect. The economy came to a halt. Roads, bridges, and public utility systems were destroyed. The agriculture sector was devastated, with 100 percent loss of crops and substantial destruction to trees and livestock, which disproportionately affected the most vulnerable segments of Dominica's population. Other key sectors, including tourism, sustained substantial losses, with all hotels reporting serious damages and room availability down to near half of pre-storm levels. The rainforests, the main tourist attraction, were destroyed. Public services and transport activities were severely hampered. Most secondary roads, critical to access arable land and transport labour and agricultural products to markets and ports, were left inaccessible. Surveys in the Project affected communities suggest that 90% of the respondents have lost the roofs of their houses, and 95% of the respondents have lost their livelihoods.¹

Based upon an initial assessment of impacts to each affected sector by the World Bank, Hurricane Maria resulted in total damages of EC\$2.51 billion (US\$930.9 million) and losses of EC\$1.03 billion (US\$380.2 million), which amounts to 224 percent of 2016 gross domestic product (GDP). Most damages were sustained in the housing sector (38 percent), followed by the transport (20 percent) and education sectors (8 percent). The greatest economic losses were sustained in the agriculture sector (32 percent), followed by the tourism (19 percent) and transport sector (14 percent).²

¹ WBG Post-Disaster Needs Assessment, Hurricane Maria, September 18, 2017 completed November 7, 2017.

² WBG Post-Disaster Needs Assessment, Hurricane Maria, September 18, 2017 completed November 7, 2017.

3.4 Socio-Economic Area of Influence

Within the Roseau Valley, three main communities of Trafalgar, Wotten Waven and Laudat were considered as the primary socio-economic area of influence (Aol) because they were in closest proximity to the proposed Project and represent the main communities that would be likely to be impacted by any employment, resettlement, community health and safety issues. All of these fall within the Roseau Valley and data from the Roseau Valley itself is utilised where appropriate and when more detailed data for each community is not available. Figure 1.1 above shows the location of Trafalgar, Wotten Waven and Laudat.

Notwithstanding the changes to the project in 2019/2020 requiring the drilling of a new reinjection well in Laudat, the three communities remain the most likely to be affected, with more direct impact in Laudat.

3.4.1 Trafalgar

Trafalgar is located in the eastern portion of the Roseau Valley. The bulk of the population (959) in the valley reside in this area and it includes the most residentially developed of the three affected areas in the Aol. The area is characterised by brightly coloured concrete houses and includes a health centre and a primary school. At the bottom of the valley, the Trafalgar area is used for agriculture including vegetables, herbs and fruit orchards. Trafalgar Falls is also a tourist destination. The community generally has pride in their natural resources and expressed some mild complaints about the increased rate of rust on metal structures in the community from the steam/sulphur in the area.

3.4.2 Wotten Waven

Wotten Waven is well known for its natural hot sulphur springs and is located in a steep, inaccessible area. The wider area surrounding Wotten Waven area is characterised by agriculture including vegetables, herbs and fruit orchards. The area also includes some residences (population is 313), a health centre and a primary school. Since the 1990s there has been a considerable development in tourism services in the Roseau Valley. This is centred on hiking and the hot sulphur water spas in Wotten Waven.

3.4.3 Laudat

Laudat is a small village nestled between three mountains: Morne Watt, Morne Micotrine, and Morne Trois Pitons. Laudat contains a sector of rainforest where numerous trees are felled for economic development. Laudat also includes a small population of 321 and is served by a health centre. The Morne Trois Pitons National Park, Freshwater and Boeri Lakes and Segment 4 of the Waitukubuli National Trail are all in the greater Laudat area.

3.5 Economic Profile

Gross Domestic Product (GDP) in Dominica estimated in 2016 was US\$812 million according to the CIA World Factbook. The economy in Dominica used to be primarily driven by agriculture but has recently shifted towards tourism as the Government increasingly promotes Dominica as a tourist destination. The income of the residents of Trafalgar, Wotten Waven and Laudat was primarily derived from agriculture, which comprised family-based farming for both local consumption and commercial purposes, and tourism. Most of the Roseau Valley residents had several jobs, including employment in the town of Roseau. However, since Hurricane Maria the World Bank has estimated that economic damages and losses amount to approximately US\$1.37 billion or 226 percent of 2016 GDP.³ Agriculture, livestock, fisheries and tourism show the steepest declines. Tourism income has further declined in 2019/20 with a reduction in cruise calls, closure of borders during traditional summer months, cancellation of festivals and strict quarantine requirements for visitors due to the COVID-19 pandemic.

In 2016 according to the CIA World Factbook, the average unemployment rate in Dominica was about 23%. Now post Hurricane-Maria, the Post Disaster Report stated that a “significant” proportion of the labour force is unemployed. The report does not quantify what is considered “significant”. However, it could be assumed that the unemployment rate post Hurricane Maria, is greater than 23% and the livelihoods of its population were likely altered as a result.

3.5.1 Agriculture

Agriculture general accounts for about 20% of GDP in Dominica and employs about 40% of the labour force. As of late 2017 pre-Hurricane Maria, there were about 2,000 hectares (4,900 acres) of land being used as pasture land for animal husbandry, comprising 2.7% of the total land area. In addition to tourism, residents of the Roseau Valley were engaged in crop cultivation and agroforestry. Many properties in the study area included the growth of citrus, other fruits, vegetables, and some root crops for consumption and for sale.

Agriculture is the second highest income-earner for the Roseau Valley’s residents after tourism. However, from 2017 farmers were increasingly turning towards tourism which was considered more profitable.

Some villages in the valley were involved in commercial farming:

- Morne Prosper: mainly vegetables (the land is relatively flat).
- Wotten Waven: more diverse production of flowers, subsistence farming, tubers.
- Trafalgar: smaller-scale production more geared to tourism as well as tubers and 2 small poultry farms.
- Laudat: tuber production, vegetables and subsistence farming and a poultry farm.

In 2016 it was reported that there was a reduction in agriculture in most villages, especially Laudat and Trafalgar due to growth in tourism. In 2016, in the Roseau Valley, those working in agriculture are mainly women (in vegetable farming in Morne Prosper and Wotten Waven). Most farms were small production units comprising short-term and small-scale operations ($\frac{1}{4}$ - 1 acre, or 1,000 – 4,000 m²). Few farmers had larger lots of land, i.e. in excess of 5 acres, or just over 20,000 m².

Hurricane Maria caused substantial damage to agriculture in Dominica, including loss and damages to animals, crops, buildings, infrastructure and equipment. Damage to forest resources was also reported, with further impacts to agriculture. The greatest economic sector losses were sustained in the agriculture sector (32 percent), followed by the tourism (19 percent) and transport sectors (14 percent).⁴ It is probable that income from agriculture in the Roseau Valley has been significantly impacted.

The trend has changed slightly in 2020 given the reduction on tourism activities and there is a return to farming. The Ministry of Blue & Green Economy, Agriculture and National Food Security has launched initiatives including a WB funded “backyard” farming initiative in a bid to increase food security.

Unpublished statistics from the Ministry indicate that forty households from Laudat with a mean backyard size of 5900 square foot have participated.

3.6 Educational Profile

National school enrolment rates are quite high in Dominica at 97.5% for 5-9 year olds and 98.3% for 10-14 year olds (The Caribbean Development Bank, 2010). According to the Ministry of Education, in 2014, 75 pupils from the Roseau Valley were attending primary school. In July 2017, the Laudat and Trafalgar Primary schools were merged given the low number of students at Laudat. Approximately 224 students from the Roseau Valley were in Secondary School in 2014. Every village in the Roseau Valley has its own primary school, but pupils must travel to Roseau once they reach secondary school age. This can represent a significant cost for parents, especially for transport.

3.7 Health Profile

Life expectancy in Dominica is 77 years (81 for women and 74 for men). The death rate in Dominica is relatively low, 8.1-9.5 per 1000 live births between 2010 and 2015. The infant mortality rate was 20.8 per 1000 live births in 2015. According to 2017 data from the Ministry of Health, 5.5-6% of births in the country were born to residents of the Roseau Valley in 2015-2016. Chronic illnesses recorded in the Roseau Valley in 2015 included cancer, pneumonia, pregnancy related illness, hypertension, heart disease, motor neuron disease, birth defect, and diseases of the urinary system. Incidences of each were between 1-2 people. Malaria is not typically present in Dominica, but Chikungunya and Dengue fever are health concerns. At least 30 cases of Zika virus were confirmed in Dominica in 2016. According to the CIA Factbook, in 2014 5.5% of GDP was spent on health (Central Intelligence Agency World Factbook Website (2017)).

There are three health centres in the Roseau Valley one in each of the potentially affected communities (Trafalgar, Wotten Waven and Laudat). The Valley is also close to the capital of Roseau and its health facilities including the Princess Margaret Hospital, which is the country's top health care establishment. The hospital has 224 beds (including 56 in a psychiatric unit) and was recently expanded per the Caraïbes Environnement Développement & Coll, May 2015 Report on the initial environmental status of the Roseau Valley in Dominica.

Damage and losses to healthcare facilities post Maria were estimated at EC\$ 48.3M (US\$ 17.85M). The Princess Margaret Hospital (PMH), Roseau, the only referral hospital in the health care system, sustained severe damage with 15 percent of its buildings totally destroyed leaving only 53 percent functional. Central medical stores lost the majority of medical supplies due to water damage but most medications were spared. Bed capacity was decreased by 95 beds.

In September 2019, the first phase of the Dominica China Friendship hospital (which is to replace the PMH), encompassing A&E, surgical and dialysis care was commissioned. The facility is scheduled to be completed in Q3 2021. An additional 40,000 square feet two-floor hospital with a 75-bed capacity, as well as a wide range of essential services and modern state-of-the-art facilities is under construction in Marigot to serve the North-East of the island. Services to be provided by the New Marigot Hospital will include Ambulatory Services, Emergency Care, Intensive Care (ICU), Maternity and Paediatric Care, Laboratory and Radiology Services and Trauma Centre.

With regard to the COVID-19 pandemic, Dominica has lifted stay at home orders, and resumed some transportation options and business operations (US Department of State). In June 2020, the government stated that it would not be extending the state of emergency and the curfew that had been in place to curb the spread of COVID-19.³ The Center for Disease Control and Prevention states that Dominica's COVID-19 risk is moderate, with some increases of cases in the past 14 days. As of October 22, 2020, Dominica had reported a total 37 cases of COVID-19 since the beginning of the pandemic, with 29 recovered cases, 8 active cases and 0 deaths (Dominica Ministry of Health, Wellness and New Health Investment Response to COVID-19).

3.8 Gender

The Dominica Country Gender Assessment (CGA), commissioned by the Caribbean Development Bank (CDB) in 2014, provides a gender analysis of the economic, social and governance sectors in Dominica. The CGA indicates that Dominica's gender inequality index, which measures three aspects of gender inequality – reproductive health, empowerment, and economic activity – has not been calculated by the United Nations Development Programme (UNDP), because of the unavailability of relevant country data.

In terms of legislation, Dominica has neither signed nor ratified the Protocol to the Convention on the Elimination of All Forms of Discrimination against Women (Gender Equality Observatory for Latin

³ CARICOM, Dominica Lifts Curfew, State of Emergency (June 2020) accessed at: <https://today.caricom.org/2020/06/30/dominica-lifts-curfew-state-of-emergency/>


America and the Caribbean). The most recent legislation with regard to gender equality has been the Protection against Domestic Violence Act, in 2001 and amendments to the Sexual Offences Act in 1998 and 1992. The law does not prohibit sexual harassment. Civil society groups reported it was a pervasive problem (US State Department Human Rights Report for Dominica, 2019). With regard to domestic violence, the most recent data reports that two women died from domestic violence at the hands of their partners in 2015, one died in 2014 and one died in 2009 (Gender Equality Observatory for Latin America and the Caribbean). In 2010, there were 177 cases of reported child abuse against girls, vs 39 against boys (CGA). The Bureau of Gender Affairs did not disaggregate reported cases of gender-based violence, but there were 391 reports between 2011 and 2013 (CGA).

The US State Department Human Rights Report for Dominica, 2019 states that: "The law criminalizes rape of men and women, including spousal rape. Although the maximum sentence for sexual molestation (rape or incest) is 25 years' imprisonment, the usual sentence in 2019 was five to seven years. Whenever possible, female police officers handled rape cases involving female victims. Women were reluctant to report domestic violence to police. The only shelter for victims of gender-based violence remained closed after suffering damage during Hurricane Maria in 2017. Civil society reported that sexual and domestic violence was common. The government recognized it as a problem, but according to civil society groups, recognition of gender-based violence, particularly domestic violence, as a problem was low among the general population. Although no specific laws criminalize spousal abuse, spouses can bring battery charges against their partner."

With regard to teen pregnancies, it has increased in recent years, going from 17.5% in 1981 to 40.3% in 2009 (Gender Equality Observatory for Latin America and the Caribbean and CGA). This represents a significantly high incidence of teenage pregnancy. Data from the Gender Equality Observatory for Latin America and the Caribbean shows that 100% of births in Dominica are attended by skilled health personnel. The country's maternal mortality rate of 222.3 per 100,000 women (2010) represents a high rate, placing Dominica at 53rd in the global ranking (CGA).

In terms of education, secondary school enrolment for 2011/2012 was slightly higher for males (50.7% for males vs 49.3% for females) but the number of women in tertiary level education is significantly higher than the number of males (62.5% vs 37.5%) (CGA). For labor participation, 58.4% of the labor force in 2011 was composed of males and 41.6% of females; however, the unemployment rate in 2011 was slightly higher for males than females, standing at 12.3% vs 9.9% (CGA).

When it comes to autonomy in decision-making and women's participation in government, Dominica exhibits male dominance in Parliament, with a male: female ratio of 87.5%: 12.5% in 2014 (CGA). For 2013, the number of male vs female village councilors was 59% vs 41%, and the number of male vs female chairpersons of village councils was 71% vs 29% (CGA). The number of women legislators are illustrated in the Figure below for the years 1997-2019 (Gender Equality Observatory for Latin America and the Caribbean).



Source: Gender Equality Observatory for Latin America and the Caribbean

Figure 3-1: Number of Women Legislators (Percentage)

3.9 Vulnerability

In 2018 the social survey respondents, focus groups and wider community expressed that there were no specific vulnerable groups in the Roseau Valley. However, during project consultation, disabled members of the community were identified, including a blind member of household and elderly PAP who were without support services. Disabled members of the community would be considered vulnerable. Elderly members of the community that could be isolated and widows would also be considered vulnerable. In addition, residents of the Roseau Valley that have been unemployed for a significant length of time (2 years or more) could also be considered vulnerable.

Post Hurricane Maria and due to loss of income due to COVID-19, new vulnerable groups emerged. Surveys in the project affected communities suggest that 90% of the respondents had lost the roofs of their houses, and 95% of the respondents lost their livelihoods⁴. Rebuilding and government housing assistance programmes have alleviated this hardship in most communities. Among the non-salaried economically active population, 3.1 million workdays were lost post-Maria. The respective loss in work days and income resulting from Hurricane Maria, is likely to have resulted in a 25 percent decline in consumption, which could translate into an increased poverty rate of 36.2 percent (from 28.9% as reported in 2009). This may, in turn, have the undesirable effect of increasing income inequality, which researchers argue could lead to an increase in violence and crime. Those community members previously considered vulnerable e.g. elderly or disable, maybe have been adversely affected by the Hurricane and the damage it has caused, further increasing their vulnerability.

No PAPs indicated loss of income from COVID-19 but indicated psychological impact due to social protocols.

⁴ WBG Post-Disaster Needs Assessment, Hurricane Maria, September 18, 2017 completed November 7, 2017.

3.10 Detailed Socio-Economic Surveys

Initial face-to-face interviews and phone discussions were held in March 2018 with the PAPs to collect census level information and verify physical assets. Face-to-face interviews included completion of a census survey questionnaire and phone interviews, which were conducted to collect more limited data, consisted of approximately ten basic questions. Given the change in project scope and reinjection line PAPs, additional surveys were conducted during August-November 2020. All but two of the parties were able to complete the full census survey. Additionally, four other potentially affected property owners in the reinjection vicinity were interviewed, however, this data is not reported below as these parties were determined not to be directly affected by the Project at this time. Additional census data was collected during June and July of 2018 and again during August -November 2020 to get a complete picture of PAP socio-economic conditions. Findings relating to the PAPs are summarized below. Photographs of the PAPs properties and some additional data is provided in Appendix B.

It is important to note that certain circumstances, particularly cultural reticence to share income and livelihood information, may have influenced the responses to the socio-economic surveys.

Survey responses directly relevant to the RAP process are summarised as follows:

- A total of approximately 56 individuals (21 landowners and their households) were identified when all members of the affected PAP households were tallied. One PAP represents two properties.
- Only one of the PAPs currently resides in one of the four identified structures.
- The surveyed PAPs were generally aged 50 to 60+. Two of the PAPs are elderly. Approximately half are single and a half married. Half are women and half men. Households generally consist of 3-4 people.
- Two of the PAPs are supporting elderly parents and approximately half of the PAPs are also supporting teenage or older children and siblings.
- Five of the PAPs presently live overseas, some did not fill in the survey in full and provided limited information. Some own other land or property in the area. Some were farmers, vendors or small business traders, a midwife, stay at home parents, unemployed or construction workers.
- Most of the PAPs experienced some adverse effects from Hurricane Maria including structural damage, income loss, or had the need for government food rations.
- Most of the PAPs are elementary school graduates, some have high school degrees and four have college degrees. All own their respective properties or are representatives of persons owning their properties
- Average household monthly income is approximately \$EC 3,000 (approximately USD 1100-). Many of the PAPs indicated that they are supporting other family members. Most of the PAPs have other working members in their households, which may reduce their vulnerability. Most of the PAPs indicated that they are responsible for spending of household finances.
- All of the PAPs are aware of the proposed Project and none have expressed opposition to it or acquisition of their property if compensation is fair.

The following Table presents additional data on the PAPs and is complemented by the entitlement matrix in Table 5-1.

Table 3-1: PAP Socioeconomic Census Data

Number	Type of Business	Gender	Age	Primary Occupation	Marital Status	Duration of Business	Household Members	Highest level of education	Recent Illness/ Symptoms
PAP1	Farming (Structure which could be used as a residence on land)	Male	54	Self-employed farmer	Married	5 years	4	Secondary School	Daughter- spinal surgery – yearly checkups required in US
PAP2	Construction (abandoned partly constructed residential structure on land)	Male	74	Construction (living and working in the U.S.)	Married	7 years	5	College	
PAP3	Farming and Construction (residential structure, crops)	Male	62	Agriculture/Construction	Single	31 years	1	Primary School	None
PAP4	Homemaker (abandoned residential structure 5+ years)	Female	49	Homemaker (Living in Germany)	Single	20	5	College	none
PAP5	Midwifery	Female	56	Midwife	Single	19	4	Post-graduate, Masters Level	None
PAP6	N/A	Male	48	Living & Working in French Territories	Married	Unknown	4	Vocational Certificate	None
PAP7	Contractor	Male	50	Contractor	Married	N/A	7	Elementary	Blind, High Blood Pressure
PAP8	Tourism – out of business- In Liquidation(drill pad)	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
PAP9	Businessperson (drill pad)	Female	N/A	Businessperson	Married	N/A	N/A	Post-Secondary	None
PAP10	Retired Vendor/Subsistence Farmer	Male	61	Subsistence farmer	Single	45	4	Primary	Diabetes
PAP11(001)	Businessperson	M	42	Businessperson	Single	N/A	3	Secondary	None
PAP12(002)	Businessperson	F	65	Businessperson	Divorced	10	3	Tertiary	None
PAP13(003)	Social Worker	F	62	Social Worker	married	44	3	Tertiary	
PAP14(004)	No response	N/A	N/A	No contact info available lives overseas	N/A	N/A	N/A	N/A	N/A
PAP15(005)*	No response	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
PAP16(006)	Retired	F	64	Retired	Married	10	4	Primary	N/A
PAP17(007)	Retired	M	87	Retired	Widowed	10+	2	Primary	None
PAP18(008)	N/A Company	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
PAP19(009)	Lawyer	F	49	Property Manager	Single	12	1	Tertiary	None

PAP20(010)**	Unemployed	F	60+	Unemployed	Single	N/A	3	N/A	None
PAP21(011)	Retired (subsistence farming)	F	60+	Retired	Married	N/A	3	N/A	None

**Landowner recently deceased – heirs refused to respond*

*** - two parcels of land*

4. IDENTIFICATION OF PROJECT IMPACTS

4.1 Land Acquisition, Physical Displacement and Resettlement Impacts

For construction of the power plant, reinjection route and associated infrastructure, seven full properties at the power plant, four full properties for the reinjection pad (RVI2), a portion of eight other properties along the reinjection line, and a portion of one property for production pad A (RVP2) would need to be acquired. This would include three structures, one of which is classified as residential, one intended for residential use and one used for livestock (refer to Section 6 for further details). Only one structure is currently housing a PAP. These properties would be directly displaced by the Project footprint. This RAP therefore considers 22 properties in total since it includes two legacy properties still to be acquired. It is important to note that two of the properties are owned by the same PAP, so there are only 21 PAPs, listed in Table 3-1.


Of the twelve properties impacted by the construction of the reinjection route and drilling of the reinjection well, eight would only require acquisition of a portion of the property to accommodate a 10 m wide corridor. Table 4-1 below illustrates the acreage and percentage of each property required for acquisition for the reinjection line route, where the average plot size is approximately one acre. As the percentages required for each property are generally small, there is still an opportunity to minimize resettlement/livelihood impacts during the design phase by placing the reinjection line route in the areas of least impact within each property, or to avoid dividing a piece of land in two. The Table below presents the estimated amount of land to be acquired for the reinjection line, per PAP. Where the land is untitled, the acreage required is given.

Table 4-1: Estimated % of Land Acquired for Reinjection Line Route

Reinjection Line Affected Party No. (PAPs 1-10 are affected by the Power Plant and RVP2)	Estimated % of Land Acquired for Reinjection Line Route (based on 10 m wide corridor)
PAP 12	149 square feet/0.20%
PAP 13	4390 square feet/13%
PAP 14	10733 square feet
PAP 15	17326 square feet
PAP 18	Unknown (governed by RoW agreement)
PAP 19	2740 square feet/7.35%
PAP 20**	12266square feet/10.2% 3894 square feet


** - owns two parcels of land

Relocation to other sites was considered as part of the RAP process, particularly by two affected parties, but all but one of the affected parties opted for compensation. The costs and benefits of replacement land versus compensation were explained to the relevant parties. In the long-term, impacts are expected to decrease further as affected people realise some of the benefits of compensation, relocation and livelihood restoration initiatives, and as the other mitigation and monitoring measures are implemented along with community development initiatives. A map of Project affected plots is shown below in Figure 4.1 and Figure 4.2.



Source: DGDC

Figure 4-1: Properties Neighboring Power Plant Site



Source: DGDC

Figure 4-2: Properties Neighboring Preferred Reinjection Line

4.2 Economic Displacement and Livelihood Impacts

Along with experiencing physical displacement, some of the parties affected by resettlement for the proposed power plant site and the reinjection pipeline route will experience economic displacement effects as the affected properties include agricultural crops, livestock, and trees. In particular, surveys show that five of the directly affected parties for the power plant site and one tenant on the pipeline route are presently engaged in agricultural activities, growing citrus and other fruits and vegetables, raising rabbits and sheep on their property. Additionally, one of the parties have agricultural structures that would be affected by the project.

4.3 Gender Impacts

From the responses received, nine of the PAPs are female and eight male which is aligned to the wider Laudat community where 52.6% is male and 47.4% female. Of the female PAPs, one is retired and one is a homemaker, one male PAP is retired and elderly.

4.4 Ecosystem Services

The Project would also potentially impact ecosystem services in the Project area. The key ecosystem services which have the potential to be significantly affected by the Project are the ecotourism resources including medicinal plants, handicrafts, and water related resources. However, many of these resources were severely damaged in the hurricane. Additional on-site surveys would be required to determine with certainty the extent of the ecosystem services impacts, but given the hurricane damage, the likelihood of unique ecosystem services being affected is considered low.

5. ELIGIBILITY AND ENTITLEMENT

5.1 Overview

In the context of this RAP, 'entitlement' is a concept through which we determine the amount and type of compensation (or other support) to be provided to a PAP for a particular impact or loss category. The process begins by linking an array of affected assets and economic activities to an affected interest or legal right, then to a potentially affected party who is deemed 'eligible' or not according to specific conditions. If qualified, the affected party is then a candidate and considered 'entitled' to an appropriate compensation package. An entitlement matrix then identifies the category of affected PAPs along with their entitlement to the various forms of support. In this instance, the affected assets are considered to be crops, structures, properties and economic activity (farming).

5.2 Eligibility and Cut-Off Date

In order to identify persons who will genuinely be displaced by the Project and who are eligible for compensation and assistance and differentiate from ineligible persons (such as opportunistic parties hoping to claim benefits), a cut-off date has been established. After the cut-off date, it is considered that the affected parties and wider public have been appropriately informed not to make improvements to, or settle on, the identified project land. Under the requirements of OP 4.12, the Project is not required to compensate encroachers after this date. The cut-off date for this Project has been established as 15 November 2020. This is the date that the detailed socio-economic survey in the community was completed for most of the affected parties and whereby the final number of farmers on the site was confirmed. Any additional persons establishing farming plots or other activities on the site after the cut-off date will not be considered as PAPs and will not be eligible for compensation. Because the potentially affected community is small (21 total property owners), the cut-off date was communicated directly to the community during meetings and one-on-one interviews, during August to October 2020.

5.3 Entitlement Matrix for Compensation

The entitlement matrix presented below in Table 5.1 captures all PAPs, the characteristics of the impact, and the types of compensation/measures to be applied. PAPs will be entitled to a combination of compensation measures, relocation and livelihood assistance, depending on the nature and extent of the impact and lost assets, as detailed in Tables 6-1 to 6-3, and their preferences. Social and economic vulnerability will be considered in determining the level of assistance provided (as discussed in Section 5.4).

Compensation and assistance will broadly consist of one or more of the following types:

1. Compensation for loss of land;
2. Compensation for the loss of trees or crops;
3. Compensation for the loss of structures;
4. Transitional financial assistance to support any movement of structures or crops;
5. Income restoration for the loss of a business or significant agricultural loss;
6. Livelihood restoration assistance; and
7. Additional support for identified vulnerability.

A principle of this RAP is that affected party livelihoods will be restored to pre-project standards and, if possible, improved. PAPs determined to be entitled to replacement land were offered that option. Details of the PAPs entitled to some form of compensation are described in Section 6. The nature of the compensation proposed following assessment of entitlement and eligibility is provided in Section 6, Valuation and Compensation.

Table 5-1: Entitlement Matrix

PAP Category	Type of Loss	Eligibility Criteria	Entitlement	# PAPs Affected	Details of Support/Compensation
Power Plant and ReInjection Route Landowners (where more than 20 percent of land needs to be acquired for the Project)	Permanent loss of land	Land title or other document establishing ownership in case of unregistered land to affected property.	Compensation at replacement cost ⁵ Valuations done using market value (considerations detailed in text following matrix) plus all transaction costs and statutory fees.	13 – PAP #1,2,3,4,5,6,7,9,10,11,16,17, 21 Note: PAP 9 is a legacy property for WW01	Appropriate price/compensation as mutually agreed with the landowners. The value agreed will be based upon the individual valuations completed by the Dominica Lands and Surveys Division, consistent with the methodology outlined in the basis of compensation letter completed by DGDC for the RAP included in Appendix A. This meets replacement costs per OP 4.12
Power Plant and ReInjection Route owners or land users	Permanent loss of trees and crops	Permanently growing crops or trees on affected property for at least one year prior to property acquisition, including pre-hurricane Maria.	Financial compensation for crops/trees. Valuations done using combination of cost of production, selling price at time of valuation and future bearing capacity.	6 – PAP #1,2,3,6,7,10	Cash compensation for the loss of trees, crops, perennials based on estimated crop values from the WB April 2018 Post Disaster Needs Assessment.
Power Plant and ReInjection Route owners or occupants	Permanent loss of a residential structure	Permanently residing on the affected property prior to property acquisition, including pre-hurricane Maria.	Compensation for lost assets. Structure will be valued by the PVU and compensation paid to the owner of the structure. Moving/transitional assistance	2 – PAP #1, 3	Appropriate price/compensation as mutually agreed with the landowners based upon Government valuation asset values. Moving assistance in lump sum payment.
Power Plant and ReInjection Route owners or land users	Permanent loss of an agricultural structure	Commercial structure present on the affected property prior to property acquisition.	Compensation for lost assets. Structure will be valued by the PVU and compensation paid to the owner of the structure. Moving/transitional assistance.	2 – PAP #1, 3	Appropriate price/compensation as mutually agreed with the landowners based upon Government valuation asset values. Moving assistance in lump sum payment.

⁵ Replacement cost means that the affected person can replace the affected asset to the same condition. Replacement cost typically reflects market value plus transaction costs, transfer or retitling fees, and salvageable materials.

Note: Two of the four structures referenced in the text have been abandoned for 5 plus years. Only one PAP resides on his property.

PAP Category	Type of Loss	Eligibility Criteria	Entitlement	# PAPs Affected	Details of Support/Compensation
Land owners with loss of income due to loss of land use	Loss of income	Farmers or business owners operating on affected property for at least one year prior to property acquisition, including pre-hurricane Maria.	Assistance for livelihood restoration. Provide access to existing social programmes: 1. Elderly pension and health care services 2. Skills training programmes	6- PAP #1,2,3,6,7,10	Loss of income compensation will be provided based upon a percentage of income loss experienced by the affected party.
Vulnerable households including households headed by women, elderly, very poor, disabled, or those affected or displaced by the effects of Hurricane Maria	Loss experienced by vulnerable parties	Qualifies under one of the above eligible criteria and is considered 'vulnerable' including widows, sole income source in the household, elderly.	Additional assistance to households for 3% of their annual income according to vulnerability levels.	4 – PAP #1, 2, 17, 20	Supplemental compensation for loss of annual income. Priority for community enhancements including health and education components. Priority for livelihood and agriculture restoration components. Priority for suitable employment and transport to nearby shopping if needed.

5.4 Vulnerable Parties and Gender Considerations

Vulnerable parties are often at a disadvantage to participate and benefit from social and economic opportunities in their communities or need special assistance to do so. Women have important economic roles and engage in a very wide range of income making activities in the agricultural and marketing sector. The RAP pays particular attention to ensuring that vulnerable people and women are the recipients of compensation pertaining to and reflecting their full activities. As a result, women and vulnerable people have been encouraged to actively participate in all Project-related resettlement consultations and negotiations and certain meetings have been conducted with women's groups. Special mitigation actions / measures for vulnerable people / women have been prepared and included in the RAP (Section 7). All compensation due to woman-headed families will be given directly to the woman family head. RAP monitoring and evaluation will pay special attention on the impact of resettlement on women and other vulnerable people. Assistance to vulnerable parties is discussed further in Section 7.2.

6. VALUATION AND COMPENSATION

6.1 Assessment of Land Value

The valuation methodology for the land compensation presented below was based on initial valuations by the provided by the Department of Lands and Surveys in July 2018 for some of the properties and estimates by DGDC based upon reference to other land valuations completed by the Department of Lands for the properties in the same area in 2017. The values were revisited in September 2020, and have remained the same given no major changes from the July 2018. The landowners were notified that their properties could be required for the project. Owners, or their representatives, of five of the seven properties under consideration for the power plant were present when the land surveys were carried out. The compensation rates to be proposed to the landowners were developed considering compensation based upon replacement value, as required by OP4.12, which includes; the market value of the land, transactional costs (legal fees associated with the process of selling and buying of land on average 10.5 % of market value), and any other fees associated with time delays as enshrined in the laws of Dominica. In ascertaining the market value of land, the property valuation unit of the Ministry of Housing and Lands relies on the individuality of each property. Physical inspection of the sites are carried out and factors such as services, access, topography, land use, size and market demand are taken into consideration. As noted below, Parties 4, 5 and 7 are included in the RAP and valuation estimates, but properties not directly required for the Project. They are included in the plan due to potential noise, visual and construction impacts. Formal property evaluations and negotiations and compensation will be completed by the GoCD, Department of Lands and Surveys, prior to construction. Affected parties shall be properly consulted in line with OP 4.12, IFC PS5 and OP-710 prior to any land acquisition. An estimate of relevant property values is provided in the Table below.

Table 6-1: Assessment of Property Values

Affected Party No.	Affected Area Project Component	Land area	Total Land Compensation* Replacement Value
1	Power plant site	439,520 ft ²	EC\$ 378,150 USD 139,916
2	Power plant site	158,994 ft ²	EC\$ 255,500 USD 94,535
3 ⁶	Power plant	32,670 ft ²	EC\$ 163,350 USD 60,440
4 ⁷	Power plant	45,128 ft ²	EC\$ 135,384 USD 50,092
5 ⁸	Power plant	23,216 ft ²	EC\$ 69,652 USD 25,771
6	Power Plant	17,688 ft ²	EC\$ 88,440 USD 32,723

⁶ Owner has also expressed to DGDC that if power plant is constructed, they wish DGDC to purchase as they do not wish to live next to the power plant. Value: DGDC estimated based on surrounding lands.

⁷ Property not required for the Project, but included in the plan due to potential noise, visual and construction impacts, and possibility that owners may wish to move if power plant is constructed.

Affected Party No.	Affected Area Project Component	Land area	Total Land Compensation* Replacement Value
7 ⁸	Power Plant	4,797 ft ²	EC\$ 9,594 USD 3,550
8	Legacy Property	37,035 ft ²	EC\$ 19,550 USD 7,234
9	Legacy Property	242150 ft ²	EC\$ 361,335 USD 133,694
10	Production Pad(RVP2)	7.56 acres	EC\$ USD
11	Reinjection Pad	0.842 acres	EC\$ 25260 USD 9,346
12	Pipeline route	149 ft ²	(based on 10m wide corridor): EC\$ 522 USD 193
13	Pipeline route	4390 ft ²	(based on 10m wide corridor): EC\$ 15365 USD 5,685
14	Pipeline route	10733 ft ²	(based on 10m wide corridor): EC\$ 37,565.50 USD13,899
15	Pipeline route	17326 ft ²	(based on 10m wide corridor): EC\$51,978 USD19,232
16	Reinjection Pad	1.6469acres	EC\$49407 USD18,281
17	Reinjection Pad	21344.4ft ²	EC\$17150 USD6,346
18	Pipeline route	Unknownft ²	(based on 10m wide corridor):easement agreement in progress
19	Pipeline route	2740ft ²	(based on 10m wide corridor): EC\$13,700 USD5,069
20**	Pipeline route	1.12268ft ² 2.3894 ft ²	(based on 10m wide corridor): 1.EC\$ 36,804 USD13,617 2.EC\$19470 USD7,204
21	Reinjection Pad	1.44acres	EC\$43,200 USD15,984

Source: Government Valuations completed in November 2020 and DGDC Estimates.

*USD Conversion Rates based upon exchange rate of 1 ECD =0.37 USD as of Dec 2020

**- owns two parcels of land

6.2 Assessment of Crops/Trees/Livestock Compensation Values

Six identified PAPs will lose assets in the form of their crops. The values presented in the Table below are an estimate of current market value for the crops based on World Bank crop loss data set developed as part of the Post Disaster Needs Assessment after Maria in 2018 presented in \$EC (East Caribbean dollars) and United States Dollars (USD) equivalent. Total compensation identified below in Table 6-1 also includes loss of income. The Ministry of Agriculture & Fisheries will carry out valuations of affected crops and determine the actual compensation payment. Valuations are completed by extension officers of the Ministry of Agriculture & Fisheries who have intimate knowledge and understanding of the holdings. Crops are valued using the following bases:

- Cost of Production if farm records exist;
- Market value (selling prices) at time of valuation if no records exist; and
- Bearing capacity for well-established farms.

Crop valuation falls under the purview of the Ministry of Agriculture & Fisheries. The values assigned to crops are specified as a range and are set by a committee of technical experts who take into consideration factors such as the species, location, production cost, market value, climate and environmental influences. The applicable range for each crop is documented in the Ministry's "Crop Valuation Guide", and a comprehensive list of crops and economic trees under the following broad categories:

- Fruit and tree crops;
- Vegetables and herbs;
- Cut flower and ornamental plants; and
- Food and root crops.

Where crops are being valued for displacement from the land or removal of the crop, the economic life of the crop is considered (particularly for tree crops). When a valuation is required for an assessment of damage to the crop, where the crop continues to grow but growth is retarded, the age at the time of damage is considered. The aforementioned provisions are generally in keeping with World Bank policy.

Contrary to local practice, however, OP 4.12 notes that in some countries, the value of the harvest is determined by the average market value of crops for the previous three years. It states further that whatever the multiplier, if food supplies are sold in the area enough cash compensation is paid to purchase equivalent supplies, taking into account the possibility of price increases caused by heightened demand from displaced persons.

Table 6-2: Crop/Tree/Livestock Values

Affected Party No.	Area of affected Crops/Livestock/Trees	Crops/Livestock/Tree Values EC ⁸	Total Compensation*
1	70 Rabbits 6 sheep	Both sheep and rabbits to be moved Moving costs estimated at EC\$ 1000	EC\$ 1,000 USD 370
2	150 Grapefruit Trees 10 Orange Trees 20 Coffee Plants	EC\$ 21,730 EC\$ 1,449 EC\$ 1,670	EC\$ 24,849 USD 9,111

⁸ Formula for valuation = acreage x years to re-establish crop/tree x typical production per acre x unit value for loss of production + number of crops trees x value to replace crop/tree.

Affected Party No.	Area of affected Crops/Livestock/Trees	Crops/Livestock/Tree Values EC ⁸	Total Compensation*
3	Trees/Crops: 8 Orange 5 Lime 8 Lemon 8 Westinsian Lime 4 Grapefruit 8 Tangerine 2 Soursop 4 Coconut 2 Sugar Apple 8 Coffee 4 Valencia Orange 4 Atomic Orange	EC: \$1,159 \$655 \$697 \$909 \$349 \$601 \$155 \$1,048 \$81 \$668 \$579 \$579	EC\$ 7,479 USD 2,742
6	Trees/Crops: 6 Orange 6 Grapefruit 1 Sugar Apple 1 Guava 2 Coconut	EC: \$869 \$523 \$41 \$47 \$524	EC\$ 2,004 USD 735
7	Trees/Crops: 31 Orange 3 Coffee 2 Grapefruit	EC: \$4,491 \$250 \$174	EC\$ 4,916 USD 1,802
10	Trees/Crops: 200 Dasheen 15 Corn	EC: \$600 \$130	EC\$730 USD270

Source: DGDC November 2020 communication and WB crop rates as used in the Maria PDNA.

*USD Conversion Rates based upon exchange rate of 1 ECD =0.37USD as of Dec 2020



Figure 6-1: Photograph of Affected Rabbit Hutch

6.3 Assessment of Assets, Residential and other Structures

Four identified PAPs will lose assets in the form of established structures. Determination of the compensation value for the structures was established based upon valuations provided by the Department of Lands and Surveys in July 2018 and revised in November 2020. Compensation for residential and other structures is based on this calculation by the Department of Lands and Surveys. Formal negotiations are ongoing. Photographs of Affected Structures are included in Appendix A. One property PAP#3 is pending valuation since permission has not been provided to access the property. Efforts are being made by the Lands and Surveys Department and DGDC to contact the owner directly to facilitate the process.

Table 6-3: Structural Valuations

Affected Party No.	Sq footage of Affected structure	Total Compensation*
1	Potential Residential House/Currently livestock dwelling – 1,017 ft ² Rabbit Hutch - 308 ft ²	EC\$ 40,000 USD 14,814
2	Incomplete, Abandoned Residential House - 418 ft ²	EC\$ 62,700 USD 23,222
3 ¹	Abandoned Residential House -	Site inspection pending
5	Residential House - 144 ft ² Shed -160 ft ²	EC\$ 25,000 USD 9,259

Source: Government Valuations completed July 2018, revised Nov 2020 *USD Conversion Rates based upon exchange rate of 1 ECD =0.37USD as of Dec, 2020.

¹ PAP lives overseas, caretaker has denied entry to the property for valuations. Communication is ongoing to resolve matter.

There is also one residential property on the reinjection pipeline route, but it is not in the part of the property that is needed for acquisition. Therefore, it is not considered in the table above.

6.4 Compensation Payment Procedure

Formal property evaluations for all of the affected properties will be completed by the GoCD Department of Lands and Surveys prior to construction followed by negotiations with the affected parties. On the basis of these negotiations, and completion of internal processes, the Ministry of Housing & Lands will disburse compensation to the affected parties. Prior to disbursement of compensation, each eligible PAP will sign a compensation certificate which sets out the mutual commitments for each party. The format of the certificates will be easily understandable to affected people. This will be countersigned by the Ministry of Housing & Lands and representatives of DGDC will be present for this process.

Following agreement and signing of the certificates, compensation will be disbursed as indicated, livelihood restoration activities will commence and the PAPs will be requested to vacate the site. DGDC will, in collaboration with the Division of Lands and Survey, be responsible for reporting on the receipt of the financial compensation of the PAPs and will arrange in kind compensation for any follow-up training.

In certain cases, it may not be feasible to pay compensation to all parties before taking possession of the land, for example when the ownership of the land in question is in dispute. There may also be cases where the landowner is out of the country. Under such circumstances, compensation funds shall be

made available for each party through deposit into an individual escrow account for that PAP. This is not the case for any of the PAPs covered in this RAP.

6.5 Livelihood Restoration and Enhancement Measures

The benefits of livelihood restoration measures were highlighted to the PAPs during consultation, such as the potential for long-term income generation, and diversification of options for themselves and their families, in contrast with cash compensation which can often be quickly consumed. Most PAPs expressed a preference for cash compensation only. However, additional measures were considered such as counselling in family health matters, business and financial management support, and post-hurricane support.

7. VULNERABILITY ASSISTANCE

Vulnerable people can be defined as, those below the poverty line, the landless, the elderly, disabled, women and children, indigenous peoples, ethnic minorities, or other displaced persons who may not be protected through national land compensation legislation (World Bank, OP 4.12).

Key factors which could be considered indicators of vulnerability for the identified PAPs include:

- Many in the communities impacted reported that they lost the roofs of their homes due to Hurricane Maria;
- Many in the affected communities reported that they have lost their livelihoods as a result of Hurricane Maria;
- Any loss of income related to COVID-19;
- Some of the PAPs are unemployed, low-income or single party headed households; and
- Some PAPs are elderly community members.

The RAP process has considered the potential for impacts on vulnerable PAPs and findings indicate that additional support should be applied to the PAPs as several would be considered vulnerable. Table 7-1 presents a vulnerability matrix for the PAPs.

Table 7-1: Vulnerability Matrix

PAP No.	Sole earner in household	Elderly or Disabled	Unemployed, low income	Receipt of Government Support Programs	Home or livelihood damaged by hurricane	Considered vulnerable
1	No	No	Yes- low income	Yes	Yes	Yes
2	Yes	Yes	Members of household unemployed post-Maria	No	No	Yes
3	Yes	No	No	No	Yes	No
4	Unknown	No	Unknown	Social support in Germany	Yes	Unknown
5	No	No	No	Yes	No	No
6	No	No	Living Overseas	No	No	No
7	No	No	No	No	Yes	No
8	Business	N/A	N/A	N/A	N/A	No
9	No	No	No	No	No	No
10	No	No	No	No	No	No
11	No	No	No	No	Yes	No
12	No	No	No	No	Yes	No
13	No	No	No	No	No	No

PAP No.	Sole earner in household	Elderly or Disabled	Unemployed, low income	Receipt of Government Support Programs	Home or livelihood damaged by hurricane	Considered vulnerable
14	Unknown	No	Living overseas – no contact	No	No	No
15	Unknown (Heirs of newly deceased – no response)	No	No	Unknown	Unknown	Unknown
16	No	No	No	No	Yes	No
17	No	Yes-elderly	No	No	Yes	Yes
18	Business	N/A	N/A	N/A	N/A	No
19	Yes	No	No	No	No	No
20**	Yes	No	Yes	No	Yes	Yes
21	No	No	No	No	Yes	No

Notes: N/A as this is a commercial business. **- owns two parcels of land

7.1 Forms of Assistance

Three of the PAPs are unemployed or low-income, four are sole earners in their households and two are elderly or are supporting elderly family members and ten experienced loss after Hurricane Maria. In total, four of the PAPs would be considered vulnerable. As such, the RAP provides an additional safety net for vulnerable households. Project-affected households and landowners that are vulnerable could potentially experience severe hardship during the livelihood restoration process and as such monitoring of these parties will be particularly important. Regular visits to each PAP will be conducted to ensure that the PAPs retain their place to live, means of income, access to medical care, and access to food and welfare of vulnerable persons, in this case all of the PAPs will be specifically tracked and reported upon by the DGDC. Further detail on Project roles and responsibilities is included in Section 10.

7.2 Compensation for Vulnerable PAPs

Compensation due to vulnerable PAPs will comprise:

- Cash payment for the supplemental compensation consisting of 3% of the PAPs typical annual income for a year by the DGDC;
- Additional assistance may take the following forms, depending upon vulnerable persons' requests and needs;
- Assistance in employment training, access to and provision of healthcare, and educational support;
- Assistance in the compensation payment procedure (e.g. specifically explain the process and procedures, make sure that documents are well understood);
- Assistance in the post-payment period to secure the compensation money and reduce risks of misuse/robbery; and
- Counselling in domestic matters such as family, health, or finances.

8. STAKEHOLDER ENGAGEMENT

8.1 Introduction

In the context of resettlement and economic displacement, stakeholder engagement serves as both an opportunity for information exchange for consultation purposes and as a collaborative form of decision-making and participation. Full details of the stakeholders consulted during each stage of the ESIA process, and the detailed outcomes and observations are provided within the ESIA, the Addendum to the ESIA and Project Stakeholder Engagement Plan (SEP) and are not repeated in this RAP.

The main objectives of consultation undertaken to date for the Project include:

- To provide information about the Project and its potential impacts to those interested in or affected by the Project, and solicit their opinion to that regard;
- To understand and address stakeholder concerns and expectations of the Project;
- To manage any unrealistic expectations and address misconceptions regarding the Project;
- To ensure participation and acceptance of the Project throughout the lifetime of the project by the key stakeholders including the community;
- To provide avenues to address any stakeholder grievances regarding the Project; and
- To agree on the asset valuation / compensation and livelihood restoration measures associated with this RAP process and discuss potential concerns.

8.2 Consultation with the Affected Community

During the geothermal drilling phase, eleven general public meetings were held in the potentially affected communities in November and December 2013 and January 2014. Five were held in Laudat, three in Trafalgar and three in Wotten Waven. A visit to the current geothermal power plant in Guadeloupe was also conducted in 2012 with members of the community to experience first-hand the workings of an operational plant. Additionally, school visits were conducted in February and March 2012 from the Wotten Waven Primary School, Trafalgar Primary School, Morne Prosper Primary School, Laudat Primary School, and Laudat Primary School where students and staff toured the drilling sites. In addition to the recent public engagement, the Grievance Mechanism was socialised within the community during the 2017 social baseline survey process.

Additionally, a town hall meeting was held in Trafalgar in December 2016 with approximately 40 in attendance to discuss the current project and ESIA. Another town hall meeting was held in Laudat in July 2017 with 43 in attendance. A third town hall meeting was held in Wotten Waven in August 2017. A final town hall meeting will be held to present the findings of the ESIA in May or June 2018. In order to facilitate further understanding of community needs and conditions, focus group meetings were held in 2016, 2017 and 2018 in Wotten Waven, Trafalgar and Laudat, described in further detail below. Because the total population of the Project AOI is relatively small (approximately 1,600), and given that the general public and many of the focus groups and landowners that would be affected by the Project are the same parties, the four formal public meetings and 15 informal forums held on the Project were considered representative of the community.

A total of 15 focus group meetings were held as part of the ESIA baseline data collection. A meeting with six representative community leaders from all of the potentially affected communities was held in Trafalgar in November 2016 to discuss the Project and the most effective means of stakeholder engagement. Focus groups meetings were also held in June, July and August of 2017 including meetings with representatives of local hotels and resorts, handicraft vendors, hot springs businesses, and

unemployed parties in the area. Groups consisted of 5-15 people and targeted questions were asked and recorded. In addition, five focus group meetings were held in the communities in March 2018 following Hurricane Maria. These included meetings with community women in Laudat, Wotton Waven and Trafalgar, and vendor meetings in Wotton Waven and Trafalgar, to identify the impacts on the community of Hurricane Maria which hit Dominica in September 2017 and to understand how conditions in the Project area have changed since the ESIA baseline data was collected pre-Hurricane Maria.

Two national consultations on the Jacobs ESIA were conducted in February 2019 one in the south and one in the north (Portsmouth). A series of public meetings to update the community on the changes in the project were held in June 2020. Given the COVID-19 public gathering protocols, the DGDC conducted 3 sessions per day for three days to allow for maximum community participation. As part of the ESIA process for the Eclipse Inc conducted 3 focus group (women, landowners and youth) meetings in August 2020 and another meeting to present the findings of the ESIA to the community in November 2020.

8.3 Consultation on the RAP

In accordance with the WBG policies (“Involuntary Resettlement Policy” and “Land Acquisition and Involuntary Resettlement” respectively), consultation on the RAP included conducting a socio-economic census survey in 2017-2018; consultation with the project affected parties on the RAP with relevant government institutions such as the Department of Lands & Surveys; and presentation of the findings of the RAP to the affected communities in 2018. Further consultations were held with new PAPs in 2020 and updated census information for those previously interviewed. The recurring concern of PAPs was that they would be fairly compensated for their lands in a timely manner. DGDC continues to present the issue of timely acquisitions and compensation to the Ministry of Lands. The relevant department consists of a small staff and various government re-housing projects are in progress. Any comments on this RAP from the community or relevant institutions will be incorporated into a final RAP. The RAP will be updated as necessary with any new information from consultations with community or relevant institutions.

9. RESETTLEMENT SITES

In accordance with World Bank resettlement policies, resettlement sites were considered for two of the PAPs identified. One preferred site was identified on the basis of location, community continuity, access to productive resources, employment, and livelihood restoration consideration. The affected PAP wanted to remain local, on a site with land that would be productive for agriculture, and with easy access from local roads, on plots of a similar size to their previous property. A photograph of the preferred site for resettlement site is included below in Figure 9.1. The costs and benefits of replacement land were explained to both PAPs. However, although the pros and cons of replacement land were explained in detail to this party, one of the two PAPs has now indicated a preference toward compensation as they felt that they would prefer the cash and would be in a better position to negotiate a lower price for the land.



Figure 9-1: Photograph of Resettlement Site 1

An additional PAP had expressed interest in a replacement property, but no specific site had been identified. This PAP has since indicated a preference for cash compensation. All the other PAPs with affected property opted for cash compensation.

Only one single person household will be physically displaced.

10. ROLES AND RESPONSIBILITIES

10.1 Overview

The land acquisition process including negotiations and final compensation will be completed by the GoCD Department of Lands and Surveys including addressing any grievances related to land acquisition. DGDC will manage livelihood restoration related and resettlement (not including land acquisition) grievances consultation, grievance redress, monitoring and evaluation of the affected parties for this RAP. DGDC has appointed a Community Liaison Officer (CLO) and Social Safeguards Specialist to support the ongoing community consultation and engagement process, both generally and specifically regarding this RAP, and who will support in this process. The CLO role will continue into the operational phase. A cooperation agreement between the DGDC and GoCD is in place (November 2019) to formalise this relationship.

10.2 Organizational Responsibilities

This section presents the organizational framework for implementing resettlement, including:

- identification of agencies responsible for delivery of resettlement measures and provision of services;
- arrangements to ensure appropriate coordination between agencies and jurisdictions involved in implementation; and
- and any measures (including technical assistance) needed to strengthen the implementing agencies' capacity to design and carry out resettlement activities; provisions for the transfer to local authorities or resettlers themselves of responsibility for managing facilities and services provided under the project and for transferring other such responsibilities from the resettlement implementing agencies, when appropriate.

Key roles and responsibilities with regards to the RAP are set out in Table 10-1.

Table 10-1: Roles and Responsibilities

Stakeholder	Interest	Roles/ Responsibilities	Timescale for Action
GoCD	Responsible for Land Acquisition Process	Complete formal land valuation for each property Complete compensation negotiations with each PAP Disburse compensation to each PAP. Manage acquisition of replacement properties as needed. Ensure the receipt of the financial compensation of the parties. For replacement property, ensure that once the property cost has been agreed, the property would then be transferred to them. Manage grievances related to land acquisition.	Prior to construction (2-3 months)
PAP	Affected properties, structures, and economic activity on site	Engage with socio-economic surveys Engage in consultation process Vacate project site as agreed on compensation certificate.	Present-vacation of site (next 3 months)
DGDC	Project developer	Engage appropriate organisations/individuals to implement the RAP. Facilitate good communications and relations with the PAPs	Present-ongoing

Stakeholder	Interest	Roles/ Responsibilities	Timescale for Action
		Manage livelihood restoration process and vulnerable party resettlement issues. Respond to livelihood restoration and resettlement (not including land acquisition) feedback and grievances in a timely manner.	
Social Safeguards Specialist	DGDC team	Implement RAP economic displacement Provide liaison between DGDC and PAPs Monitor RAP, with particular attention to vulnerable persons Identify and provide additional support as required.	Present-ongoing throughout Project operations
CLO	DGDC team	Support Implementation of RAP Manage General Grievances Responsible for general Project-related community consultation.	Present-ongoing throughout Project operations
Consultant	Consultant	Audit / supervise the process.	TBD
Eclipse	Consultant	Conduct socio-economic surveys of PAPs	July-November 2020

10.3 Compensation Payment Procedure

Appendix B presents the basis of proposed compensation and plan for each PAP including livelihood restoration. Prior to disbursement of compensation and commencement of livelihood restoration measures, each eligible PAP will sign a compensation certificate which sets out the mutual commitments for each party. The format of the certificates will be easily understandable to the PAPs. This will be countersigned by GoCD Department of Lands and Surveys. This compensation plan includes commitments as follows:

- GoCD to pay the agreed compensation prior to the commencement of project construction and land clearance;
- PAP to vacate the affected land including harvesting crops prior construction; and
- Both parties to abide by the requirements of the RAP.

Following agreement and signing of the certificates, compensation will be disbursed to the bank account of the owner of the property and resettlement and livelihood restoration activities will commence and the PAPs will be requested to vacate the site. The GoCD will be responsible for ensuring receipt of the financial compensation of the parties. Vacation of the site will be carried out by the PAPs and monitored by DGDC.

10.4 Resettlement Procedure

If applicable, once a suitable resettlement site has been identified, the Department of Lands and Survey shall formally survey the property and negotiate with the PAP and upon agreement submit request for permission for its transfer. The Department of Lands and Surveys is only able to accommodate resettlement for properties/lands owned by the State. There is no provision for acquiring private property for transfer. This process includes commitments as follows:

- GoCD to transfer the property to the PAP prior to the commencement of project construction and land clearance, purchase, certification and transfer;

- PAP to vacate the affected parcel including harvesting crops prior construction; and
- Both parties to abide by the requirements of the RAP.

10.5 Livelihood Restoration and Enhancement Measures

DGDC will support with the coordination of any transport or livelihood restoration support measures required by the PAPs during the physical relocation process. Resources of the GoCD will be utilised as required to support this process. Careful monitoring and evaluation will be required to manage the risk of unnecessary hardship, and to confirm that the various assistance activities are working as intended. The monitoring process is described in further detail in Section 12 of this document.

11. GRIEVANCE MANAGEMENT

11.1 Overview

The Dominica Geothermal Development Company (DGDC) is committed to ensuring compliance with the Environmental and Social Management Plans (ESMP) policies and procedures.

The Project is committed to maintaining lasting, transparent, culturally appropriate and efficient relationships with its internal and external stakeholders, through communication and engagement measures that allow receiving, analyzing and solving any concern, doubt, question regarding the environmental and social performance of the Project in all of its activities. The External Grievance Mechanism is an instrument to guarantee transparency and commitment between the Project and the local population.

Based on the foregoing, the Project has developed an External Grievance Mechanism with the objective of identifying and managing the potential external nonconformities (e.g. from the affected communities) and/or complaints in a timely and effective manner.

This grievance mechanism is in place and has been communicated to the community and general population. It is published on DGDC's website (www.geodominica.dm) and allows for grievances to be submitted online and anonymously.

11.1.1 Objective

Establish an External Grievance Mechanism so that the Project can handle external complaints, presented by stakeholders outside the Project (e.g. affected communities, external stakeholders, interested groups, etc.), during the development of its projects by giving them an adequate response, generating satisfactory agreements and implementing compensatory and corrective actions, when necessary.

By establishing an effective External Grievance Mechanism, DGDC will be able to manage potential conflicts of interest by segregating the roles and responsibilities of individuals involved in the concern, suggestion or grievance management process and avoiding placing individuals in a position where conflicts could be perceived to arise. The Project recognizes that unforeseen impacts may occur, and that the maintenance of an open line of communication with the communities and/or those potentially affected by the Project is important to maintain transparent and cordial relations. In addition, international standards require the establishment of an External Grievance Mechanism in order to address the interested parties' concerns.

As a general policy, DGDC will work proactively towards preventing grievances through the implementation of mitigation measures (as identified by the ESIA) and liaising with the community. These activities are designed to anticipate and address potential issues before they become grievances. This will be the responsibility of the Project Manager and the Community Liaison Officer (CLO).

The sections below consider types of grievances that may arise, confidentiality and anonymity, and the Project's grievance resolution process.

The grievance mechanism covers the various aspects of the Project, including:

- The Project in general, including planning, construction and operation;
- The process of environmental impact assessment; and
- The compensation and resettlement processes.

Each affected person is free to register a grievance, in accordance with procedures specified below. The grievance process focuses on first identifying whether the grievance can be addressed through additional

communication between the complainant and members of the Project Team, or by providing additional information to the complainant. If the grievance cannot be resolved internally, the Project Team will then seek to resolve the grievance through mediation by local authorities, and finally, if a resolution cannot be reached, judicial appeal. The procedure does not replace the public mechanisms of resolution of conflicts in Dominica's legal system but covers the legal process in the Grievance Mechanism to minimize the management of grievances and escalation to the judicial system.

11.1.2 Scope of Application

This plan will apply during the development of DGDC's activities and during the Project's life cycle. It is DGDC's responsibility to ensure that reception complaints are aligned to international best practices.

11.1.3 Definitions

The main terms used in this document are defined below:

Table 11-1: Terms and Definitions

Term	Definition
Claim	Concern, suggestion, complaint, or grievance raised by an individual or group of individuals that need to be addressed.
Claimant	Person or group of people communicating a claim to DGDC.
Concern	Requests for information or general negative perceptions unrelated to a specific Project impact or incident. If not addressed to the satisfaction of the claimant, concerns may become claims.
Conflict of interest	A conflict of interest exists where there is a divergence between the interests of an employee or contractor and his or her responsibilities or capabilities under this directive, such that an independent observer might reasonably question whether the actions of that person are influenced by his or her own interests.
Contractor	An individual or a company that has entered into a contract to provide goods or services to DGDC. The term covers parties directly contracted by DGDC and those contracted by a Contractor company, also referred to as subcontractors.
Grievance	A an actual or perceived problem raised by an individual or group of individuals that that might give grounds for complaint and needs to be addressed. Claims can result from either real or perceived impacts of DGDC's operations. The terms "claim" and "grievance" can be used interchangeably.
Suggestion	Proposal, insinuation, or indication that is submitted with the aim of proposing an action to improve DGDC's internal processes.
Retaliation	Any adverse action taken against a Claimant, employee, or contractor whose purpose is to frustrate the operation of this directive.
External Grievance Mechanism	A procedure through which a grievance can be raised by a member of the community, assessed, investigated and responded to. It is also a framework through which workers can gain access to remedy for any adverse impacts or damage they have suffered as a result of business activities.

11.2 Roles and Responsibilities

In order to properly implement the External Grievance Mechanism, DGDC requires the involvement of the people listed below.

Table 11-2: Roles and Responsibilities

Role	Responsibilities
Board of Directors	<ul style="list-style-type: none"> Review and approve the External Grievance Mechanism.
Finance & HR Manager	<ul style="list-style-type: none"> Ensure the availability of resources necessary for the implementation of the External Grievance Mechanism.
Safeguards Manager	<ul style="list-style-type: none"> Ensure the correct implementation of the External Grievance Mechanism.
Representative of DGDC's Legal Area	<ul style="list-style-type: none"> Evaluate and determine the origin of the complaints received and define the measures to be taken in response, as suitable according to what is stated in this plan.
Managing Director	<ul style="list-style-type: none"> Be familiarized with the External Grievance Mechanism and provide the necessary resources to ensure its proper implementation.
Safeguards Manager	<ul style="list-style-type: none"> Ensure the correct implementation of the External Grievance Mechanism. Review and approve the contractor project-specific External Grievance Mechanism. Update the External Grievance Mechanism.
Grievance Mechanism Team	<ul style="list-style-type: none"> Be familiarized and disseminate the External Grievance Mechanism among external stakeholders. Prepare the Communication Report, and follow up on the feedback received. Share the External Grievance Mechanism Database with the Managing Director. Share the received feedback with the Project Manager.
Community Liaison Officer (CLO)	<ul style="list-style-type: none"> Collect on a weekly basis the complaints presented, whether submitted physically or via website. Review the nature of the complaint, as well as the company's departments potentially involved. Solve, as immediate as possible the feedback received, if there are conditions to do so. Keep a record of the solutions that were given for documentation, monitoring or verification of the solution applied.
Employees, contractors and subcontractors	<ul style="list-style-type: none"> Read and be familiarized with the External Grievance Mechanism.

Source: DGDC, 2020

11.3 Activities

The External Grievance Mechanism Plan establishes the guidelines for external stakeholders to submit complaints, grievances and concerns arising from any project's activities and operations, ensuring the accessibility and effectiveness of the process.

11.3.1 Principles

DGDC recognizes that this plan has to guarantee the same level of integrity and respect for all the people involved, as well as for any type of claim. To this regard, the Project's External Grievance Mechanism will be:

- **Understandable and reliable** (e.g. the affected stakeholders must understand the procedure, the confidentiality of the person filing the complaint must be protected, the expected deadline for receiving a response must be shared);
- **Culturally appropriated and accessible** (e.g. complaints can be filed in the local language, the technology required to file a complaint must be of common use, illiterate people can file complaints verbally);
- **Free of charge** (e.g. raising a complaint will not have any cost);
- **Anonymity** (e.g. the claimant will have the option to remain anonymous);
- **Proportional** (e.g. to provide the appropriate level of management to address the grievance promptly);
- **Rights-Compatible** (e.g. outcomes and remedies will be in line with internationally recognized human rights legislation and national law. No aspect of the mechanism will prevent community members from enforcing their legal rights. Community members will be protected against retaliation for having raised complaints);
- **Inclusive and non-discriminatory** (e.g. all grievances, from all community members regardless of age, ethnicity, mental or physical disability, race, religion, gender, sexual orientation or gender identity, will be accepted, reviewed and solved as needed);
- **Transparent** (e.g. every complaint will be treated seriously, and dealt with consistently and in an impartial, confidential and transparent manner. The process is transparent and provides timely feedback to the claimant).

The present plan establishes the guidelines of the External Grievance Mechanism and describes how the Project along with its CLO will proceed in order to adequately and satisfactorily address the possible complaints expressed by the community or other external stakeholders. Complaints related to internal stakeholders (e.g. workers, contractors, subcontractors, etc.) are covered on the Internal Grievance Mechanism Management Plan.

The External Grievance Mechanism aims to prevent social contingencies and conflicts with the people that might be affected by the development of the Project, since it will provide, at all times, effective attention, and it has the obligation to respond to the requests of all claimants.

DGDC has established a process for the reception, registration, review, analysis, resolution and evaluation of complaints, claims and concerns to be implemented in all of its projects. The process will be documented through a physical record file and will end with the closure and written agreement on the resolution of both parties (i.e. the claimant and the Project).

11.3.2 Publication of the Mechanism


Based on the Stakeholder Engagement Plan, the Safeguards Manager and CLO will inform the affected communities and other external stakeholders about the Grievance Mechanism and the communication channels to submit complaints, claims or suggestions regarding any activities related to the Project, as well as how and where to submit them. This information will be shared through:

- Direct dialogue;

- Distribution of printed material such as brochures and posters, which will be proposed by the ESG team and reviewed by the Marketing and Communication management of DGDC;
- Available information at the Community Centre;
- Press and media; and
- Didactic educational tools (e.g. games, videos, books, etc.).

11.3.3 Grievance Mechanism Procedure

In order to ensure the proper implementation of the External Grievance Mechanism, and the resolution of the feedback received, this mechanism is divided into four main steps. These steps are presented in the figure below.



Source: ERM, 2020

Figure 11-1: General Grievance Mechanism Procedure

These steps are designed based on the recommendations of the International Finance Corporation (IFC), through which a communication channel and responsible for monitoring in each of them is designated.

11.3.3.1 Reception and Registration

The CLO will manage the External Grievance Mechanism. The external claimants will be able to submit their grievances through the following reception channels:

- Website – www.geodominica.dm

Telephone and emails. The points of contact for grievances and comments are:

Name:	Allan Toussaint
Address:	Floors 1&2, 18 Kennedy Avenue, Roseau
Email:	Allan.toussaint@geodominica.com
Telephone Number:	(767) 448 6178/79; 275 7392

Name:	Lyn Fontenelle
Address:	Floors 1&2, 18 Kennedy Avenue, Roseau
Email:	Lyn.fontenelle@geodominica.com
Telephone Number:	(767) 448 6178/79; 235 5462

- A Grievances Mailbox placed at the Community Centre. The mailbox's precise location will be shared with the community during public consultation and other disclosure of information events.

Any complaint or suggestion that is entered by the aforementioned means must follow the External GM form which shall contain the following information:

- Place and date of the complaint or suggestion;
- Reason for the feedback, with details of the events;
- Claimant's contact information (In case the grievance is not anonymous); and
- Claimant's proposed solution to the issue.

The process will begin with the receipt of a complaint or suggestion by the CLO and notify the claimant that the claim has been received, will be reviewed and taken for analysis. DGDC's grievance flow chart is provided in the figure below.




Figure 11-2: DGDC’s Grievance Flow Chart

Once the suggestions and/or complaints have been received, the CLO will complete the Communication Report and the information collected regarding the complaint and/or suggestion will be captured in the External GM Database to register the complaints and/or suggestions.

If the claim is readily resolvable (e.g., a request that can be immediately granted or an easy solution can be applied without an investigation process), the person from the CLO receiving the claim takes action to address the issue directly and records the details in the External GM Database. If the claim subject is considered sensitive by the claimant (e.g., in cases regarding abuse, sexual harassment, or other forms of gender-based violence), a special point of contact with adequate training will be provided. The claimant will have the option to talk to a point person of their same gender, if requested.

Claims will not be applicable in cases when:

1. It is not directly related to DGDC, its contractors, or subcontractors;
2. It is out of DGDC's influence;
3. Its nature exceeds the scope of the present External Grievance Mechanism;
4. The claimant has no standing to file; and/or
5. There are other formal mechanisms/institutions or community procedures more appropriate to address the issue.

When the claim is classified as non-applicable following the above criteria, DGDC will clearly communicate the reasons why it cannot be considered to the claimant, and when possible, DGDC will provide information to help them redirect their claim to the right institution or party.

The External Grievance Database is updated weekly to reflect the current state of the claim until the claim has been resolved according to the claimant. Reception of the claim will be acknowledged within ten (10) days after the claim is received. If an investigation is needed, this will take up to 30 days (low risk claims), up to 15 days (medium risk claims) and 5 days (high risk claims).

The Project will provide a means by which all external stakeholders will be able to raise anonymous complaints. This gives the most vulnerable members of the affected communities, the confidence that they will not be retaliated against for raising concerns and can be fundamental to shifting power dynamics in between the Project and the communities. Therefore, in case of an anonymous case, the resolution will be published on a visible and accessible notice board at the Community Center.

11.3.3.2 *Review, Analysis and Investigation*

Once the complaints have been filed, the review, analysis and investigation process will unfold as follows:

1. The CLO will collect on a weekly basis the complaints presented, whether submitted physically or via website, and will review the nature of the complaint, as well as the company's departments potentially involved;
2. The CLO will make an initial assessment of severity in coordination with the H&S Manager, if necessary. The grievances will be classified in four categories:

Table 11-3: Classification of Grievances

Classification	Risk Level	Validity	Response
Non-Admissible	None	Unsubstantiated	CLO will clearly communicate the reasons why it cannot be considered to the claimant, and when possible, provide information to help them redirect their claim to the right institution or party.
Low	No or low	Unsubstantiated	CLO will conduct investigation, document findings and provide a response

Classification	Risk Level	Validity	Response
Medium	Possible risk and likely a one-off event	Possible substantiation	CLO and an appropriate investigation team will conduct investigation. The Site Manager or Occupation Health and Safety Manager may decide to stop work during the investigation to allow the corrective preventive actions to be determined. The CLO will provide a response.
High	Probable risk and could reoccur	Probable substantiation	CLO will get the contractor to organise a Major Investigation Team including DGDC and GoCD for prompt investigation and resolution. Work will be stopped in the affected area. The CLO will provide a response.

- a. **Non-Admissible** (e.g. claims that are not directly related to the Project, its contractors or subcontractors, out of DGDC's influence);
 - b. **Low Risk** (e.g. claims that do not require resolution per se, but instead only require information or a certain clarification to be provided to the claimant. If there are recurring complaints that have been previously received and addressed by the Project, DGDC will reconsider elevating the importance of the complaint, as this might be a sign that the response to the grievance has been insufficient or inadequate);
 - c. **Medium Risk** (e.g. claims that require resolution and are related to minor risks associated with health, the environment, construction, transportation, and external stakeholders. Although important, they do not pose an immediate risk); and
 - d. **High Risk** (e.g. claims related to the security and safety of the community stakeholders, as well as those that, according to criteria of the Community Relations team, require immediate response as the claim poses an immediate major health and safety risk or a risk to an individual, to a large or small group or several groups of stakeholders. This includes claims regarding illegal and abusive activities).
3. The CLO will prepare the Communication Report that includes the information listed below:
- a. Internal tracking folio number provided to the claimant;
 - b. Type of feedback,
 - c. Area potentially involved;
 - d. Claimant's information (In case the grievance is not anonymous);
 - e. Date the complaint or suggestion was originated;
 - f. Grievance Risk Category (Low, Medium or High);
 - g. Brief description of the complaint or suggestion;
 - h. Area responsible for monitoring and solution;
 - i. Recommended solution; and
 - j. Term of resolution.

Once the claim has been reviewed, the investigation must be carried out in the first instance by the CLO. In case the feedback transcends and involves more areas of the Project, the suggestions and/or complaints will also be channeled to the Project Manager and the HR Manager, as appropriate, to coordinate resolution with the departments involved, depending on the scope of each, and to determine the actions to follow.

Regardless of the categorization of the claim, the claimant must always be informed that her or his grievance has been received and it is being investigated. The answer must be given in written and/or verbal form, in a clear and precise language, preferably respecting the claimant's language. In cases where the complaint is anonymous, the response will be published at the Project's Community Relations Office/Community Centre. The deadline for the resolution of a complaint or claim is according to the categories as presented in the table above.

In high-risk situations, where there is a possibility of serious danger (e.g., death, sexual harassment), DGDC will consider involving other member teams to weigh in on the resolution strategy. In these type of cases, an alternative timeline will be established for addressing and involving third parties as needed, such as police and hospitals. The Project will always protect the confidentiality of the claimant. The special procedure for High Risk Claims is described below.

1. The claim enters an expedited process for investigation and resolution by the CLO and if applicable, the Major Investigation Team, when appropriate.
2. The Major Investigation Team initiates the investigation immediately and coordinates with local authorities to appropriately address the matter for claims related to allegations of illegal or abusive acts.
3. The CLO meets the claimant to gather additional information as necessary. Subsequently, he or she investigates the claim (e.g., meets with members of the security team involved in the claim), develops, and implements corrective actions in collaboration with other project staff, as necessary.
4. If both the CLO and other staff involved in the resolution of the claim are all the same gender, and the claimant prefers to speak to a person of his or her same gender, DGDC will facilitate this request. This option will be disseminated when disclosing the procedure. If additional investigations are needed, these are promptly undertaken.

The CLO will log the receipt of a comment, formally acknowledge it, track progress on its investigation and resolution, and respond in writing with feedback to the aggrieved party. They will initiate the investigation and ensure its speedy conclusion aiming to provide a response with ten (10) working days, unless there are exceptional circumstances. If the Project receives a large number of unsubstantiated grievances, the process will be reviewed to define instances when no response is needed.

If the person responsible of the claim is not able to obtain a resolution within 10 days of the reception of the claim, he or she submits the claim to the CLO, who notifies and seeks advice from the H&S Manager.

Where investigations are required, Project staff and outside authorities as appropriate will assist with the process. The CLO will collaborate with GoCD to identify an appropriate investigation team with the correct skills to review the issue raised and to decide whether it is Project related or whether it is more appropriately addressed by a relevant authority outside the Project.

The investigation will also aim to identify whether the incident leading to the grievance is a singular occurrence or likely to reoccur. Identifying and implementing activities, procedures, equipment and training to address and prevent reoccurrence will be part of the investigation activities. In some cases, it will be appropriate for the CLO to follow up at a later date to see if the person or organization is satisfied with the resolution or remedial actions.

Before the final resolution is issued, the agreed resolution will be reviewed by the claimant, or his or her worker representative, and will confirm his or her agreement with the solution proposed.

11.3.3.3 *Resolution*

Once the complaints have been categorized and reviewed, the resolution and closure process will unfold as follows:

1. The first step for the resolution is the determination of the timeframe and its inclusion in the registration file previously elaborated.
2. The claim will be discussed by the CLO, and if necessary, the managers of the areas involved. In the case of complaints related to allegations of illegal or abusive acts, the Project will immediately initiate the investigation to adequately address the matter. Based on the investigation, the complaint may or may not proceed.
3. Depending on the risk category, the approach will be defined. The CLO, together with a representative of the Legal Area will evaluate and determine the origin of the complaint and define the measures to be taken in response. All responses must be signed by the ESG Manager before being communicated to the employee and/or interested parties.
4. If the complaint is not admissible, the claimant will be notified.
5. The CLO and the Managing Director will have performed an analysis of all the viable resolutions, seeking to, at all times, provide solutions that respond to the claimant, from a position of dialogue and respect. A complaint will be dismissed only when all the instances of solution have been exhausted, explaining in writing to the claimant, in a clear and indubitable manner, the reasons for the refusal on the resolution of the complaint.
6. All documentation issued during the process by the company to interested parties must be sent by email or written notification. In any case, the answer must have the corresponding record (the folio of complaint or suggestion) and will be properly archived as part of the process.

11.3.3.4 *Right to Appeal*

If an external stakeholder who is not satisfied with the procedure or resolution, she or he can contest DGDC's decision. The claimant will have a maximum period of fifteen (15) business days to express any disagreement with the response and appeal it. Once the deadline has elapsed and there are no new grounds for complaint, the process will be considered closed.

In the event that a claimant wishes to challenge/appeal DGDC's decision or propose a counter offer, the Board of Directors will decide whether DGDC can resolve the dispute or it is necessary to involve a third party (e.g. a mediator, technical expert, local authority, or ombudsman) to reach an agreement between the parties and resolve the dispute. The claimant will always have the right to seek other legal or administrative resources. The last resort will be the national judicial process.

When a resolution agreement is established, both parties, the Head of Safeguards acting as the representative of DGDC and the claimant, will sign it in writing. Once the solution is implemented, both parties in recognition of compliance with the agreement will sign a compliance agreement again.

11.3.3.5 *Evaluation and Follow Up*

It is the responsibility of the CLO to follow up on all responses to suggestions and/or complaints in written and/or verbal form, especially those of medium and high priority, so as to confirm that the response given to the interest group was adequate, given the circumstances and criteria applicable at the time of filing the complaint. The External GM Database is used to follow up each claim until it is resolved and closed. Both a grievance and commitments register is kept by DGDC.

11.4 Confidentiality and Protection from Retaliation

The Project is committed to protecting the identity of claimants and anyone else involved in the claim, and to handling personal information in accordance with legal requirements. This duty extends to all employees and representatives of DGDC, its contractors and community members who participate in the External Grievance Mechanism process.

Information about a claim is shared within the company on a need-to-know basis and only to the extent necessary to complete the steps in this directive. DGDC will not share personal information with third parties unless required by law or authorized by the claimant.

When a claim relates to a specific DGDC or contractor employee, that person cannot play a role in the External Grievance Mechanism process in order to prevent conflicts of interest.

DGDC does not tolerate retaliation against claimants, be they an employee, contractor or external stakeholder. When concerns about retaliation are raised, Human Resources/ CLO is responsible for leading an investigation into the alleged retaliation under DGDC's Human Resources Policy and Code of Conduct.

11.5 Documentation and Monitoring

Weekly during construction and bi-annually during operation, the CLO will send the External GM Database to the Project Manager with information on the feedback received through a consolidated report showing the status of each claim and its indicators, removing identification information to protect the confidentiality of the complainant and guaranteeing anonymity.

This plan will be monitored continuously and is designed to facilitate the integration of lessons learned during its execution. The Project will be able to respond adequately to situations as soon as they develop.

The External Grievance Mechanism Plan will be reviewed annually, however, if required, the mechanism could be updated as necessary. It will also ensure that contractors update their procedures at least once a year.

11.6 Key Performance Indicators

The table below present the key performance indicators that will evaluate the implementation of this plan:

Table 11-4: Key Performance Indicators

Impact	Indicator	Performance Goals/ KPIs	Method/Tool/ Frequency
GM attainment	DGDC will review the External Grievance Database, including complaints closed and those unresolved. Number of grievances received per month versus number of grievances resolved.	100% of grievances resolved in a timely manner	External Grievance Mechanism Database and Community Relations Team / Quarterly
GM time efficiency	DGDC will review the External Grievance Database, especially the number of days between the grievances submission until its resolution and closure to calculate the average length of time needed to resolve grievances.	Max. 10 days	External Grievance Mechanism Database and Community Relations Team / Quarterly

Impact	Indicator	Performance Goals/ KPIs	Method/Tool/ Frequency
GM Focus/ Risk Areas	DGDC will review the External Grievance Database and if necessary talk to the Community Relations Team to breakdown the grievances topics (e.g. health, safety, etc.) and grievance source	Resolve 100% of grievances from all sources and about all topics. Disseminate information regarding the different solutions when there are recurrent complaints in order to decrease recurrent grievances.	External Grievance Mechanism Database and Community Relations Team / Quarterly
Method of grievance reporting	DGDC will review the External Grievance Database and engage with community members to check the use and success of the different grievance reporting methods (e.g., number of grievances received by phone, at the office, website, and boxes).	100% of reporting methods will be functional and accessible at all times.	Community Relations Team / Quarterly
GM dissemination	DGDC will monitor all GM informational documents, meetings, and events where the GM was disclosed and explained to the affected communities.	GM dissemination of information in at least 70% of disclosure of information events, consultations and other activities.	Community Relations Team Records / Quarterly

12. MONITORING AND EVALUATION

12.1 Monitoring Objectives

Monitoring and evaluation are essential components of the RAP process. The objective is to provide feedback and to identify problems and successes as early as possible to allow for timely adjustment to implementation arrangements as needed. Monitoring and evaluation activities need to be integrated into the overall Project management process and a comprehensive monitoring plan that identifies the organizational responsibilities, methodology, and the schedule for monitoring and reporting must be developed for the RAP. For a full list of monitoring and evaluation objectives, see Appendix C.

The monitoring and evaluation process includes the following objectives:

- Monitoring of specific situations or difficulties arising from the implementation of the RAP or compliance with its objectives; and
- Evaluation of the mid- and long-term impacts of the RAP on affected households' livelihood, environment, local capacities, on economic development and settlement.

Monitoring aims to correct implementation methods during the course of the Project, as required, while evaluation is intended at checking whether policies have been complied with and provides lessons learnt for amending strategies from a longer-term

12.2 Monitoring Indicators

Monitoring will address the following aspects:

- Socioeconomic monitoring: follow-up of the welfare/status of the PAPs including regular survey of current income and cost of living, re-establishment of property, residence and livelihoods and other economic activities;
- Grievances and grievance management system including any issues to be resolved; and
- Assistance in livelihood restoration including any unforeseen costs/challenges such as transport or other costs.

The monitoring and evaluation measures put in place are designed to ensure that the implementation of the RAP is carried out in accordance with the relevant requirements of the WBG, IDB, CDB and IFC as well as national requirements.

Measuring progress and impacts related to the aspects described above would be based on the following indicators:

- Livelihoods would be measured through a quantitative income or expenditure survey;
- Use of capital will be reviewed via interviews and receipts to determine livelihood sustainability; and
- Qualitative indicators measuring perception and well-being of PAPs.

12.3 Monitoring Process

The DGDC Safeguards Specialist will undertake monitoring of the RAP implementation. Bi-monthly progress reports will be prepared for up to two years. The monitoring will consider the timeline of the process, outcomes of compensation/livelihood restoration and any other impacts that occur as part of the process. The RAP implementation schedule is shown in Table 12-1.

Table 12-1: RAP Implementation Schedule

TASKS	Month 1	Month 2	Month 3	Month 4	Month 5	Month 6	Month 7	Month 8
Completion of RAP								
Approval of RAP/Community Consultation								
Implementation of RAP								
Payment of Compensation to PAPs								
DGDC Site Clearance								
Grievance Mechanisms and Procedures Implemented								
Construction Begins								
Performance Monitoring								
External Evaluations (up to two years)								

Monitoring will continue for up to two years and will focus on ensuring that the PAPs are not subject to undue hardship during the transition given that they are all considered to be vulnerable.

12.4 Evaluation Objectives

Evaluation is a key step to ensure that the RAP process is being completed in line with WBG / IFC policies. The evaluation of the RAP will have the following specific objectives:

- Assessment of the compliance of the implementation of resettlement, relocation and livelihood restoration activities with objectives and methods as set out in this RAP;
- Assessment of the compliance of the implementation of the RAP process with laws, regulations and safeguard policies as stated above;
- Assessment of compensation procedures as they have been implemented;
- Evaluation of the impact of the resettlement, relocation and livelihood restoration process on incomes and standard of living, with focus on the requirement that PAPs income are restored or improved; and
- Identification of actions to take to improve the positive impacts of the programme and mitigate its possible negative impacts, if any.

12.5 Evaluation Process

DGDC will use an independent consultant (Evaluator) to conduct an annual evaluation starting six months after implementation of the RAP to evaluate compliance with objectives, procedures, policies, laws and regulations. The Evaluator will be an independent consultant with experience in the conduct of resettlement and livelihood restoration planning. The Evaluator will be carefully chosen on the basis of

hands on experience, no previous involvement in the Project, and proven ability to identify actions that improve implementation and mitigate negative impacts of economic displacement.

The RAP implementation will be evaluated against a number of key performance criteria, which will be identified by the Evaluator and DGDC based on consultation conducted to date with the community. These criteria will likely include access to employment, income, food security livelihood restoration and enterprise, and health and nutrition. The grievance management system will also be evaluated for its effectiveness. This evaluation will also verify that compensation payments have been made as promised, have been properly processed, and recommendations are being implemented. The schedule for independent evaluation of RAP implementation is six months following completion of RAP implementation. The evaluation will be repeated each year for 2 years.

13. BUDGET AND SCHEDULE

It is essential that all costs be estimated carefully and included in the detailed RAP budget. DGDC have itemized resettlement costs by categories of impact, additional entitlements and other resettlement expenditures including training, coordination, and monitoring. The results are presented in a tabular form below that illustrates expenditures over the life of the Project. Costs included are:

- Resettlement plan preparation consultancy;
- Cash compensation for land;
- Cash compensation for crops, trees, or livestock;
- Compensation for structures;
- Livelihood restoration measure costs;
- Conflict resolution; and
- Monitoring, evaluation and auditing costs.

The estimated RAP budget is presented in Table 13-1. These costs are indicative and consultant fees will need to be verified.

Table 13-1: Estimated RAP Budget

ITEM	Description	COST USD*
1	Land Acquisition Compensation	662,811
2	Structural Compensation	47,295
3	Tree/Crop Compensation	27511
4	Vulnerable Assistance (1 year)	10,000 ⁹
Sub-total		747,617
5	Program Development, Management and Grievances	2,000
6	Community Consultation and Engagement	4,000
8	External Evaluation	10,000 (2 years)
Sub-total		16,000
TOTAL		763,617

*USD Conversion Rates based upon exchange rate of 1 ECD = 0.37 USD as of December 2020

⁹ Estimated as some vulnerable owners wouldn't declare income.

14. REFERENCES

- Commonwealth of Dominica, Land Acquisition Act Chapter 53:02
- Eclipse Inc (2020). DRAFT Environmental and Social Impact Assessment – Construction and Operation of geothermal reinjection well RVI2 and of pipeline
- International Finance Corporation (2007). Environmental, Health, and Safety General Guidelines.
- International Finance Corporation (2008). Environmental, Health and Safety Guidelines for Thermal Power Plant.
- International Finance Corporation (2012). Performance Standards on Environmental and Social Sustainability.
- NPC (2011). Macroeconomic Impacts of the Domestic Oil & Gas Industry, September 15, 2011 (PWC multipliers used).
- World Bank Group (2001) Involuntary Resettlement Policy Operational Policy (OP) 4.12
- World Bank Group (2006). Physical Cultural Resources Operational Policy (OP) 4.11
- Central Intelligence Agency World Factbook Website (2017). [Accessed at <https://www.cia.gov/library/publications/the-world-factbook/geos/do.html> in April 2018]
- Post Disaster Needs Assessment Hurricane Maria, September 18 2017, Government of the Commonwealth of Dominica.

APPENDIX A ASSETS INVENTORY – PHYSICAL STRUCTURES



Figure A-1: Potential Residential Structure (currently Goat/Sheep Shed) A1



Figure A-2: Rabbit Hutch Structure A2



Figure A-3: Residential Structure B1




Figure A-4: Residential Structure Incomplete C3



Figure A-5: Shed C3

APPENDIX B BASIS OF VALUATION

Lands

Lands are valued at replacement cost by the Property Valuations Unit (PVU) of the Department of Lands & Surveys using the following approach:

Market Value + transactions cost

Market Value is defined as 'the estimated amount for which an asset or liability should exchange on the valuation date between a willing buyer and a willing seller in an arm's length transaction after property marketing and where the parties had each acted knowledgeably, prudently and without compulsion'.

- Each property is seen as unique;
- Inspection of each property is done and evaluated using the following factors:
 - Services;
 - Access;
 - Topography;
 - Land use;
 - Market (supply & demand); and
 - Size.

Transaction Cost include all fees and costs associated with the transaction. These include:

- Assurance Fund – 1%
- Judicial Fee – 2^{1/2} %
- Stamp Duty – 4%
- Solicitor's Fees – 3%
- Vendor's Fees – 3%

In instances where properties are acquired by the Government, provision is made in the Land Acquisition Surveyors fees and other costs incurred are also paid.

Structures

The valuation of structures is driven by the market. Given that underdeveloped nature of market forces in Dominica, the PVU uses a 'cost of construction' approach. A full inspection of the structure is done by experienced officers of the unit and the following factors taken into account:

- Age of structure;
- Quality of finishing; and
- Type of structure i.e. intended use and materials used in construction.

Present rates used by the PVU range from EC\$250-\$275 per square foot. Straight line depreciation (age of building/anticipated life) is applied.

Crops

Crop valuation is done by officers of the Extension Unit of the Ministry of Agriculture using a combination of the following:

- Cost of Production of a crop;
- Selling price at time of valuation; and
- Bearing Capacity.

Therefore:

- Cost of Production

An assessment is done to ascertain what stage in the production cycle the affected crops are at and known costs are apportioned based on field size and location. Activities include land clearing, ploughing and hoeing, planting, weed control & fertilising, pest and disease management, transportation, harvesting, and marketing. This method is best employed when farm records exist.

- Selling Price at time of valuation

Where insufficient records exist, crops are valued at a reasonable/average selling price of the finished product at the time of valuation.

- Bearing Capacity

In addition to costs of production, the valuation considers the number of years/cycles for which the farmer could have reasonably expected to gain returns from the current crop. This method is also used for the valuation of livestock.

APPENDIX C COMPLETION AUDIT TABLE OF CONTENTS

1. Executive Summary: Concise summary of resettlement undertaken to date, need for any on-going resettlement, magnitude of displacement, activities undertaken, grievances and key issues addressed, outstanding and on-going monitoring and evaluation processes and key recommendations.
2. Background: A brief description of the monitoring process to date covering the project and impacted communities, magnitude of displacement, key resettlement and livelihood impacts, legal framework, eligibility criteria and entitlement framework, timing of the various components of physical and economic displacement undertaken, resettlement and/or livelihood restoration activities and compensation provided and major or outstanding issues or grievances.
3. Review Objectives: Outline of the main objectives of the resettlement and/or livelihood restoration plan and a summary of studies and activities undertaken in support of resettlement implementation and livelihood restoration (e.g., preliminary and on-going consultation, stakeholder mapping and census surveys, asset surveys, socio-economic baseline studies, participatory planning meetings, site selection studies, organizational structures for implementation), and assessment of the process and evaluation of the outcome (including any participatory monitoring and evaluation methodologies used).
4. Key Findings: Issues to be considered may include, among others:
 - a. Extent of public information and consultation in advance of land acquisition, and adequacy of ongoing consultation;
 - b. Types of compensation provided and adequacy of that compensation (e.g., sufficient to cover replacement costs of lost assets, housing conditions, compensation/entitlements, income restoration and livelihood sustainability measures);
 - c. Level of participation of affected people in decisions regarding compensation rates, location of new resettlement sites and options for livelihood restoration;
 - d. Adequacy of replacement housing in terms of physical structure, location, and access to resources and services (such as health, education, water and sanitation, transportation, social and medical security, agricultural and pastoral land, employment opportunities and training and community development initiatives);
 - e. Effectiveness of livelihood restoration measures;
 - f. Integration into host communities;
 - g. Impact on cultural property;
 - h. Measures taken to protect (affected) vulnerable persons and groups;
 - i. Adequacy of the grievance redress process and outcomes; and
 - j. Monitoring and evaluation process and outcomes.
5. Conclusion and Key Recommendations/Corrective Actions: Concise summary of conclusions and recommendations, and for any gaps or outstanding issues, provide a proposed time bound Corrective Action Plan with Key Actions, dedicated Human Resources, proposed Timeline for closeout and a Budget.